
USACE / NAVFAC / AFCEC / NASA UFGS-10 22 26.23 (August 2016)
Change 2 - 08/20

Preparing Activity: NAVFAC Superseding
UFGS-10 22 26.23 (August 2010)

UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UMRL dated July 2020

SECTION TABLE OF CONTENTS

DIVISION 10 - SPECIALTIES

SECTION 10 22 26.23

COILING PARTITIONS

08/16

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 PRE-INSTALLATION REQUIREMENTS
 - 1.3.1 Preconstruction Requirements
 - 1.3.2 Product Data
 - 1.3.3 Manufacturer's Guarantee
- 1.4 DELIVERY, HANDLING AND STORAGE

PART 2 PRODUCTS

- 2.1 COILING PARTITIONS
- 2.2 MATERIALS
 - 2.2.1 Aluminum Extrusions
 - 2.2.2 Steel Sheets
 - 2.2.3 Fabric Covering
 - 2.2.4 Seals and Sweepstrips
 - 2.2.5 Ceiling Guards
- 2.3 PERFORMANCE REQUIREMENTS
 - 2.3.1 Fire Endurance
 - 2.3.2 Laboratory Acoustical Requirements
- 2.4 ELECTRICAL OPERATORS
- 2.5 FABRICATION
 - 2.5.1 Framework
 - 2.5.2 Suspension System
 - 2.5.3 Covering
 - 2.5.4 Sound Insulation
 - 2.5.5 Air Release
 - 2.5.6 Seals
 - 2.5.7 Hardware
 - 2.5.8 Accessories

PART 3 EXECUTION

- 3.1 INSTALLATION
 - 3.1.1 Existing Work
 - 3.1.2 Electrical Operators
 - 3.1.3 Adjustment
- 3.2 FIELD TESTS
 - 3.2.1 Operational Test
 - 3.2.2 Visual Test
 - 3.2.3 Acoustical Test
- 3.3 CLEANING
- 3.4 SUPPORT SERVICE

-- End of Section Table of Contents --

USACE / NAVFAC / AFCEC / NASA UFGS-10 22 26.23 (August 2016)
Change 2 - 08/20

Preparing Activity: NAVFAC Superseding
UFGS-10 22 26.23 (August 2010)

UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UMRL dated July 2020

SECTION 10 22 26.23

COILING PARTITIONS
08/16

NOTE: This guide specification covers the requirements for coiling partitions, manually and/or electrically operated.

Coiling partitions are partitions with independent covers enclosing a dead-air space and separated by an internal mechanism operating laterally across the face of the opening to a coiled closed position.

Coiling partitions may be a sight barrier (noninsulated), or sound barrier (with sound liner), or both. Coiling partitions have fabric or metal panel covers which are joined to reflect a pantographic movement of the door surfaces when the door is either manually or electrically operated.

This section does not include folding or operable walls and partitions whose rigid panels are individually moved or hinged along their vertical edges to fold in serpentine fashion.

Associated work found in other sections includes:

Steel supporting members or hanger rods, [Section 05 50 13 MISCELLANEOUS METAL FABRICATIONS][Section 05 51 33 METAL LADDERS][Section 05 52 00 METAL RAILINGS][Section 05 51 00 METAL STAIRS].

Wood blocking, rough bucks, and headers, Section 06 10 00 ROUGH CARPENTRY.

Wood trim, wood or hardboard ceiling guard, or soffits, Section 06 20 00 FINISH CARPENTRY.

Lock cylinders, Section 08 71 00 DOOR HARDWARE.

Operator field connections to power sources and inner connection to control switches, Division 16, "Electrical."

Adhere to UFC 1-300-02 Unified Facilities Guide Specifications (UFGS) Format Standard when editing this guide specification or preparing new project specification sections. Edit this guide specification for project specific requirements by adding, deleting, or revising text. For bracketed items, choose applicable item(s) or insert appropriate information.

Remove information and requirements not required in respective project, whether or not brackets are present.

Comments, suggestions and recommended changes for this guide specification are welcome and should be submitted as a Criteria Change Request (CCR).

NOTE: The following information should be shown on the drawings:

1. Location, size, and coiling area of coiling partitions.
2. Direction of operation, header conditions indicating height, track anchorage, track channel, and jamb conditions.
3. Partition supporting structure. The structural support for the partition is not part of this section; it must be indicated and specified separately.
4. A schedule of partitions by type, sizes, and stack space and identified by mark number or letter
5. For electrically operated partitions, show power source and desired switch location.

PART 1 GENERAL

1.1 REFERENCES

NOTE: This paragraph is used to list the publications cited in the text of the guide specification. The publications are referred to in the text by basic designation only and listed in this paragraph by organization, designation, date, and title.

Use the Reference Wizard's Check Reference feature when you add a Reference Identifier (RID) outside of the Section's Reference Article to automatically place the reference in the Reference Article. Also use the Reference Wizard's Check Reference feature to update the issue dates.

References not used in the text will automatically be deleted from this section of the project specification when you choose to reconcile references in the publish print process.

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

- ASTM A653/A653M (2020) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
- ASTM B221 (2014) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
- ASTM B221M (2013) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric)
- ASTM C423 (2009a) Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method
- ASTM D751 (2006; R 2011) Coated Fabrics
- ASTM E84 (2020) Standard Test Method for Surface Burning Characteristics of Building Materials
- ASTM E90 (2009; R2016) Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements
- ASTM E336 (2020) Standard Test Method for Measurement of Airborne Sound Attenuation between Rooms in Buildings
- ASTM E413 (2016) Classification for Rating Sound Insulation
- ASTM E557 (2012; R 2020) Standard Guide for Architectural Design and Installation Practices for Sound Isolation between Spaces Separated by Operable Partitions

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

- CDPH SECTION 01350 (2010; Version 1.1) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

CHEMICAL FABRICS AND FILM ASSOCIATION (CFFA)

CFFA-W-101-D (2002) Quality Standard for Vinyl Coated Fabric Wallcovering

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70 (2020; ERTA 20-1 2020; ERTA 20-2 2020; TIA 20-1; TIA 20-2; TIA 20-3; TIA 20-4) National Electrical Code

NFPA 101 (2018; ERTA 18-1; ERTA 18-2; ERTA 18-3; ERTA 18-4; TIA 18-1; TIA 18-2; TIA 18-3; TIA 18-4) Life Safety Code

NFPA 286 (2019) Standard Methods of Fire Tests for Evaluating Contribution of Wall and Ceiling Interior Finish to Room Fire Growth

UNDERWRITERS LABORATORIES (UL)

UL 10B (2008; Reprint May 2020) Fire Tests of Door Assemblies

1.2 SUBMITTALS

NOTE: Review Submittal Description (SD) definitions in Section 01 33 00 SUBMITTAL PROCEDURES and edit the following list to reflect only the submittals required for the project.

The Guide Specification technical editors have designated those items that require Government approval, due to their complexity or criticality, with a "G." Generally, other submittal items can be reviewed by the Contractor's Quality Control System. Only add a "G" to an item, if the submittal is sufficiently important or complex in context of the project.

For submittals requiring Government approval on Army projects, a code of up to three characters within the submittal tags may be used following the "G" designation to indicate the approving authority. Codes for Army projects using the Resident Management System (RMS) are: "AE" for Architect-Engineer; "DO" for District Office (Engineering Division or other organization in the District Office); "AO" for Area Office; "RO" for Resident Office; and "PO" for Project Office. Codes following the "G" typically are not used for Navy, Air Force, and NASA projects.

The "S" following a submittal item indicates that the submittal is required for the Sustainability eNotebook to fulfill federally mandated sustainable requirements in accordance with Section 01 33 29

SUSTAINABILITY REPORTING. Locate the "S" submittal under the SD number that best describes the submittal item.

Choose the first bracketed item for Navy, Air Force and NASA projects, or choose the second bracketed item for Army projects.

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are [for Contractor Quality Control approval.][for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government.] Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Manufacturer's Qualifications; G[, [_____]]

Manufacturer's Sample Warranty

Statement of Code Compliance; G[, [_____]]

Statement of Standards Conformity; G[, [_____]]

Verification of Field Measurements; G[, [_____]]

[Existing Electrical Data

] SD-02 Shop Drawings

Submit Fabrication Drawings for coiling partitions consisting of fabrication and assembly details to be performed in the factory.

Submit Installation Drawings for the following items in accordance with paragraph INSTALLATION, of this section.

Coiling Partition Layouts; G[, [_____]]

Suspension System; G[, [_____]]

Finish Hardware; G[, [_____]]

Jamb Panels; G[, [_____]]

Accessories; G[, [_____]]

[Electrical Operators; G[, [_____]]

] Wiring diagrams; G[, [_____]]

] Submit drawings for the system that include dimensions and weight of stacked partition, layout of the work including stacking area, track and jamb fastening methods, seal details, and installation details.[Submit wiring diagram and installation details for electrical operator.]

SD-03 Product Data

Framework

Suspension System

Finish Hardware

Sound Seals and Sweepstrips

Covering

[Indoor Air Quality for Fabrics and Wallcoverings; S

] Ceiling Guard

Meeting Posts

Jamb Panels

Rolling Post

Pull-In Latch

[Electrical Operator

] Switches

] SD-04 Samples

Covering; G[, [_____]]

SD-06 Test Reports

Laboratory Acoustical Requirements

Acoustical Test

SD-10 Operation and Maintenance Data

Coiling Partitions, Data Package 1; G[, [_____]]

[Electrical Operators, Data Package 5; G[, [_____]]]

Submit in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

SD-11 Closeout Submittals

Manufacturer's Guarantee

1.3 PRE-INSTALLATION REQUIREMENTS

1.3.1 Preconstruction Requirements

No less than 30 calendar days prior to the scheduled commencement of installation of coiling partitions, submit the following to the Contracting Officer:

Manufacturer's Qualifications

Manufacturer's Sample Warranty

Statement of Code Compliance

Statement of Standards Conformity

Verification of Field Measurements and Existing Electrical Data

Fabrication Drawings and Installation Drawings

1.3.2 Product Data

Submit the following information for review:

Finish Hardware

Jamb Panels and Accessories

Sound Seals and Sweepstrips

Ceiling Guard

Meeting Posts

Rolling Post

Pull-In Latch

[Electrical Operator

Switches

]1.3.3 Manufacturer's Guarantee

Provide [Manufacturer's Guarantee](#) for partitions against defects in material and workmanship for a period of two years from date of installation. In addition, provide ten year guarantee for the pantographs, trolleys and tracks from date of acceptance for beneficial use.

1.4 DELIVERY, HANDLING AND STORAGE

Deliver materials to project site in manufacturer's original, unopened, and undamaged packages with labels legible and intact. Labels must indicate the manufacturer, brand name, size, finish, and placement location. Store coiling partitions and accessories in unopened packages in a manner that will prevent damage. Handle partition materials in accordance with manufacturer's instructions.

PART 2 PRODUCTS

2.1 COILING PARTITIONS

Provide full coiling type partitions, factory finished, supported from overhead track without floor guides, and complete with all hardware, track, and accessories necessary for operation. Provide partition

framework with a mechanism that gives stability and maintains uniform spacing of partition folds in all partition positions. Provide completely concealed framework with a [vinyl-coated fabric covering][_____]. Provide partitions [manually] [and] [electrically] operated, [bi-parting] [and] [one-way] type as indicated. Provide patterns and colors of [fabric][_____] [approved by the Contracting Officer] [as indicated].[Provide manufacturer's standard pendant pull on leading edge of manually operated partitions over 3600 mm 12 feet high.]

2.2 MATERIALS

2.2.1 Aluminum Extrusions

ASTM B221M ASTM B221, Alloy 3003.

2.2.2 Steel Sheets

ASTM A653/A653M, [Z 180G90 coating designation].

NOTE: If a fabric covering is required, include the following section.

[2.2.3 Fabric Covering

NOTE: Specify minimum total weight and minimum coating weight for the fabric covering type selected using the listing below:

Total Weight (kilograms per square meter): Type I - 0.237; Type II - 0.442; Type III - 0.748
Coating Weight (kilograms per square meter): Type I - 0.170; Type II - 0.237; Type III - 0.407
Total Weight (ounces per square yard): Type I - 7; Type II - 13; Type III - 22
Coating Weight (ounces per square yard): Type I - 5; Type II - 7; Type III - 12

CFFA-W-101-D, Type II. Fabrics and wallcoverings must meet emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type). Provide validation of indoor air quality for fabrics and wallcoverings.

]2.2.4 Seals and Sweepstrips

NOTE: Coiling partitions need a floor and ceiling seal to avoid gaps that will lower the advertised sound transmission rating. For any partition that requires a sound rating, use seals and ceiling guards provided by the manufacturer of the partition. Provide a baffle in the ceiling plenum above the partition with a STC rating equal to the partition. Provide a floor surface that will allow the bottom sweep to make a positive seal.

Provide perimeter seals of manufacturer's standard product, without crack or craze when subjected to severe usage.

2.2.5 Ceiling Guards

Furnish partitions with ceiling guards or integral track and ceiling guards as recommended by the manufacturer.

2.3 PERFORMANCE REQUIREMENTS

2.3.1 Fire Endurance

NOTE: Select flame spread and smoke developed criteria to suit project.

For partitions more than 5.6 square meters 60 square feet in area, provide fabric and lining with flame spread rating of 25 or less, fuel contribution rating of 15 or less, smoke generation of 50 or less when tested in accordance with ASTM E84. Complete assembly must also meet or surpass the requirements of NFPA 101 and UL 10B.

2.3.2 Laboratory Acoustical Requirements

NOTE: Specify sound transmission class as determined by project requirements. The requested rating should be between 35 and 45 STC. 39 and 40 STC are widely available. If more is required, another type of moveable partition should be used. Specify a panel weight of no less than 14 kg per square meter 3 psf for STC of 35, 24 kg per square meter 5 psf for STC of 45.

Provide certificates verifying coiling partitions have been tested in accordance with ASTM C423 and ASTM E90 by a laboratory accredited by the U.S. Bureau of Standards and have attained a sound transmission class (STC) of not less than [40] [_____] in a fully extended position. Partition tested must be of the same construction, materials, and model number as the partition to be provided and be fully operable. Test specimen must be not less than [12 square meters in area] [4200 by 2700 mm] [126 square feet in area] [14 feet by 9 feet]. Panel weight must be [14] [24] kg per square meter [3] [5] lbs per square ft.

[2.4 ELECTRICAL OPERATORS

NOTE: Specify electrical operators for those partitions whose size and weight preclude manual operation. Refer to manufacturers' literature. Indicate those partitions requiring electrical operation on the project drawings. Delete this paragraph when electrically operated partitions are not required in the project.

Provide manufacturer's recommended standard electrical operator for [each partition] [partitions indicated]. Provide [wiring diagrams](#).

2.5 FABRICATION

2.5.1 [Framework](#)

Fabricate framework, including posts, pantographs, hinges, hinge plates, and rods from either extruded aluminum or ferrous metal. Arrange frames requiring pantographs for horizontal pantograph action with pantographs located at top and bottom of the frame. Provide pantographs spaced not over [1200 mm 4 feet](#) apart. Provide intermediate pantograph at center of doors less than [2400 mm 8 feet](#) high unless the door has vertical metal reinforcing. The pantographs must operate smoothly with positive coiling action and have a control device to prevent flattening of the folds when the panel is fully extended. Ferrous metal must be either cadmium plated or zinc coated. Posts, at the option of the door manufacturer, may have phosphate treatment and manufacturer's shop finish paint.

2.5.2 [Suspension System](#)

Provide a suspension system consisting of steel or aluminum track and trolleys designed to support the weight of the partition. Provide steel track of [1.5 mm 16 gage](#) minimum, phosphate treated and finished, or zinc or cadmium coated. Provide extruded aluminum track with minimum thickness of [3 mm 1/8 inch](#). Tracks may have an integral ceiling guard. Trolleys must have at least two ball bearing nylon or steel tired wheels spaced according to manufacturer's design criteria and four at an end post.

2.5.3 [Covering](#)

Covering fabrics must conform to the requirements of [ASTM D751](#) and [NFPA 286](#).

Attach fabric to the framework with fasteners that permit easy removal of the cover but prevent sagging or separation. Position vertical seams in the bottoms of valleys and reinforce. Provide top and bottom edges of cover fabrics with [12 mm 1/2 inch](#) minimum turned hems.

2.5.4 [Sound Insulation](#)

Provide sound insulation as necessary to achieve the specified sound transmission mission class, conforming to [ASTM E413](#).

2.5.5 [Air Release](#)

Provide an air release system which allows trapped air within the partition to be released during the stacking process.

2.5.6 [Seals](#)

Provide perimeter seals as necessary to produce the sound transmission class specified [and to pass the visual field test specified].

2.5.7 [Hardware](#)

Provide hardware of the heavy-duty type standard with the manufacturer. Provide pulls and latches for all partitions. Provide partitions with [keyed locks] [privacy latches] [magnetic contact latches] [foot bolts].

2.5.8 Accessories

Provide [multiple meeting posts] [rolling posts] [switches] [ceiling guards] [recessed tracks] [curved tracks] as indicated.

PART 3 EXECUTION

3.1 INSTALLATION

Do not install building construction materials that show visual evidence of biological growth.

3.1.1 Existing Work

NOTE: Show the structural support necessary to accommodate the size and weight of the partition. ASTM E557 has design as well as installation criteria.

Check openings scheduled to receive [coiling partitions](#) for correct dimensions.

Install partitions in accordance with the approved [coiling Partition Layouts](#), manufacturer's directions, and [ASTM E557](#). Provide structural support for the track support elements as indicated.

Submit to the Contracting Officer a certification of the following:

- [Statement of Code Compliance](#) for the completed partition installation.
- [Statement of Standards Conformity](#)

[3.1.2 [Electrical Operators](#)

NOTE: Delete this paragraph when electrically operated partitions are not required.

Conform Electrical components and installation to the requirements of [NFPA 70](#). Provide the partition manufacturer's standard drive and control components required to operate the partition properly. Power source is as indicated.

]3.1.3 Adjustment

[Adjust manually operated partitions to open and close from any position with a maximum horizontal force of [130 N 30 pounds](#) applied to pendant pull, box or handle.] [Adjust drive components and limit switches of electrically operated partitions to ensure the partitions operate properly upon activation of the control switch.]

3.2 FIELD TESTS

3.2.1 Operational Test

Operate partition at least three times to demonstrate that partition is

capable of being moved from the stored position to the fully extended position smoothly and quietly [and without overloading the drive components]. [Activate the emergency release mechanism and demonstrate proper operation of the partition in the manual mode.] Adjust partitions which do not operate properly and retest.

3.2.2 Visual Test

NOTE: Delete this paragraph when light leakage will not be objectionable.

Conduct visual field tests for light leakage with all room lights turned on in the space on one side of the partition. Darken space on the other side of the partition. Light leakage from the lighted space to the darkened space is not acceptable. If light leakage does occur, adjust the partition to correct the problem and retest.

3.2.3 Acoustical Test

NOTE: Delete this paragraph in projects requiring STC ratings of less than 40. Noise Isolation Class (NIC) is a number that can measured, and usually runs up to 10 points below laboratory results, i.e. lab STC 40, field NIC 30. This test is rarely necessary.

Field sound performance: provide partition testing by an independent certified acoustical consultant in accordance with [ASTM E336](#), and achieve a Noise Isolation Class (NIC) of [_____] plus or minus two. Adjust or modify partitions which do not comply, and retest.

3.3 CLEANING

Clean any soiled parts of the partition according to manufacturer's instructions.

3.4 SUPPORT SERVICE

Equipment and component maintenance must be supported by a service organization which is reasonably convenient to the site of installation.

-- End of Section --