
USACE / NAVFAC / AFCEA / NASA UFGS-03 11 19.00 10 (February 2012)

Preparing Activity: USACE New

UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UMRL dated January 2013

SECTION TABLE OF CONTENTS

DIVISION 03 - CONCRETE

SECTION 03 11 19.00 10

INSULATING CONCRETE FORMING

02/12

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 QUALITY ASSURANCE
 - 1.3.1 ICF Manufacturer Qualification
 - 1.3.2 Installer Qualification
 - 1.3.3 Pre-Installation Meetings
 - 1.3.4 Mock-Ups
- 1.4 DELIVERY, STORAGE, AND HANDLING
- 1.5 FIELD/SITE CONDITIONS
- 1.6 SUSTAINABLE DESIGN REQUIREMENTS
 - 1.6.1 Local/Regional Materials
 - 1.6.2 Environmental Data
 - 1.6.3 Plastic Identification

PART 2 PRODUCTS

- 2.1 SYSTEM DESCRIPTION
 - 2.1.1 Design Requirements
 - 2.1.2 Performance Requirements
- 2.2 MANUFACTURED UNITS
 - 2.2.1 Description
 - 2.2.2 Performance/Design Criteria
- 2.3 MATERIALS
 - 2.3.1 Expanded Polystyrene (EPS)
 - 2.3.2 Cross Ties and Fastening Strips
- 2.4 ACCESSORIES
 - 2.4.1 Bracing, Scaffolding, and Wall Alignment
 - 2.4.2 Door and Window Bucks
 - 2.4.3 Waterproofing
 - 2.4.4 Fasteners

PART 3 EXECUTION

- 3.1 EXAMINATION
- 3.2 PREPARATION

- 3.3 INSTALLATION
- 3.4 CONCRETE PLACEMENT
- 3.5 FIELD QUALITY CONTROL
- 3.6 CLEANING
- 3.7 PROTECTION

-- End of Section Table of Contents --

USACE / NAVFAC / AFCEA / NASA UFGS-03 11 19.00 10 (February 2012)

Preparing Activity: USACE New

UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UMRL dated January 2013

SECTION 03 11 19.00 10

INSULATING CONCRETE FORMING 02/12

NOTE: This guide specification covers the
requirements for Insulating Concrete Forming (ICF).

Adhere to UFC 1-300-02 Unified Facilities Guide
Specifications (UFGS) Format Standard when editing
this guide specification or preparing new project
specification sections. Edit this guide
specification for project specific requirements by
adding, deleting, or revising text. For bracketed
items, choose applicable items(s) or insert
appropriate information.

Remove information and requirements not required in
respective project, whether or not brackets are
present.

Comments, suggestions and recommended changes for
this guide specification are welcome and should be
submitted as a Criteria Change Request (CCR).

PART 1 GENERAL

NOTE: This guide specification will normally be
used in conjunction with the following Sections as
applicable to the project:

Section 03 15 00.00 10 CONCRETE ACCESSORIES
Section 03 20 00.00 10 CONCRETE REINFORCING
Section 03 30 00.00 10 CAST-IN-PLACE CONCRETE
Section 03 30 00 00 CAST-IN-PLACE CONCRETE

ICFs are used as stay-in-place forms for structural
concrete, load-bearing and nonload-bearing walls,
below grade and above grade walls. The forms remain
in place after placement and curing of concrete and
must be protected by approved interior and exterior
finish materials.

1.1 REFERENCES

NOTE: This paragraph is used to list the publications cited in the text of the guide specification. The publications are referred to in the text by basic designation only and listed in this paragraph by organization, designation, date, and title.

Use the Reference Wizard's Check Reference feature when you add a RID outside of the Section's Reference Article to automatically place the reference in the Reference Article. Also use the Reference Wizard's Check Reference feature to update the issue dates.

References not used in the text will automatically be deleted from this section of the project specification when you choose to reconcile references in the publish print process.

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONCRETE INSTITUTE INTERNATIONAL (ACI)

ACI 117	(2010; Errata 2011) Specifications for Tolerances for Concrete Construction and Materials and Commentary
ACI 301	(2010; Errata 2011) Specifications for Structural Concrete
ACI 305R	(2010) Guide to Hot Weather Concreting
ACI 306R	(2010) Guide to Cold Weather Concreting
ACI 318	(2011; Errata 2011; Errata 2012) Building Code Requirements for Structural Concrete and Commentary
ACI 347	(2004; Errata 2008; Errata 2012) Guide to Formwork for Concrete

ASTM INTERNATIONAL (ASTM)

ASTM C177	(2010) Standard Test Method for Steady-State Heat Flux Measurements and Thermal Transmission Properties by Means of the Guarded-Hot-Plate Apparatus
ASTM C203	(2005a; R 2012) Breaking Load and Flexural Properties of Block-Type Thermal Insulation
ASTM C518	(2010) Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter

Apparatus

ASTM C578	(2012a) Standard Specification for Rigid, Cellular Polystyrene Thermal Insulation
ASTM D1621	(2010) Compressive Properties of Rigid Cellular Plastics
ASTM D1622	(2008) Apparent Density of Rigid Cellular Plastics
ASTM D1761	(2006) Standard Test Methods for Mechanical Fasteners in Wood
ASTM D1972	(1997; R 2005) Standard Practice for Generic Marking of Plastic Products
ASTM E119	(2012a) Standard Test Methods for Fire Tests of Building Construction and Materials
ASTM E2129	(2010) Standard Practice for Data Collection for Sustainability Assessment of Building Products
ASTM E2634	(2011) Standard Specification for Flat Wall Insulating Concrete Form (ICF) Systems
ASTM E84	(2012b) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E90	(2009) Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements

U.S. GREEN BUILDING COUNCIL (USGBC)

LEED NC	(2009) Leadership in Energy and Environmental Design(tm) New Construction Rating System
---------	---

1.2 SUBMITTALS

NOTE: Review submittal description (SD) definitions in Section 01 33 00 SUBMITTAL PROCEDURES and edit the following list to reflect only the submittals required for the project.

The Guide Specification technical editors have designated those items that require Government approval, due to their complexity or criticality, with a "G." Generally, other submittal items can be reviewed by the Contractor's Quality Control System. Only add a "G" to an item, if the submittal is sufficiently important or complex in context of the project.

For submittals requiring Government approval on Army projects, a code of up to three characters within the submittal tags may be used following the "G" designation to indicate the approving authority. Codes for Army projects using the Resident Management System (RMS) are: "AE" for Architect-Engineer; "DO" for District Office (Engineering Division or other organization in the District Office); "AO" for Area Office; "RO" for Resident Office; and "PO" for Project Office. Codes following the "G" typically are not used for Navy, Air Force, and NASA projects.

Choose the first bracketed item for Navy, Air Force and NASA projects, or choose the second bracketed item for Army projects.

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for [Contractor Quality Control approval.] [information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government.] Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Insulating Concrete Form[; G][; G, [_____]]

Submit data including dimensions of individual ICF block for each form type and details of EPS panels and cross ties.

[Local/Regional Materials; LEED NC]
[Environmental Data]
Accessories

SD-04 Samples

Mock-Up Installation of ICF[; G][; G, [_____]]

SD-06 Test Reports

ICC ES Evaluation Report

SD-07 Certificates

Materials
3rd Party Agency Certification

SD-08 Manufacturer's Instructions

Installation

SD-10 Operation and Maintenance Data

Plastic Identification

1.3 QUALITY ASSURANCE

1.3.1 ICF Manufacturer Qualification

Manufacturer who has been successfully producing ICF products for a period of not less than 5 years and who has experience similar to this project in size, scope and complexity. Manufacturer shall have an [ICC-ES Evaluation Report](#) or certification showing conformance to [ASTM E2634](#) as evidence that the Insulating Concrete Forming (ICF) units are code-compliant.

1.3.2 Installer Qualification

Installer shall be trained by the ICF manufacturer or an ICF Technical Advisor to ensure product is installed in accordance with the manufacturer's published installation instructions. Installer must have experience in ICF systems and successfully completed at least [3] [____] projects that are similar to this project in size, scope and complexity.

1.3.3 Pre-Installation Meetings

NOTE: When the construction consist largely of Insulating Concrete Forming, it is suggested that a pre-installation meeting be required. Otherwise, if the construction is primarily another building material the pre-installation meeting may be omitted.

Prior to commencement of ICF installation and associated work, conduct a meeting at project site with the Contracting Officer, ICF manufacturer's representative, and trades responsible for installing forms, concrete, and reinforcement.

1.3.4 Mock-Ups

NOTE: Complexity of work and scope of quality control should be carefully evaluated before requiring Contractor to construct a mock-up. Delete paragraph if mock-up is not required.

Complete [Mock-Up Installation of ICF](#) with full-size erected assemblies with details including at least one window. Provide mock-up to establish that proposed materials and construction techniques provide acceptable visual effect. Materials used for mock-up shall be those proposed for actual construction and meet the following requirements:

- a. Locate mock-up installation in the location as directed by the Contracting Officer.
- b. Demonstrate the required concrete thickness, insulation and workmanship.
- c. Demonstrate window openings with sill, head and jambs.
- d. Do not proceed with the remaining work until mock-up is approved by the Contracting Officer.
- e. When directed, demolish and remove the mock-up from the site.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver products in original factory packaging, bearing listing and labeling identification of product, manufacturer and lot number. Handle and store products in location to prevent physical damage and soiling. Ensure that UV protection is provided for material stored on site beyond 30 days.

1.5 FIELD/SITE CONDITIONS

Conform to **ACI 305R** and **ACI 306R** for hot and cold weather concreting requirements.

1.6 SUSTAINABLE DESIGN REQUIREMENTS

1.6.1 Local/Regional Materials

NOTE: Using local materials can help minimize transportation impacts, including fossil fuel consumption, air pollution, and labor. Using materials harvested and manufactured within an 800 km (500 mile) radius from the project site contributes to the following LEED credit: MR5. Coordinate with Section **01 33 29** LEED(tm) DOCUMENTATION. Use second option if Contractor is choosing local products in accordance with Section **01 33 29** LEED(tm) DOCUMENTATION. First option shall not be used for USACE projects. Army projects shall include second option only if pursuing this LEED credit.

Include this submittal only if pursuing LEED credit MR5.

[Use materials or products extracted, harvested, or recovered, as well as manufactured, within a **[800] [] km [500] [] mile** radius from the project site, if available from a minimum of three sources.] [See Section **01 33 29** LEED(tm) DOCUMENTATION for cumulative total local material requirements. Insulating Concrete Forming materials may be locally available.] Submit documentation indicating distance between manufacturing facility and the project site. Indicate distance of raw material origin from the project site. Indicate relative dollar value of local/regional materials to total dollar value of products included in project.

1.6.2 Environmental Data

NOTE: ASTM E2129 provides for detailed documentation of the sustainability aspects of products used in the project. This level of detail may be useful to the Contractor, Government, building occupants, or the public in assessing the sustainability of these products.

Submit manufacturer's descriptive data. Documentation indicating

percentage of post-industrial and post-consumer recycled content per unit of product. Indicate relative dollar value of recycled content products to total dollar value of products included in project. [Submit Table 1 of **ASTM E2129** for the following products: [____].]

1.6.3 Plastic Identification

NOTE: The marking system indicated below is intended to provide assistance in identification of products for making subsequent decisions as to handling, recycling, or disposal.

Verify that plastic products to be incorporated into the project are labeled in accordance with **ASTM D1972**. Where products are not labeled, provide product data indicating polymeric information in the Operation and Maintenance Manual and in accordance with Section **01 78 23** OPERATION AND MAINTENANCE DATA.

- a. Type 1: Polyethylene Terephthalate (PET, PETE).
- b. Type 2: High Density Polyethylene (HDPE).
- c. Type 3: Vinyl (Polyvinyl Chloride or PVC).
- d. Type 4: Low Density Polyethylene (LDPE).
- e. Type 5: Polypropylene (PP).
- f. Type 6: Polystyrene (PS).
- g. Type 7: Other. Use of this code indicates that the package in question is made with a resin other than the six listed above, or is made of more than one resin listed above, and used in a multi-layer combination. Provide the package make up.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Insulating concrete wall form system shall consist of two panels of molded expanded polystyrene (EPS) insulation connected by cross ties to act as permanent formwork for cast-in-place reinforced concrete beams, lintels, non-load-bearing walls, load-bearing walls, foundation walls, and retaining walls while provide insulating characteristics.

2.1.1 Design Requirements

Design, engineer, and construct formwork in accordance with methodology of **ACI 347** for anticipated loads, lateral pressures, and stresses, and capable of withstanding the pressures resulting from placement and vibration of concrete. Monitor the adequacy of formwork design and construction prior to and during concrete placement as part of the approved Quality Control Plan.

2.1.2 Performance Requirements

The **Insulating Concrete Form** (ICF) wall system shall provide minimum[**100 mm**

4 inches] [150 mm 6 inches] [200 mm 8 inches] [250 mm 10 inches] [300 mm 12 inches] forming cavity width. The cavity width shall be a consistent flat rectangular cross section. Provide cross ties in the ICF wall system at 200 mm 8 in o.c. maximum. ICF system shall have fastening strips 25 mm 1 inch minimum flange width for the full vertical or horizontal span of the wall to fasten exterior and interior wall finishes. Space fastening strips at a maximum of 406 16 inches on center. Wall system shall provide accurate positioning of concrete reinforcing bars within the form cavity conforming to ACI 318. Submit manufacturer's literature describing product, materials, installation procedure and accessories.

2.2 MANUFACTURED UNITS

2.2.1 Description

The ICF system includes an expanded polystyrene forming unit used to construct a monolithic reinforced concrete wall. The forms remain in place, providing a concrete wall to be finished with conventional interior and exterior wall coverings. Provide form unit types and sizes as determined by the ICF manufacturer to provide walls indicated. Provide form materials in accordance with the manufacturer, other specifications herein, and the following:

2.2.2 Performance/Design Criteria

NOTE: Some ICF's are available with a 45 mm (1-3/4 inch) EPS option. These forms are an economical option for interior demising walls and environments where high thermal insulation values are not as important. The typical R-value of a 45 mm (1-3/4 inch) EPS ICF is R-14. Also, ICF manufacturer's typically do not have all form types in every core thickness. Usually straight and 90 degree corner units are available in each core thickness.

Insulating Concrete Forms provide a minimum[100 mm 4 inch] [150 mm 6 inch] [200 mm 8 inch] [250 mm 10 inch] [300 mm 12 inch] concrete "flat" cross section. Use preformed forms with interlocking edges to facilitate course-to-course bonding to prevent uplift and lateral failure. Provide manufacturer form unit types for straight, 90 degree corners, 45 degree corners, brick ledges, and tapered top forms. ICF unit shall provide a minimum R-value of [R-22] [R-16 for 100 mm 4 inches ICF unit] [R-14 for units with 45 mm 1-3/4 inches thick EPS panels] as tested in accordance with Test Method ASTM C518/ASTM C177. EPS shall provide a maximum vapor permeation of 0.09 perm-meter 3.5 perm-inch. Finish wall assembly shall have a minimum rating of Sound Transmission Class (STC) [50] [____] sound attenuation performance as tested in accordance with Test Method ASTM E90. The fire resistive-rated construction of the complete ICF wall assembly including EPS, cross tie material, and concrete shall be in accordance with Test Methods ASTM E119.

Conform the Insulating Concrete Forming System to the following minimum requirements:

TABLE 1 - PROPERTIES

Properties	ASTM Test	Value
Density	ASTM D1622	24 kg/m3 1.5 lbs/ft3
Thermal Resistance	ASTM C177	0.275 m2.C/W per cm (min)4.0 F.ft2.h/Btu per in (min)
Compressive Strength	ASTM D1621	103 kPa15.0 psi
Flexural Strength	ASTM C203	276 kPa (min.)40.0 psi (min)
Flame Spread	ASTM E84	25 maximum
Smoke Developed	ASTM E84	450 maximum

2.3 MATERIALS

Submit 3rd party agency certification stating that product supplied meets the requirements of ASTM E2634.

2.3.1 Expanded Polystyrene (EPS)

NOTE: Some ICF Manufacturers have 50 mm (2 inches) thick EPS panels for their 100 mm (4 inch) wide ICF wall systems. Designer should confirm EPS panel thickness provides the appropriate R-value for this project. Some ICF's are available with a 45 mm (1-3/4 inch) EPS option. These forms are an economical option for interior demising walls and environments where high thermal insulation values are not as important.

Expanded Polystyrene shall conform to ASTM C578. Provide Type II EPS panels, Flame Resistant with[63 mm 2-1/2 inch][45 mm 1-3/4 inch][____] thick minimum EPS panels.

2.3.2 Cross Ties and Fastening Strips

NOTE: ICF Forms are widely available that include fastening strip recessed from 6 mm (1/4 inch) up to 38 mm (1-1/2 inches) below the outside surface of the EPS panels. The deeper recesses help facilitate the placement of electrical and plumbing utilities within the wall. 13 mm (1/2 inch) recess appears to be standard for most ICF Manufacturers. Designer may include a range of recess depths, i.e., 13mm (1/2 inch) to 38 mm (1-1/2 inches)

Use plastic or metal cross ties spaced at 200 mm 8 inches o.c. maximum. Cross ties shall allow for multiple reinforcement placement positions to meet the structural design. Provide fastening strips with 25 mm 1 inch minimum flange width for the full vertical or horizontal span of the wall

to fasten exterior and interior wall finishes. Recess the fastening strips [6 mm 1/4 inch][13 mm 1/2 inch][38 mm 1-1/2 inches][_____] below the outside surface of the panels. Clearly mark the flanges on the surface of the EPS panels. Provide a fastening strip in the corners of corner forms.

2.4 ACCESSORIES

2.4.1 Bracing, Scaffolding, and Wall Alignment

Support ICF system prior to the attachment of permanent structural elements to protect the ICF components from damage during construction.

2.4.2 Door and Window Bucks

Use extruded vinyl, pressure treated wood, or metal buck material to frame door and window openings.

2.4.3 Waterproofing

Waterproofing material shall be compatible with EPS system and as specified in Section [07 13 53 ELASTOMERIC SHEET WATERPROOFING] [07 14 00 FLUID-APPLIED WATERPROOFING]

2.4.4 Fasteners

Fasteners of interior and exterior wall finishes to ICF wall system shall conform to ASTM D1761. Fasteners shall be corrosion-resistant and have sufficient length to penetrate the flanges of the fastening strips.

PART 3 EXECUTION

3.1 EXAMINATION

Verify that footings and slabs are installed level and true to the structural design. Ensure dimensions and steel reinforcement are as indicated.

3.2 PREPARATION

Clean top of footings and slabs of all foreign substances, frost, ice, and standing or running water prior to starting installation of ICF system. Use methods and materials approved by ICF manufacturer.

3.3 INSTALLATION

Install ICF system in accordance with the manufacturer's installation and technical manual; submit a copy of the manual. Provide bracing and shoring to ensure stability of formwork to prevent overstressing of ICF units due to construction loads in accordance with ACI 301. Install ICF system in running bond pattern. Anchor formwork to supporting surfaces to prevent upward or lateral movement of the ICF units during concrete placement. Place sleeves, inserts, anchors, and embedded items required for adjoining work or for support of adjoining work before concrete placement. Align fastener strips to facilitate interior and exterior wall finishes. Install concrete reinforcement according to the structural drawings at all walls, lintels, beams, and around openings. Install window and door bucks at each location where an opening is required. Install metal starter track on the footing and affix to first ICF course to ensure that base of wall does not become misaligned during concrete placement. Install alignment bracing

around the entire wall of the structure to ensure the ICF system is straight and plumb before and during concrete placement.

3.4 CONCRETE PLACEMENT

NOTE: Designer should indicate on the drawings location of construction joints and provide the necessary details, including any required dowels or keyways. Refer to ACI 318 for additional information for construction joints in structural members.

Before placing concrete, verify that installation of formwork, reinforcement, and embedded items is complete and that required inspections have been performed. Deposit concrete in horizontal layers of depth to not exceed formwork design pressures. If concrete cannot be placed in continuous pour, provide construction joints [as indicated] [as approved by the Designer of Record] [as on the approved concrete placement plan]. Consolidate placed concrete with mechanical vibrating equipment conforming to ACI 301. Variations from plumb and designated building lines shall not exceed the tolerances specified in ACI 117.

3.5 FIELD QUALITY CONTROL

The ICF manufacturer's representative or technical advisor shall provide on-site training to installer to ensure familiarity of ICF manufacturer's installation procedures and technical manual. Inspect erected formwork, reinforcement placement, door and window opening construction, concrete placement, and alignment and bracing system to ensure that work is in accordance with drawings. Installer to ensure that the cast-in-place concrete walls are level, plumb, square, and straight and that all dimensions conform to the drawings and are within required tolerances. Notify the Contracting Officer in writing of defective forms within 7 working days of the date of ICF inspection.

3.6 CLEANING

Clean formed cavities, within ICF units, of debris and foreign matter prior to concrete placement. Clean up and properly dispose of all debris remaining on job site related to the installation of the ICF system, recycling materials as required.

3.7 PROTECTION

Provide temporary coverage of installation of ICF system to reduce exposure to ultraviolet light should final finish application be delayed longer than 60 days.

-- End of Section --