
USACE / NAVFAC / AFCEA UFGS-02151 (August 2004)

Preparing Activity: USACE Superseding
UFGS-02151A (July 2004)

UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UMLR dated 22 December 2004

Latest change indicated by CHG tags

SECTION TABLE OF CONTENTS

DIVISION 02 - SITE CONSTRUCTION

SECTION 02151

SOIL WASHING THROUGH SEPARATION/SOLUBILIZATION

08/04

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 MEASUREMENT AND PAYMENT
 - 1.3.1 Measurement
 - 1.3.2 Payment
 - 1.3.2.1 Treatability Studies
 - 1.3.2.2 Demonstration Test Run
 - 1.3.2.3 Feed Oversize Materials Treatment and/or Disposal
 - 1.3.2.4 Feed Materials Treatment
 - 1.3.2.5 Other Work Items
 - 1.3.3 Excess Quantity
 - 1.3.4 Reprocessing
- 1.4 SYSTEM DESCRIPTION
 - 1.4.1 Soil Washing Treatment Process
 - 1.4.2 Soil Washing Treatment Plant
 - 1.4.2.1 Soil Preparation and Feed System
 - 1.4.2.2 Soil Washing and Separation System
 - 1.4.2.3 Spent Washwater Treatment System
 - 1.4.2.4 Plant Supporting System
 - 1.4.3 Performance Requirements
 - 1.4.4 Cut Size Requirement
 - 1.4.5 Installation Requirements
 - 1.4.6 Results of Previously Conducted Treatability Studies
 - 1.4.7 Utilities
 - 1.4.8 Spent Washwater Treatment and Disposal Requirements
 - 1.4.9 Solid Waste Treatment and Disposal Requirements
 - 1.4.10 Emissions and Dust Control
 - 1.4.11 Noise Control
 - 1.4.12 Sampling, Monitoring, and Control Requirements
 - 1.4.13 Contaminated Material Measurement Accuracy Requirements
 - 1.4.14 Mobilization
 - 1.4.15 Demobilization

- 1.5 QUALIFICATIONS
- 1.6 DELIVERY, STORAGE, AND HANDLING
- 1.7 SITE CONDITIONS
 - 1.7.1 Environmental Requirements
 - 1.7.2 Existing Conditions

PART 2 PRODUCTS

- 2.1 MATERIALS
 - 2.1.1 Water Supply
 - 2.1.2 Reagent/Additive Certificates of Analyses
- 2.2 MIXES
- 2.3 SAMPLES FOR TREATABILITY STUDIES

PART 3 EXECUTION

- 3.1 EXAMINATION
- 3.2 PREPARATION
 - 3.2.1 Stockpiles of Contaminated Materials
 - 3.2.1.1 Liner
 - 3.2.1.2 Cover
 - 3.2.1.3 Diversion Measures
 - 3.2.1.4 Stockpile Leachate
 - 3.2.2 Foundations
- 3.3 ERECTION, INSTALLATION, AND DEMOBILIZATION
- 3.4 OPERATION
 - 3.4.1 Different Types of Contamination and Materials
 - 3.4.2 Stockpile Management
 - 3.4.2.1 Feed Oversize
 - 3.4.2.2 Feed Material
 - 3.4.2.3 Treated Materials
 - 3.4.2.4 Process Sludge
 - 3.4.3 Auxiliary Requirements for System Operations
 - 3.4.4 Management of Reagents/Additives
 - 3.4.5 Change of Operating Conditions
 - 3.4.6 Management of Treatment Plant Wastewater
 - 3.4.7 Equipment Inspection and Maintenance
 - 3.4.8 Daily Operations Report
- 3.5 TESTS
 - 3.5.1 Post Treatment Testing
 - 3.5.2 Reprocessing
 - 3.5.3 Government Testing
- 3.6 GOVERNMENT INSPECTION
- 3.7 DEMONSTRATION
 - 3.7.1 Field Demonstration
 - 3.7.2 Full Scale Processing Equipment
 - 3.7.3 Sampling Locations
 - 3.7.4 Testing
 - 3.7.5 Commencement of Full Scale Operation
- 3.8 PROCESS MATERIALS MANAGEMENT

-- End of Section Table of Contents --

USACE / NAVFAC / AFCEA UFGS-02151 (August 2004)

Preparing Activity: USACE Superseding
UFGS-02151A (July 2004)

UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UMRL dated 22 December 2004

Latest change indicated by CHG tags

SECTION 02151

SOIL WASHING THROUGH SEPARATION/SOLUBILIZATION 08/04

NOTE: This guide specification covers the requirements for removal of heavy metals/inorganics, organics, and radioactive wastes by water-based soil washing.

Comments and suggestions on this guide specification are welcome and should be directed to the technical proponent of the specification. A listing of technical proponents, including their organization designation and telephone number, is on the Internet.

Recommended changes to a UFGS should be submitted as a Criteria Change Request (CCR).

Use of electronic communication is encouraged.

Brackets are used in the text to indicate designer choices or locations where text must be supplied by the designer.

PART 1 GENERAL

NOTE: This UFGS provides the framework for developing a project-specific soil washing specification. It should be modified as necessary for a given site, to incorporate the conditions, soil washing technology, and regulatory requirements which are specific to the site.

The appropriate regulatory agencies should be consulted to obtain their approval of work plans, specifications, drawings, and on the sampling methodology for a soil washing treatment project. The maximum allowable quantity of the treated materials or the process sludge from which one composite sample must be taken for characterization

and/or compliance should also be verified. This maximum allowable quantity per composite sample collection may effect the size of a stockpile, and subsequently, determine the number of days required to reach this quantity based on the daily generation of the treated materials or the process sludge.

The soil washing operation considered in this section starts with the raw contaminated material piles; continues through preparation, feeding, washing, separation, stockpiling, waste (solid, liquid and/or gaseous) treatment and disposal; ends at the treated clean material piles. Refer to Section 02111 EXCAVATION AND HANDLING OF CONTAMINATED MATERIAL for requirements related to excavation of the contaminated materials and redeposition (or backfilling) of the treated clean materials. Refer to Section 02120 TRANSPORTATION AND DISPOSAL OF HAZARDOUS MATERIALS for requirements relevant to offsite transportation and disposal.

Additional references from Federal, state, and local regulatory requirements; utility company regulations; and applicable codes and standards published by scientific and engineering institutions should be included where appropriate in the body of the specification. Some of the potentially applicable Federal regulations are listed as follows:

Toxicity Characteristic Leaching Procedure (TCLP)

Recording and Reporting Occupational Injuries and Illnesses

Occupational Safety and Health Standards

Safety and Health Regulations for Construction

Permitting

National Primary and Secondary Ambient Air Quality Standards

National Emission Standards for Hazardous Air Quality Pollutants

State and Local Air Quality Standards

National Pollution Discharge Elimination System (NPDES) Discharge Limitations and Permit Procedures

Hazardous Waste Identification and Standards Applicable to Generators, Transporters, and Owners and Operators of Treatment, Storage and Disposal Facilities (TSDF)

Land Disposal Restrictions (LDRs)

Department of Transportation Hazardous Materials

Program Procedures

Hazardous Materials Transportation Regulations

Standards for Protection Against Radiation

Land Disposal of Low-Level Radioactive Waste

Packaging and Transportation of Radioactive Materials

1.1 REFERENCES

NOTE: Issue (date) of references included in project specifications need not be more current than provided by the latest guide specification. Use of SpecsIntact automated reference checking is recommended for projects based on older guide specifications.

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D 2216	(1998) Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass
ASTM D 4643	(2000) Determination of Water (Moisture) Content of Soil by the Microwave Oven Method

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA 540/2-91/020A	(1991) Guide for Conducting Treatability Studies under CERCLA: Soil Washing: Interim Guidance
EPA 540/R-92/071a	(1992) A Guide For Conducting Treatability Studies Under CERCLA, Final Report

1.2 SUBMITTALS

NOTE: Submittals must be limited to those necessary for adequate quality control. The importance of an item in the project should be one of the primary factors in determining if a submittal for the item should be required.

A "G" following a submittal item indicates that the submittal requires Government approval. Some submittals are already marked with a "G". Only delete an existing "G" if the submittal item is not complex and can be reviewed through the Contractor's Quality Control system. Only add a "G" if the

submittal is sufficiently important or complex in context of the project.

For submittals requiring Government approval on Army projects, a code of up to three characters within the submittal tags may be used following the "G" designation to indicate the approving authority. Codes for Army projects using the Resident Management System (RMS) are: "AE" for Architect-Engineer; "DO" for District Office (Engineering Division or other organization in the District Office); "AO" for Area Office; "RO" for Resident Office; and "PO" for Project Office. Codes following the "G" typically are not used for Navy projects.

Submittal items not designated with a "G" are considered as being for information only for Army projects and for Contractor Quality Control approval for Navy projects.

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for [Contractor Quality Control approval.] [information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government.] The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Soil Washing Work Plan[; G][; G, [____]]

The Work Plan shall be submitted within [45] [____] days after notice to proceed. The Contractor shall allow [30] [____] days in the schedule for Government review and approval of the Work Plan. The Work Plan shall address the technical requirements listed in this section. The Work Plan shall include, but is not limited to, the following:

a. Schedule. The schedule shall specify dates for the start and completion of [treatability studies] [____], mobilization, installation, field demonstrations, treatment of contaminated materials, disposal of wastes, and demobilization. The schedule shall include details such as intended hours of operation, scheduled downtime, and routine maintenance downtime.

b. Project Organization. A project organization shall be proposed for carrying out the remediation of contaminated materials by soil washing treatment. An organization chart including subcontractors shall be provided. The responsibilities of each individual in the organization shall be clearly defined in terms of project activities including, but not limited to: project management and coordination; scheduling and schedule control; quality control; sampling, measurement, analysis, and data management; and operation and maintenance of the treatment plant. In addition, the previous experience of each individual in the project organization shall also be submitted for review and approval. Credentials of new operators, quality control

personnel, and supervisory engineering and technical staff shall be furnished to the Contracting Officer for approval [5] [_____] working days prior to such personnel assuming duties onsite.

c. Treatability Study Work Plan. The Treatability Study Work Plan shall outline the planned testing and evaluation. This study shall include, but not be limited to: contaminated materials characterization (including the contaminant concentration as a function of grain size if a cut size needs to be determined), washwater determination and optimization, residuals management, mass balance calculation, unit processes/operations evaluation, cut size determination for separation (if applicable), treated materials characterization, sampling locations, analytes, testing protocols, and waste streams characterization. In addition, the Treatability Study Work Plan shall include a thorough discussion of how the study's operating conditions will compare with full scale conditions, and how the variances will be addressed in scale-up. If proprietary reagents/additives are to be used in the processes, Material Safety Data Sheets (MSDS's) and other non-proprietary type information of the reagents/additives shall be provided to assess their potential for secondary contamination during the installation and operation of the treatment plant.

d. Principles of Operation. A detailed description of the proposed treatment plant shall be provided. The description shall include treatment systems and corresponding unit operations, treatment capacity, preparation of feed material, soil handling and feed systems, quality of washwater, properties and handling of reagents/additives, mechanism of contaminant removal, characteristics and stockpiling of the treated materials, and wastes generation and disposal. Post treatment criteria, [disposal criteria] [discharge criteria] and [air emissions criteria] [_____] shall be presented based on the proposed treatment plant and the site conditions.

e. Equipment. Treatment system equipment shall be described completely. The description shall include, but not be limited to, equipment identification, manufacture make and model, physical size, operating conditions, and materials of construction.

f. Drawings. The drawings provided shall include, but not be limited to: layout of the treatment plant including feed material stockpiles, including a drainage and leachate collection plan for the area, treated material stockpiles, and solid waste stockpiles; piping and instrumentation diagrams; and process flow diagrams.

g. Quality Control. A site-specific quality control program shall be provided to detail the procedures for inspection, testing, and correction of deficiencies. This program shall ensure that the Contractor's operations comply with the requirements of the contract plans and specifications with respect to quality of materials, workmanship, construction, finish, functional performance, and accuracy of data.

h. Process Material Tracking Schedule. A proposed Process Material Tracking Schedule for recording and managing the quantities of the contaminated materials processed, [feed oversize

treated and/or requiring disposal], [process sludge treated and/or requiring disposal], [other waste streams requiring disposal such as [____]], [reprocessing of treated materials that fail to meet post treatment criteria] [____], and the treated clean materials to be backfilled.

i. Mobilization and Demobilization. A mobilization and demobilization plan shall be included.

Field Demonstration[; G][; G, [____]]

The Field Demonstration Plan shall outline the planned demonstration and evaluation activities. This plan shall address, but not be limited to, contaminated materials characterization (including the contaminant concentration as a function of grain size if a cut size needs to be determined), proposed demonstration testing runs (including specification of washwater mix design and testing/operating conditions of the unit processes/operations for each run), sampling locations, analyses, and analytical methods, mass balance calculation and performance evaluation [for each major piece of equipment], cut size determination for separation (if applicable), treated materials and waste characterization, health and safety monitoring and control, and waste treatment and/or disposal. If proprietary reagents/additives are to be used in the processes, MSDS's and other non-proprietary type information of the reagents/additives shall be provided to assess their potential for secondary contamination during the demonstration testing.

Noise Control[; G][; G, [____]]

For environmental compliance, a site-specific Noise Control and Monitoring Plan. This plan shall include, but not be limited to, expected noise level, sources of noise, proposed noise control, and types and locations of monitoring devices.

Emissions and Dust Control[; G][; G, [____]]

For environmental compliance and process control, a site-specific Emissions and Dust Control Monitoring Plan. This plan shall include, but not be limited to, expected quantity of emissions, sources of emissions, proposed emissions control. If an air pathway analysis indicates monitoring is required, backup calculations, and regulatory information substantiating decisions proposed by the Contractor shall be provided in addition to types and locations of monitoring devices.

Permits and Certifications

The Contractor shall obtain the permits, certifications, and/or substantive regulatory requirements necessary for the configuration, installation, operation, and closure of the treatment plant. The required permits, certifications, and/or substantive regulatory requirements shall be provided along with the Work Plan. For those permits, certifications, and/or substantive regulatory requirements which have not been obtained, a copy of these applications shall accompany the Work Plan.

SD-06 Test Reports

Treatability Study Report

The Treatability Study Report shall address, but not be limited to, the materials, procedures, and methods used in the study; tests performed; sampling and analysis; mass balance and performance evaluation; and results, conclusions with supporting dialog, and recommendations.

Field Demonstration Report[; G][; G, [_____]]

The Field Demonstration Report shall address, but not be limited to, the following: contaminated materials collection and characterization; demonstration test runs (including washwater mix design and testing/operating conditions); sampling locations and corresponding analytical methods; mass balance calculation (including water, materials, and contaminants) for each unit process and waste stream; performance evaluation; cut size determination for separation (if applicable); treated materials and wastes characterization; wastes treatment and/or disposal; conclusions; and recommendations. In addition, the day-to-day log of operations and adjustments to optimize the treatment system shall be included in the appendices.

Water Supply Analysis

The water shall be analyzed to verify before use, and the analytical results provided.

Daily Operations Report

Reports of daily tests and operations.

Physical and Chemical Test Results

During the soil washing treatment operation, the physical and chemical test results of the [contaminated materials] [_____], treated materials, and wastes, background sampling under stockpiles and the plant area prior to construction activities, and following removal of the soil washing equipment and stockpile areas. The test results shall include time of sampling, location of sampling, and Contractor Quality Control (such as duplicate sample analysis, field and trip blank analysis, laboratory QC analysis, etc.) results. Data validation of the test results shall be performed before submittal. The sample collection, packaging, shipping, analyses, and reporting shall be conducted in accordance with Section 01450A CHEMICAL DATA QUALITY CONTROL, Section 01451A CONTRACTOR QUALITY CONTROL, and [_____].

SD-07 Certificates

Reagent/Additive Certificates of Analyses

Certificates of analyses for reagent and additives.

1.3 MEASUREMENT AND PAYMENT

NOTE: This paragraph should be modified based on

the project specific conditions. Special Clauses should address modification of the full scale remediation unit price due, if warranted, based on the results of the field demonstration testing. This paragraph should be deleted if the work is in one lump sum contract or there is a separate Measurement and Payment Section.

1.3.1 Measurement

NOTE: Materials (such as soil, sediment, and sludge) at a given site should be classified as contaminated materials when levels of the organic, inorganic, and radioactive contaminants in the contaminated materials exceed the site action level criteria which have been established based on regulatory requirements and/or site-specific risk assessment to protect human health and the environment.

The feed oversize and the feed materials shall be weighed separately during operation of the soil washing treatment plant (the treatment plant). The feed oversize (or debris) consists of the oversized materials separated from the raw contaminated materials by the soil preparation and feed system. The feed materials are the balance of the raw contaminated materials after the feed oversize has been removed. [A properly calibrated platform weigh scale] [_____] and/or [conveyor belt weigh scale] [_____] shall be used to accurately measure the gross (bulk) weights in [metric ton short ton] [_____] of the feed oversize and the feed materials, respectively. The measured gross (bulk) weight of the feed materials to be treated by soil washing shall be converted to dry weight based on the [percent moisture content] [_____] of representative feed material samples. [The percent moisture content shall be determined in accordance with ASTM D 2216] [ASTM D 4643] [_____] . [Moisture content shall be determined [daily.] [for every [500] [_____] [metric ton short ton] of feed material.]]

1.3.2 Payment

Compensation for performing [treatability studies] [_____] , demonstration testing, treatment and/or disposal of the feed oversize, soil washing treatment of feed materials, and other base bid project activities will be provided as specified in the following subparagraphs.

1.3.2.1 Treatability Studies

NOTE: Delete this paragraph if treatability studies have already been performed. In that case, the Contractor has the option to perform additional treatability studies at Contractor's expense.

Payment for treatability studies will be [included as part of base bid items] [based on lump sum price] [_____] . The price will include costs for labor and materials for: preparing plans; collecting representative contaminated materials; conducting the studies (including sampling and

analysis); evaluating results; preparing the treatability study report; and treating and/or disposing of study-derived wastes.

1.3.2.2 Demonstration Test Run

Payment for field demonstration test runs will be [included as part of base bid items] [based on lump sum price for each test run requested by the Contracting Officer and properly completed]. The price will include costs for labor and materials for: [hauling] [____], stockpiling, processing and treatment, testing and analyzing, report preparation, treatment and/or disposal of wastes (solid, liquid and/or gaseous) generated during test runs, and other incidental work (such as, manufacturers' field services, health and safety monitoring and controls, and utilities). The demonstration test runs shall be performed at full scale throughout as specified in this section.

1.3.2.3 Feed Oversize Materials Treatment and/or Disposal

The feed oversize materials shall include, but not be limited to, contaminated materials, roots, tree trunks, construction debris, etc., greater than [50 mm 2 inches] [____] in size. Payment for treatment and disposal of feed oversize material shall be based on the contract unit price schedule for each [metric ton short ton] [____] on a gross (bulk) weight basis of the previously untreated feed oversize material. The unit price shall include costs for labor, disposal, and [materials] [stockpiling] [transporting] [treatment] [other incidental work] [____].

1.3.2.4 Feed Materials Treatment

Payment for soil washing treatment of the feed materials will be based on the contract unit price schedule for each [metric ton short ton] [____] on a dry weight basis of the previously untreated feed materials entering the treatment plant following removal of feed oversize material. This unit price will include costs for materials, labor, [hauling] [____], stockpiling, processing and treatment, testing and analyzing, operation and maintenance, and wastes (solid, liquid and/or gaseous) treatment and/or disposal.

1.3.2.5 Other Work Items

Payment for other work items not included in the above paragraphs will be included in the payment for the base bid for remediation of the contaminated materials. The other work items include submittals related to operation of the treatment plant, soil washing mobilization and demobilization, site preparation in the treatment plant area, configuration and installation of the treatment plant, manufacturers' field services, environmental compliance monitoring, health and safety monitoring and controls, and utilities required for the soil washing operation if approved by the Government as necessary for the project.

1.3.3 Excess Quantity

**NOTE: This paragraph should be coordinated with
design drawings and paragraphs Measurement and
Payment for consistency.**

The payment for the excess quantity shall be based on the contract excess

quantity unit price schedule for each additional [metric ton short ton] [_____] of previously untreated feed oversize material (on a gross weight basis) and feed materials following separation of feed oversize materials (on a dry weight basis) entering the treatment plant.

1.3.4 Reprocessing

The Contractor will not be paid for reprocessing the contaminated materials not meeting the post treatment criteria outlined in this section. Contaminated materials requiring reprocessing shall be identified and deducted from the daily production quantity.

1.4 SYSTEM DESCRIPTION

NOTE: If pretreatment such as blending for a homogenous feed or separating contaminated materials with different characteristics for different treatment operating conditions is required, some of the pretreatment requirements should be specified in Section 02111 EXCAVATION AND HANDLING OF CONTAMINATED MATERIAL so the pretreatment required can be properly specified in this specification without any duplication. In addition, representative samples of the contaminated materials excavated and stockpiled should be collected and analyzed regularly to check and document the physical and chemical characteristics of the contaminated materials. These sampling and analysis efforts should also be specified in the section dealing with excavation and stockpiling.

For remediation using soil washing, a Request for Proposal (RFP) rather than Invitation for Bid (IFB) procurement process is generally used to select a Contractor.

1.4.1 Soil Washing Treatment Process

Washwater shall consist of water only or water plus approved reagents/additives such as acids, bases, surface active agents (surfactants), solvents, and chelating or sequestering agents, to enhance the solubilization and/or separation of the contaminants and thus increase the efficiency of the soil washing treatment.

1.4.2 Soil Washing Treatment Plant

The treatment plant shall be configured based on the contaminated material characteristics data, [the Contractor's own interpretation of the previously conducted treatability study results] [_____] , and [the bench-scale and/or pilot-scale treatability studies performed by the Contractor] [_____]. The treatment plant [shall be transportable. The] materials, components, accessories, and equipment used to fabricate the treatment plant shall meet their functional requirements, and shall be compatible with the contaminants of concern, the reagents/additives used in the treatment processes, and the operating conditions of each unit operation. The Contractor may propose a treatment plant different from the treatment plant for which specific requirements are provided in this

section, in which case the proposed treatment plant capable of providing equivalent performance shall be addressed in detail [in the Contractor's proposal] [and] [in the Work Plan] [_____]. The Contractor shall provide a safe and reliable soil washing treatment plant in compliance with the applicable codes, regulations, and specified requirements; the Contractor shall submit Permits and Certifications as specified in the Submittals paragraph. The treatment plant shall consist of the following major systems:

1.4.2.1 Soil Preparation and Feed System

Soil preparation and feed system shall include, but not be limited to, feed oversize separation, blending and/or separation of different materials (if needed), stockpiling of feed oversize and feed materials, conveying, feeding, treatment and/or disposal of feed oversize, dust/emission controls, and measurement of feed oversize and feed materials. The capacity of this system shall be sized based on the downstream treatment system operations.

1.4.2.2 Soil Washing and Separation System

Soil washing and separation system shall include mixing, washing, [solids and liquid separation] [particle size separation] [_____], dewatering, stockpiling of treated materials, and measurement of process parameters and treated materials. Treated materials are the feed materials having been washed and separated by the soil washing and separation system. Treated clean materials are the treated materials which meet the post treatment criteria. The system shall be equipped with direct means for controlling the washwater settings including [pH] [temperature] [pressure] [composition] [quantity] [contact time] and [cut size] [_____]. The mixing and washing equipment shall have the capability to dissociate the contaminated fine particles from the coarse particles and/or to solubilize the contaminants into the washwater so that the post treatment criteria can be achieved. [Magnetic separation of ferrous material shall be done using electromagnets.] The dewatering equipment shall have the capability of lowering the moisture content to less than [10] [15] [_____] percent as required for the backfilling operation. The treated materials shall be separately stockpiled on a [daily] [_____] basis [according to the sampling and testing requirements] [_____].

1.4.2.3 Spent Washwater Treatment System

Spent washwater is washwater that has been in contact with contaminated feed materials or other contaminated surfaces, consisting of a mixture of contaminated fine particles and/or dissolved contaminants, washwater, and run off water from storage and treatment areas. Spent washwater treatment system (if required) shall include physical, chemical, and/or biological treatment of spent washwater; dissolved and/or suspended solids removal; process sludge dewatering; recycle, reuse, and/or discharge of treated washwater; stockpiling, treatment and/or disposal of process sludge; and measurement of treatment parameters and dewatered and/or treated process sludge. Process sludge is the sludge resulting from the removal of dissolved contaminants and/or the contaminated fine particles in the spent washwater. The treated washwater shall meet the quality limits for [recycle] [reuse] [discharge], and/or [disposal] [_____]. The process sludge shall be treated and/or disposed of according to its characteristics and regulatory requirements.

1.4.2.4 Plant Supporting System

The plant supporting system shall include facilities for water storage and distribution, reagents/additives storage and distribution, [power and steam] [power] generation and distribution, and fire safety. These supporting facilities shall have adequate capacities to provide water, reagents/additives, power, [steam] [____], and fire protection necessary for operation of the soil preparation and feed system, soil washing and separation system, and [spent washwater treatment system] [____]. Reagents/Additives used in the treatment plant shall be stored in tanks, drums or other containers which are made of compatible materials. The feeding equipment for each reagent/additive shall consist of a feed tank and mixer for preparing feed stock, and a metering pump for controlled feeding.

1.4.3 Performance Requirements

NOTE: Table 1 should be developed based on site-specific contaminants of concern and regulatory requirements.

Planned treatment criteria, as well as sampling and analysis requirements, should be reviewed by regulatory agencies in the early stages of design. These criteria generally consist of cleanup levels and/or contaminant limits derived from risk based requirements, Toxicity Characteristic Leaching Procedure (TCLP) limits, Synthetic Precipitation Leachate Procedure (SPLP), Resource Conservation and Recovery Act (RCRA), Land Disposal Restrictions (LDRs), and RCRA delisting requirements. Coordinate backfilling with Section 02111 EXCAVATION AND HANDLING OF CONTAMINATED MATERIAL to ensure geotechnical parameters are specified.

A treatment plant capable of processing contaminated materials at [an average expected rate factoring in downtime, startup time, and shutdown time] [a designed rate based on adjusted dry weight] of [[____] metric short tons per hour] [____] shall be provided. The concentrations of the contaminants in the treated material and in the TCLP extract of the treated material shall not exceed, respectively, the cleanup level and TCLP extract limit specified in Table 1. Section 01450A CHEMICAL DATA QUALITY CONTROL contains requirements related to multimedia chemical sampling and analysis.

TABLE 1
POST TREATMENT CRITERIA

CLEANUP LEVEL IN TREATED MATERIAL

PARAMETER	TOTAL CONCENTRATION IN TREATED MATERIAL	TCLP EXTRACT LIMIT
[Arsenic	[____] mg/kg	[____] mg/l]
[Cadmium	[____] mg/kg	[____] mg/l]
[Chromium	[____] mg/kg	[____] mg/l]
[Lead	[____] mg/kg	[____] mg/l]

TABLE 1
POST TREATMENT CRITERIA

CLEANUP LEVEL IN TREATED MATERIAL

PARAMETER	TOTAL CONCENTRATION IN TREATED MATERIAL	TCLP EXTRACT LIMIT
[Pentachlorophenol	[] mg/kg	[] mg/l]
[1,4-Dichlorobenzene	[] mg/kg	[] mg/l]
[PCBs	[] mg/kg]	
[Radium	[] pCi/g]	

1.4.4 Cut Size Requirement

NOTE: This paragraph should be deleted if removal of contaminants is not dependent upon separation of contaminated fine particles (i.e., entirely due to solubilization or other removal techniques). This paragraph provides options for either the design engineer to specify or the Contractor to choose the cut size requirements. The feed materials at a given site may have different physical and chemical characteristics. Therefore, during soil washing treatment, different cut sizes may be used so that the treated materials will meet the post treatment criteria. If the design engineer chooses to specify the cut size and if treatment involves a variety of cut sizes, then the different cut sizes should be specified for different feed materials in this paragraph.

Cut size is the targeted grain size used to define the demarcation of the coarse and fine fractions of the feed materials to be separated during the soil washing operation. [The feed materials shall be treated to meet the post treatment criteria by using a cut size of no greater than [] micron in the soil washing treatment.] [Each cut size shall be based on the treatability study results so that the treated materials will meet the post treatment criteria with minimum generation of process sludge. Each selected cut size with supporting documentation shall be submitted for review prior to implementation. The supporting document shall include information correlating contaminant concentrations for the various size fractions based on the grain size distribution.]

1.4.5 Installation Requirements

The treatment plant shall be installed in accordance with applicable action-specific and location-specific federal, state, and local regulations. If the technical specifications overlook and/or conflict with the applicable codes, standards, and/or regulations, the Contracting Officer shall be informed and consulted for interpretation.

1.4.6 Results of Previously Conducted Treatability Studies

NOTE: This paragraph should be deleted if no

previous treatability studies have been conducted.

The unit processes/operations employed in the previous treatability studies (bench and/or pilot scale) may not be the same as those proposed by the Contractor. Documentation of the previous treatability studies should provide prospective contractors with sufficient information to prepare a detailed proposal and should include the testing materials, procedures and conditions, sampling and analytical methods, evaluation, and results.

The previously conducted treatability study documents in Appendix [_____] are for information purposes only. The results indicate that soil washing is capable of meeting the post treatment criteria identified in this section. However, the Contractor shall perform an independent evaluation of these studies and results. If deemed necessary, additional studies shall be performed at the Contractor's own expense to confirm the previously conducted treatability studies and results. Based on the Contractor's own interpretation of the previous studies and results [and the Contractor's own studies and results], the Contractor shall provide a full scale treatment plant which meets the requirements identified in this section.

1.4.7 Utilities

NOTE: The locations and details (such as utility point of contact, sizes, capacities, and flows) of the utility hookups should be provided on the drawings for the Contractor's use.

The Contractor shall provide the utilities associated with the installation and operation of the treatment plant including, but not limited to: telephone, electricity, water, [steam,] [gas,] [____], sanitary, and solid waste facilities. The [telephone] [electricity] [steam] [water] [gas] [sanitary] and [solid waste facilities] [____] are available at the site. [Refer to the drawings for hookup locations and other details.]

1.4.8 Spent Washwater Treatment and Disposal Requirements

NOTE: These paragraphs provide the generic requirements for wastewater treatment and disposal, solid waste treatment and disposal, and emission and dust control. These paragraphs should be modified based on the site specific design of the soil washing treatment plant and regulatory requirements.

The spent washwater should be treated if necessary and reused or treated for offsite disposal.

Modify this paragraph to reflect the following site-specific requirements.

If a performance specification is prepared, the treatment and disposal requirements should be

specified based on the conceptual/process design and applicable regulations. Table 2 should be presented to list the disposal/discharge criteria for the contaminants of concern in accordance with regulatory requirements. If the specification is prepared based on detailed design, the detailed design requirements describing the treatment and disposal scenario as well as the unit processes/operations employed should also be specified.

Spent washwater should be characterized to determine whether it constitutes a RCRA hazardous waste in accordance with RCRA Identification and Listing of Hazardous Wastes or applicable state regulations. The "derived-from" rule requires treatment residues from the treatment of RCRA listed waste to be managed as listed waste. If the spent washwater is classified as a hazardous waste, a determination should be made as to whether additional treatment is required to comply with LDRs. In addition, the requirements in RCRA Standards for Generators of Hazardous Waste and applicable state regulations should be identified and satisfied.

If other wastewaters are treated along with the spent washwater, they should be mentioned in this paragraph. These wastewaters may include, for example, the rainfall run offs from the stockpiles of feed oversize, feed materials, treated materials, and process sludge; and the wastewaters generated from onsite treatment of feed oversize, process sludge, and/or spent process treatment material.

The Contractor shall characterize the spent washwater. The spent washwater shall be recycled and/or treated for reuse whenever possible, to minimize the amount of wastewater requiring treatment and disposal. The spent washwater shall meet the criteria presented in Table 2 at the time of [disposal] [discharge]. The Contractor shall modify Table 2 [in the proposal] [and] [_____] in the Work Plan to address additional requirements such as changes to spent washwater characteristics requiring additional treatment or a change in the [disposal] [discharge] criteria.

TABLE 2
SPENT WASHWATER DISPOSAL/DISCHARGE CRITERIA

PARAMETER	DISPOSAL/DISCHARGE CRITERIA
[Arsenic	[_____] mg/l]
[Cadmium	[_____] mg/l]
[Chromium	[_____] mg/l]
[Lead	[_____] mg/l]
[Pentachlorophenol	[_____] mg/l]
[1,4-Dichlorobenzene	[_____] mg/l]
[PCBs	[_____] mg/l]
[Radium	[_____] pCi/l]

1.4.9 Solid Waste Treatment and Disposal Requirements

NOTE: Solid wastes generated during the plant operation may include feed oversize, process sludge, and/or spent process treatment material.

One treatment and disposal scenario for each of these solid wastes should be clearly defined.

If a performance specification is prepared, the treatment and disposal requirements should be specified based on the conceptual/process design. Table 3 should be presented to list the disposal criteria for the contaminants of concern for each of the solid wastes. The applicable federal, state, and local regulations specifically related to the site should be identified. If the specification is prepared based on detailed design, the description of the treatment and disposal scenario as well as the individual treatment components should also be specified.

If secondary solid, liquid, and gaseous wastes are generated by onsite treatment, their treatment and disposal requirements should be addressed in the same manner as the solid, liquid, and gaseous wastes generated by the treatment plant. If the liquid wastes are treated along with the spent washwater, their treatment and disposal requirements should be addressed in the paragraph entitled Spent Washwater Treatment and Disposal Requirements. Similarly, the gaseous wastes can also be addressed in the paragraph entitled Emissions and Dust Control Requirements.

The solid wastes shall be characterized. The [feed oversize removed from the raw contaminated materials] [process sludge generated from treatment of spent washwater] and [spent process treatment material] [_____] from installation, operation and closure of the treatment plant shall be properly treated and/or disposed of. Spent process treatment material is the process treatment material for which the capacity to remove contaminants from the contaminated medium in a treatment process has been used or exhausted. Solid waste disposal shall meet the criteria presented on Table 3. The Contractor shall propose modifications to Table 3 to address solid wastes generated by the soil washing treatment plant with characteristics which necessitates additional treatment, and/or disposal requirements be attained. These additional requirements shall be addressed [in the proposal] [and] [_____] in the Work Plan.

TABLE 3
SOLID WASTE DISPOSAL CRITERIA

PARAMETER	DISPOSAL CRITERIA	
	CONCENTRATION LEVEL IN TREATED SOLID WASTE	TCLP EXTRACT LIMIT
[Arsenic	[] mg/kg	[] mg/l]
[Cadmium	[] mg/kg	[] mg/l]
[Chromium	[] mg/kg	[] mg/l]
[Lead	[] mg/kg	[] mg/l]
[Pentachlorophenol	[] mg/kg	[] mg/l]
[1,4-Dichlorobenzene	[] mg/kg	[] mg/l]
[PCBs	[] mg/kg]	
[Radium	[] pCi/g]	

1.4.10 Emissions and Dust Control

NOTE: An air pathways analysis should be performed during design in accordance with EP 1110-1-21 Air Pathway Analysis for the Design of Hazardous, Toxic and Radioactive Waste (HTRW) Remedial Action Projects. Depending upon the contaminants of concern in the contaminated materials, the unit processes/operations employed in the treatment plant, the amount of pollutants emitted, and the geographical location of the site, the emission standards and limitations for certain contaminants and dust control can be identified from the following regulations including, but not limited to, National Primary and Secondary Ambient Air Quality Standards, National Emission Standards for Hazardous Air Quality Pollutants, and state and local regulations.

Based on the regulatory requirements, the proper technologies or apparatus for the emissions control if required can be determined. Upon completion of the design of the treatment plant, these emission requirements and control technologies should be defined by the design engineer.

Modify this paragraph to reflect the following site-specific requirements.

If a performance specification is prepared, the emissions, dust sources, and contaminants of concern should meet specified requirements based on applicable regulations. Table 4 should list the emissions criteria for the contaminants of concern for each emission and dust source, and if applicable, monitoring requirements should be specified. The applicable federal, state, and local regulations should also be identified. If the specification is prepared based on detailed design,

the technologies or apparatus for controlling the emissions and dust sources should also be specified.

The emissions and dust sources shall be characterized. The emissions shall meet the criteria presented in Table 4. The monitoring requirements for emissions and dust control shall be developed in accordance with the environmental compliance required by the regulatory agencies and the health and safety requirements. They shall be implemented during the installation and operation of the treatment plant to ensure compliance. The Contractor shall modify Table 4 [in the proposal] [and] [_____] in the Work Plan to address treatment plant emissions sources, dust sources, and control technologies, which differ from those presented in Table 4.

TABLE 4
AIR EMISSIONS CRITERIA

PARAMETER	EMISSIONS CRITERIA
_____	_____
[_____]	[_____]

1.4.11 Noise Control

NOTE: Based on the geographical location of the site, and the land uses and environment surrounding the site, the site-specific noise level requirements for the day and night operations and monitoring requirements can be identified from the state and local regulations and/or developed by interacting with the state and local agencies. These requirements should be specified in this paragraph.

The treatment plant shall meet the state and local noise pollution control regulations. The monitoring requirements for noise control shall be developed in accordance with the environmental compliance required by the regulatory agencies. Noise control requirements shall be implemented during the installation, operation, and closure of the treatment plant.

1.4.12 Sampling, Monitoring, and Control Requirements

NOTE: The process and waste generation data storage requirements should be specified based on the quantity, frequency, and requirement of data reduction and analysis for a specific project.

The treatment plant shall have the appropriate sampling and monitoring equipment for controlling the performance of the treatment processes and for complying with design and regulatory requirements. The monitoring and control equipment for the treatment processes shall have the necessary accuracy and sensitivity to measure and control the operating ranges for system parameters such as [materials feed rate] [washwater flow rate] [pH] [contact time] [cut size] [_____] so that the treatment plant can perform to its designed capacity, efficiency, and reliability. The unit operations of the treatment plant shall be complete with required instruments,

controls, and local control panels. A main control center shall be provided to facilitate the overall control of the treatment plant. The signal transmission to and from the main control center shall be [4-20 mA] [____]. The process and waste generation data shall be maintained in the main control center and recorded on [magnetic tapes] [discs] or [____].

1.4.13 Contaminated Material Measurement Accuracy Requirements

Scales, meters, and volumetric measuring devices for measuring feed oversize, feed materials, reagents, and water shall have an accuracy of plus or minus [0.5] [____] percent of the quantity being measured. Scales shall be calibrated at least once every 5 working days.

1.4.14 Mobilization

The treatment plant shall not mobilize to the site until the Work Plan has been approved by the Contracting Officer or Designated Contracting Officer's Representative and the Contractor has received written confirmation. The Contractor's mobilization plan shall include, but not be limited to, preparation, arranging, and/or transportation of personnel, material, and equipment; and connecting supporting utilities for installation and operation of the treatment plant. Delays caused by the Contractor's failure to meet regulatory requirements shall result in no additional cost to the Government. The equipment which is rented and/or previously used for other site remediation shall be decontaminated and tested for contaminants of concern before being brought to the site.

1.4.15 Demobilization

Demobilization shall begin only after the contaminated materials, spent washwater, and solid wastes have been treated and disposed of in accordance with the post treatment criteria listed in Table 1, the disposal/discharge criteria in Table 2, and the disposal criteria in Table 3, respectively. Demobilization shall include disconnecting and removal of utility service lines, decontamination of equipment and the treatment plant area, disposal of decontamination wastes, disposal of spent washwater left from operation of the treatment plant, removal of the unused reagents/additives and the equipment associated with the treatment plant, and [demolition and disposal of foundation slab] [____]. [Post treatment testing shall also be performed after demobilization to verify that the area associated with soil washing treatment operations is not contaminated. The soils in the area shall meet the post treatment criteria listed in Table 1] [____].

1.5 QUALIFICATIONS

NOTE: Requirements for the Contractor's experience should be determined and specified based on the experience, availability, and advancement of the soil washing technology industry and the site-specific requirements.

The Contractor shall demonstrate capabilities and experience adequate to configure, install, and operate a soil washing treatment plant to remediate the contaminated materials. The Contractor shall demonstrate a minimum of [3] [____] years of experience in the field of soil washing and/or the successful completion of [at least [1] [____] soil washing project of comparable size and scope] [at least [3] [____] soil washing pilot scale

treatability studies, demonstration studies, and/or full scale remediation projects that required handling and transportation of soils contaminated with [RCRA hazardous wastes] [CERCLA hazardous material] [_____]]. The Contractor shall provide a field team (consisting of soil washing unit operators, quality control personnel, health and safety personnel, supervisory engineering, and technical staff) qualified to install and operate the treatment plant.

1.6 DELIVERY, STORAGE, AND HANDLING

The equipment, raw materials (including reagents/additives), contaminated materials, and treated materials shall be safely transported, stored, and handled. Packaging and shipping of these items shall be in compliance with United States Department of Transportation (USDOT) requirements. Storage and handling of these items onsite shall be in accordance with the manufacturer's recommendations and in compliance with applicable regulatory requirements.

1.7 SITE CONDITIONS

NOTE: The pertinent site characterization data should be placed in the appendices of the technical specifications or on the drawings, and referenced here. If the site contains a significant amount of debris (feed oversize), the available information about its extent and characterization should also be provided. Indicate the detail to which site characterization has been performed and indicate where obvious data gaps exist. The information should also include construction limits, property utilities, chemical data, geotechnical data, sampling locations and boring logs.

The site investigation data presented is representative of surface and subsurface conditions at a specific location; variations in the contaminated materials could occur.

1.7.1 Environmental Requirements

NOTE: When temperature is below the freezing point, the treatment plant equipment may not function properly or efficiently. Frozen materials can make excavation, conveying, screening, and blending operations difficult and less cost-effective. The general practice is to avoid the operation of an outdoor treatment plant during the extreme winter weather. In places where there is a long winter season or in projects where the plant operation is required throughout the year to meet the project schedule, it may be necessary to perform soil washing inside a temporary building with proper heating and ventilation. Use of UFGS should address only the minimal requirements to satisfy the temporary construction.

1.7.2 Existing Conditions

NOTE: The information presented in Table 5 and in the Appendix should also include other information such as chemical data, geotechnical data, sampling locations, and boring logs. The information presented in Table 5 can be presented either in tabular form or on the drawings.

TABLE 5
NATURE AND EXTENT OF CONTAMINATION

1. Contaminated zones are defined on the Drawings [_____].
2. Area in square m yd.
3. Depth in m ft.
4. Volume in cubic m yard.

SECTION 02151 Page 23

configuration. Discrepancies between the data presented and field conditions discovered during the initial trial/startup period shall be brought to the Contracting Officer's attention immediately.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Water Supply

Water shall not contain oils, acids, salts, alkalis, organic matter, solids or other substances that could be detrimental to the successful treatment of the contaminated materials; the Contractor shall submit a Water Supply Analysis as specified in the Submittals paragraph.

2.1.2 Reagent/Additive Certificates of Analyses

The treatment plant may use reagents/additives for formulation of washwater, treatment of spent washwater, control of air emissions, and treatment of solid wastes. The parameters for each reagent/additive to be provided shall include, but are not limited to, chemical formula, grade/purity, form, strength, and typical supplier. The residuals of these reagents/additives in the treated materials or the solid, liquid and gaseous wastes from the treatment plant shall not cause secondary contamination to the environment. A certificate of analysis for each of the reagents/additives shall be supplied by the vendor and shall accompany each shipment. Reagents/additives shall be shipped in properly labeled containers with instructions for handling and storage.

2.2 MIXES

The composition of washwater and the quantity ratios of washwater to feed materials shall be determined for the mixing and washing operations to achieve the required treatment results.

2.3 SAMPLES FOR TREATABILITY STUDIES

NOTE: This paragraph should be included if treatability studies are to be performed by the Contractor. Action level criteria should be specified for the purpose of collecting representative samples for treatability studies. Table 6 should be developed based on site-specific contaminants of concern and their corresponding action levels. Since the action level criteria are also applicable to excavation, coordination between this section and the section dealing with excavation and stockpiling should be made with respect to these criteria.

[The Contracting Officer will provide the required samples to the Contractor to conduct the treatability studies.] [The Contractor shall select sampling locations and collect representative samples to conduct the treatability studies. The existing site conditions presented in paragraph Existing Conditions shall be considered for selecting sampling locations. The collected treatability study samples shall have contaminant concentration levels [representative of the average concentration of the

contaminants identified] [and] [greater] [than the action level criteria presented] in Table 6. Otherwise, sampling shall be repeated until the contaminant concentration levels exceed the action level criteria. The Contractor shall coordinate the sampling protocol with the Contracting Officer before obtaining the samples.] Treatability studies shall not commence until soil samples meet the aforementioned concentration criteria. The treatability studies shall be conducted in accordance with EPA 540/2-91/020A and EPA 540/R-92/071a.

TABLE 6
ACTION LEVEL CRITERIA

PARAMETER	ACTION LEVEL CRITERIA
[Arsenic	[] mg/kg]
[Cadmium	[] mg/kg]
[Chromium	[] mg/kg]
[Lead	[] mg/kg]
[Pentachlorophenol	[] mg/kg]
[1,4-Dichlorobenzene	[] mg/kg]
[PCBs	[] mg/kg]
[Radium	[] pCi/g]

PART 3 EXECUTION

3.1 EXAMINATION

A pre-installation examination of the treatment plant equipment for any damage, defect, and dilapidation shall be conducted. The results of the pre-installation examination shall be documented and submitted to the Contracting Officer for review and information. Upon completion of the treatment plant installation, a pre-operational test of the equipment and controls shall be performed under operating conditions using clean water to check for leaks and continuity. The Contracting Officer's Representative will conduct an independent examination to ascertain the condition and functionality of the equipment. Based on this examination, the Contracting Officer has the right to reject the entire system or any damaged, defective or dilapidated equipment. The cost associated with equipment or control replacement or repair, and delays caused by the rejection shall be borne by the Contractor.

3.2 PREPARATION

3.2.1 Stockpiles of Contaminated Materials

NOTE: Background sampling under the stockpiles of contaminated materials should be performed before their construction, unless previous information is adequate. Coordinate with Section 02111 EXCAVATION AND HANDLING OF CONTAMINATED MATERIAL.

The clearing and grubbing as well as excavation shall be performed in accordance with Section 02111 EXCAVATION AND HANDLING OF CONTAMINATED MATERIAL. Stockpile storage areas for feed oversize, feed materials, treated materials, process sludge and [] shall be constructed. [One]

[_____] composite surface background sample shall be taken from the stockpile areas prior to their construction to document the level of contamination present at the onset of construction [_____] . Contamination under stockpile areas resulting from remedial action activities shall be cleaned up to [action] [background] levels at the Contractor's expense. The following minimum requirements shall be incorporated in the stockpile design:

3.2.1.1 Liner

NOTE: The liner is not always necessary and should be deleted if not required. If the liner is required, then reference separate section to address installation and construction of the liner.

A [geomembrane] [_____] liner shall be used under the stockpiles to prevent the release of contaminated leachate to the environment. The construction and installation of the liner shall conform to the manufacturer's requirements. The minimum thickness of the liner shall be [1 mm 40 mils] [_____] . [Liner shall be as specified in Section [_____] .]

3.2.1.2 Cover

NOTE: This paragraph will be included if an impermeable synthetic cover is considered necessary.

A [geomembrane] [_____] (reinforced ultra-violet stabilized polyethylene) cover shall be used to prevent precipitation from entering a stockpile and volatile emissions and dust from escaping. [The cover shall not be used during active plant operation.] Control measures such as wetting the stockpile surfaces shall be employed to suppress dust. The minimum thickness of the cover shall be [0.25 mm 10 mils] [_____] .

3.2.1.3 Diversion Measures

Berms, a minimum of [[300] [_____] mm [12] [_____] inches] in height and/or other suitable diversion measures (such as drainage swale) shall be constructed around the stockpiles to prevent run on and run off.

3.2.1.4 Stockpile Leachate

NOTE: Leachate may not need treatment. If treatment is needed, it can be treated and disposed of at an offsite facility or treated along with the spent washwater for reuse, discharge, and/or offsite disposal. If the leachate is classified as a derived waste from a listed hazardous waste, it should be contained and then characterized.

Coordinate this paragraph with requirements in paragraph Spent Washwater Treatment and Disposal Requirements. Typically, water will be treated on a batch basis. If a continuous discharge is anticipated, modify the paragraph accordingly and

include sample type and frequency.

The Contractor shall characterize the leachate collected from the stockpiles to determine the need for treatment prior to reuse in the soil washing process. The Contractor shall not discharge the leachate to the environment, or transport it offsite for disposal prior to analyzing for and meeting the discharge requirements in paragraph SPENT WASHWATER TREATMENT AND DISPOSAL REQUIREMENTS. The vessel, impoundment, [____], storing the leachate shall be tested prior to emptying that storage facility. No leachate shall be added to a storage facility after a sampling event until the unit is emptied. For discharge or offsite disposal, the applicable Federal, state, and local regulatory requirements shall be met.

3.2.2 Foundations

NOTE: Minimum requirements should be specified for the foundation/containment area of the treatment plant. Depending upon the duration of soil washing treatment, the weight support requirement of the plant, rainfall and equipment washdown water collection requirements, the foundation to be employed can range from a simple foundation consisting of synthetic liner, sand, and/or gravel, to a concrete slab. For a long term project, large project, or a project handling multiple soil fractions, a concrete or asphalt pad should be provided for the treatment plant.

Suitable foundations (ranging from a simple foundation consisting of synthetic liner, sand and or gravel, to an asphalt or a concrete slab) shall be constructed to support and accommodate the treatment plant. Concrete shall be proportioned in accordance with Section 03300A CAST-IN-PLACE STRUCTURAL CONCRETE. The area around the soil washing equipment shall be graded so that the water drains away from the work area adjacent to the treatment area. Water collected shall be recycled or properly treated for disposal.

3.3 ERECTION, INSTALLATION, AND DEMOBILIZATION

NOTE: Referenced UFGS should be edited to include only the minimum requirements applicable to a temporary installation.

The treatment plant shall be erected and installed on a temporary basis and shall be removed from the site after completion of the contract work. The erection and installation shall be performed such that there is minimal damage to the existing site environment. [The mechanical work shall conform to the requirements of Section [____]]. The electrical work shall conform to the requirements of Sections [16370A ELECTRICAL DISTRIBUTION SYSTEM, AERIAL] [16375A ELECTRICAL DISTRIBUTION SYSTEM, UNDERGROUND] [____], and [Section 16402 INTERIOR DISTRIBUTION SYSTEM]. The plumbing work shall conform to the requirements of [Section 15400A PLUMBING, GENERAL PURPOSE] [Section 15200 PIPELINES, LIQUID PROCESS PIPING] [____].

3.4 OPERATION

3.4.1 Different Types of Contamination and Materials

Different types of contamination, materials, and resulting waste streams shall be treated separately if the testing results indicate that different operating conditions of the treatment plant have to be implemented in order to achieve effective treatment of these materials.

3.4.2 Stockpile Management

NOTE: Sampling location, contaminant type, and sampling frequency should be presented for each feed type and/or treated material/sludge. A format similar to Tables 1 and 2 should be used. During the design, the design engineer should interact with the regulatory agencies to determine the requirements pertaining to the type of storage facility, accumulation time, and permitting for feed oversize, feed materials, treated materials, and process sludge for incorporation into the related subparagraphs.

The different materials generated by the treatment plant shall be stockpiled separately as specified below. The wastewater, solid wastes, and dust generated during stockpile management shall be handled as specified in Paragraph SYSTEM DESCRIPTION. The stockpiles shall be managed so no contaminants or fine particles are released into the environment. Run on and run off water shall be controlled in the stockpile areas. The rainfall run off and any leachate material from the stockpile areas shall be collected and treated for discharge/disposal or used for make up water in the treatment plant.

3.4.2.1 Feed Oversize

The feed oversize stockpiles shall be treated (if required) and disposed of according to their waste classification and accumulated quantities.

3.4.2.2 Feed Material

The feed material stockpiles shall be limited to a quantity capable of sustaining [5] [_____] days operation of the treatment plant.

3.4.2.3 Treated Materials

Treated materials shall be segregated into units (stockpiles) on a [daily] [_____] basis for post treatment testing. If the test results indicate the treated materials of a stockpile meet the post treatment criteria presented in Table 1, this stockpile of treated materials shall be combined with the stockpile of previously treated clean materials awaiting backfilling. Treated materials that do not meet the post treatment criteria in Table 1 shall be reprocessed by the treatment plant.

3.4.2.4 Process Sludge

The process sludge stockpiles shall be treated (if required) and disposed

of in a cost effective manner, according to their waste classification and quantities accumulated.

3.4.3 Auxiliary Requirements for System Operations

All required spare, auxiliary, and support equipment, such as a portable generator to provide emergency power for lighting, controls, and computer system operation [,_____] shall be provided.

3.4.4 Management of Reagents/Additives

Sufficient quantities of the required reagents/additives shall be stored in the plant area to support the operation of the treatment plant. The reagents/additives shall be stored in accordance with manufacturer's instructions and regulatory requirements. The reagent/additive holding times shall not be exceeded.

3.4.5 Change of Operating Conditions

NOTE: If adjustment to the mix design is required due to change in feed material characteristics, then the Contractor's adjusted mix design should be evaluated by the Contracting Officer for the extent of changes from the previous mix design. Further, price negotiation may be required based on the extent of changes from the previous mix design.

The following two requirements shall be met in order to be considered for change of operating conditions: (1) the physical and chemical characteristics of the contaminated materials are significantly different from the originally defined characteristics, and (2) the treatment requirements cannot be met under the current treatment plant mix design and related operating conditions. When change of operating condition is necessary, the Contractor shall notify the Contracting Officer before changes are made to the mix design and related operating conditions. The Contracting Officer may require the Contractor to perform a field demonstration for significant changes made to the mix design and related operating conditions in accordance with paragraph DEMONSTRATION, for approval. Changes to mix design and associated time and costs shall be accomplished at no additional cost to the Government.

3.4.6 Management of Treatment Plant Wastewater

The wastewater generated by the unit operations of the soil washing treatment plant shall be recycled and/or reused to the maximum extent for plant operations in order to minimize the need for new makeup water and limit the treatment, discharge, and/or offsite disposal of wastewater. If a wastewater treatment system (including the Spent Washwater Treatment System) is provided, it shall have the capacity and capability to treat the wastewater (including collected rainfall run offs) for recycle or reuse. Wastewater discharged to the environment, or sent to an offsite treatment facility shall comply with the requirements identified in paragraph SPENT WASHWATER TREATMENT AND DISPOSAL REQUIREMENTS.

3.4.7 Equipment Inspection and Maintenance

The equipment shall be properly and routinely inspected and maintained to

provide the operation of the treatment plant as required by the contract schedule. Any schedule delay and cost associated with power failure, line plugging, improper functioning of equipment and controls, unavailability of labor and materials, etc., shall be the responsibility of the Contractor. The Contractor is also responsible for providing alternate/auxiliary power source if sufficiently reliable source is not available.

3.4.8 Daily Operations Report

A daily operations report shall be submitted for review following each day's operation of the treatment plant. The daily operations report shall consist of a log of operating conditions including, but not limited to: hours of operation; staffing; weather conditions; noise, dust, and emissions monitoring data; process materials tracking schedule; sample shipment; receipt of analytical results; changes in operating parameters; results of the testing and calibration activities; and inspection and maintenance activities. In addition, physical and chemical test results generated onsite or received from offsite laboratories shall be attached to the report.

3.5 TESTS

NOTE: The amount of post treatment testing performed should be minimized. It is preferable to maintain quality control of the treatment plant by verifying the designed operating conditions during the field demonstration and by monitoring and controlling the operating parameters to achieve the designed performance.

3.5.1 Post Treatment Testing

NOTE: Time limits for sample shipment, analysis, and reporting of results should be selected based on the analytical costs and the management of stockpiles.

The shorter the turnaround time requested, the higher the analytical cost will be. In addition, there are time limits on how fast the requested analyses can be completed. Coordinate with the regulators and Section 01450A CHEMICAL DATA QUALITY CONTROL regarding the maximum quantity of material per composite sample. This will define the size of each stockpile, and the time required to reach this quantity. Coordinate requirements with paragraph STOCKPILE MANAGEMENT.

The feed oversize is generally handled by either onsite decontamination for backfilling or offsite disposal as hazardous wastes. The disposal of spent process treatment material such as activated carbon is generally negotiated as part of the suppliers contract and may not require post treatment testing. Therefore, only treated materials and the process sludge are addressed in this paragraph. Offsite

transportation and disposal of feed oversize, spent process treatment material, and process sludge require manifesting and record keeping for each material shipment.

One composite sample shall be collected from each stockpile for each [_____] [CM] [CY] of feed material treated and the process sludge generated. One composite sample shall be collected for each [_____] [CM] [CY] of oversize material generated. One composite sample shall be collected for each [_____] [CM] [CY] of sludge generated. The samples shall be sent to the laboratory for analysis via overnight shipment. The laboratory shall analyze the samples within [48] [_____] hours. The results of the analysis shall be telecopied or telephoned to the Contractor. The Contractor shall report the results to the Contracting Officer within [4] [_____] hours after receipt of the results. The treated material samples shall be analyzed for the parameters listed under post treatment criteria in Table 1. The process sludge samples shall be analyzed for the parameters specified in Table 3.

3.5.2 Reprocessing

Reprocessing and retesting shall be performed on the treated materials that do not meet the post treatment criteria listed in Table 1. The treated material which needs to be reprocessed shall be done at no additional cost to the Government. Treated materials that do not meet the post treatment criteria shall be [immediately reprocessed and retested] [stored separately while waiting for reprocessing and retesting].

3.5.3 Government Testing

The Contractor's sampling and analysis, as well as quality assurance laboratory requirements shall be as indicated in Section 01450A CHEMICAL DATA QUALITY CONTROL.

3.6 GOVERNMENT INSPECTION

The Government will conduct inspection of the system installation and perform periodic inspections during the plant operation to verify that the project activities are performed in accordance with the approved plans, specifications, and the regulatory requirements. Inspection findings shall be addressed immediately and resolved to the Government's satisfaction.

3.7 DEMONSTRATION

3.7.1 Field Demonstration

NOTE: The contract should contain provisions for issuing a second notice (or third notice in project where treatability studies are performed) to proceed by Contracting Officer upon approval of the field demonstration.

This paragraph is prepared based on a continuous operation of the treatment plant. If the treatment plant is operated as a batch process, the requirements on the minimum operation time and the sample frequency should be modified accordingly.

Prior to full scale soil washing operations, a field demonstration shall be performed at the full scale throughput capacity to verify the performance of the treatment plant. Preliminary tests and system checkout shall be performed prior to the field demonstration in order to minimize problems during the field demonstration. Each field demonstration run shall be conducted for a minimum period of [8] [_____] hours per day for at least [2] [_____] days. During the demonstration run, [composites samples] [_____] shall be taken every [2] [_____] hours from the feed materials, [feed oversize] [_____] , spent washwater, effluent from treatment of spent washwater, treated materials, process sludge, and the other locations necessary to perform mass balance calculations. The samples shall be analyzed for the purpose of performing mass balance calculations and to evaluate compliance with regulatory requirements. The Contractor shall allow [10] [_____] working days in the schedule for Government review and approval of the field demonstration report. A field demonstration run shall be performed on each distinctive type of material or contaminant which requires a substantial change in treatment plant operating conditions.

3.7.2 Full Scale Processing Equipment

The full scale treatment plant shall be utilized for the field demonstration. The operating conditions used during the field demonstration shall be the same as those proposed for use during the remediation.

3.7.3 Sampling Locations

NOTE: Specify each location and depth at which contaminated material samples for the field demonstration will be obtained. A separate table listing minimum concentrations of specific contaminants may be inserted if desired.

Contaminated materials used for the field demonstration shall be obtained [as directed by the Contracting Officer] [_____] . In order to be sure that the contaminated materials are appropriate for use in the field demonstration runs, [1] [_____] initial composite sample for chemical analysis per demonstration run shall be performed on the contaminated materials to verify the average contaminant concentration levels are representative of the average contaminant concentrations at the site [and exceed the action level criteria listed in Table 6] [_____] . A composite sample representing the minimum period identified in paragraph FIELD DEMONSTRATION.

3.7.4 Testing

Testing shall be performed to verify that the treated materials from the field demonstration meets the post treatment criteria listed in Table 1. If the treated materials produced during the field demonstration do not meet the post treatment criteria, an equal quantity of the same type of material that failed shall be reprocessed, using properly modified operating conditions, until satisfactory results are obtained. The treated materials that failed the demonstration testing shall be returned to the contaminated materials stockpile for processing during remediation. Testing of the contaminated and the treated materials before and after

demonstration test runs shall be performed in accordance with the same testing protocol as proposed for the full scale operation.

3.7.5 Commencement of Full Scale Operation

NOTE: It is preferable to direct the Contractor to stop processing contaminated materials until results from the field demonstration testing indicate the Contractor's proposed operating conditions can successfully treat the contaminated materials.

Full scale operations shall not be initiated until written approval has been received from the Contracting Officer, and the following submittals have been approved: [soil washing work plan] [field demonstration report] [_____]. [After completion of the field demonstration, the Contractor may continue to process the contaminated materials. However, if test results indicate that treated materials do not meet the post treatment criteria listed in Table 1, the contaminated materials treated with the failed operating conditions shall be reprocessed at no additional cost to the Government.]

3.8 PROCESS MATERIALS MANAGEMENT

NOTE: Table 7 is an example and should be modified based on site-specific conditions and requirements.

Process materials tracking shall be performed during the operation of the treatment plant. The schedules for process materials tracking shall provide data and information to identify locations and quantities of materials at any given time. The tracking shall be performed on materials including, but not limited to, contaminated materials, feed oversize, feed materials, treated materials, treated clean materials, [_____], and process sludge. Tracking of each material shall start from the original source, continue through various stages of handling and treatment, and end at the ultimate disposal. The Contractor shall use Table 7 or other equivalent schedule approved by the Contracting Officer to perform the material tracking during operation. Table 7 shall be filled out for each material and each of the locations where this material is stockpiled or temporarily stored, including Stockpile Number. The completed tracking schedules shall be submitted to the Contracting Officer as part of the Daily Operations Report.

TABLE 7
SCHEDULE FOR PROCESS MATERIALS TRACKING
DURING SOIL WASHING OPERATION

MATERIAL: CONTAMINATED SOIL
LOCATION: STOCKPILE NO. CS-1

INPUT			OUTPUT			REMARKS
DATE/ TIME	FROM	QUANTITY	TO	QUANTITY	QUANTITY AT THE LOCATION	
4/15/98 8:00 AM	--	0	--	0	0	Excavation starts
10:00 AM	Excavation Area No. 1	54	--	0	54	
12:00 Noon	Same	54	Soil Preparation and Feed System	38	70	
2:00 PM	--	0	Same	38	32	

TABLE 7
SCHEDULE FOR PROCESS MATERIALS TRACKING
DURING SOIL WASHING OPERATION

MATERIAL: CONTAMINATED SOIL
LOCATION: STOCKPILE NO. CS-1

INPUT			OUTPUT			REMARKS
DATE/ TIME	FROM	QUANTITY	TO	QUANTITY	QUANTITY AT	
					THE LOCATION	
(QUANTITIES IN SHORT TONS)						
4/15/98 8:00 AM	--	0	--	0	0	Excavation starts
10:00 AM	Excavation Area No. 1	70	--	0	70	
12:00 Noon	Same	70	Soil Preparation and Feed System	50	90	
2:00	--	0	Same	50	40	

TABLE 7
SCHEDULE FOR PROCESS MATERIALS TRACKING
DURING SOIL WASHING OPERATION

MATERIAL: CONTAMINATED SOIL
LOCATION: STOCKPILE NO. CS-1

	INPUT			OUTPUT		
	<hr/>			<hr/>		
	(QUANTITIES IN SHORT TONS)					
DATE/ TIME PM	FROM	QUANTITY	TO	QUANTITY	QUANTITY AT THE LOCATION	REMARKS
						<hr/>

-- End of Section --