
USACE / NAVFAC / AFCEA UFGS-02111 (September 2003)

Preparing Activity: USACE Superseding
UFGS-02111 (September 2001)

GUIDE SPECIFICATION FOR CONSTRUCTION

References are in agreement with UMRL dated 22 December 2004

SECTION TABLE OF CONTENTS

DIVISION 02 - SITE CONSTRUCTION

SECTION 02111

EXCAVATION AND HANDLING OF CONTAMINATED MATERIAL

09/03

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 MEASUREMENT AND PAYMENT
 - 1.2.1 Measurement
 - 1.2.2 Payment
 - 1.2.2.1 Excavation and Transportation
 - 1.2.2.2 Backfilling
 - 1.2.2.3 Stockpiling
- 1.3 SUBMITTALS
- 1.4 SURVEYS
- 1.5 REGULATORY REQUIREMENTS
 - 1.5.1 Permits and Licenses
 - 1.5.2 Air Emissions
- 1.6 DESCRIPTION OF WORK
- 1.7 CHEMICAL TESTING
- 1.8 SCHEDULING

PART 2 PRODUCTS

- 2.1 BACKFILL
- 2.2 SPILL RESPONSE MATERIALS

PART 3 EXECUTION

- 3.1 EXISTING STRUCTURES AND UTILITIES
- 3.2 CLEARING
- 3.3 CONTAMINATED MATERIAL REMOVAL
 - 3.3.2 Excavation
 - 3.3.3 Shoring
 - 3.3.4 Dewatering
- 3.4 CONFIRMATION SAMPLING AND ANALYSIS
- 3.5 CONTAMINATED MATERIAL STORAGE
 - 3.5.1 Stockpiles
 - 3.5.2 Roll-Off Units

- 3.5.3 Liquid Storage
- 3.6 SAMPLING
 - 3.6.1 Sampling of Stored Material
 - 3.6.2 Sampling Liquid
 - 3.6.3 Sampling Beneath Storage Units
- 3.7 SPILLS
- 3.8 BACKFILLING
 - 3.8.1 Confirmation Test Results
 - 3.8.2 Compaction
- 3.9 DISPOSAL REQUIREMENTS
- 3.10 CLOSURE REPORT

-- End of Section Table of Contents --

USACE / NAVFAC / AFCEA UFGS-02111 (September 2003)

Preparing Activity: USACE Superseding
UFGS-02111 (September 2001)

GUIDE SPECIFICATION FOR CONSTRUCTION

References are in agreement with UMRL dated 22 December 2004

SECTION 02111

EXCAVATION AND HANDLING OF CONTAMINATED MATERIAL 09/03

NOTE: This guide specification covers the requirements for excavation, handling, and temporary storage of contaminated material.

Comments and suggestions on this guide specification are welcome and should be directed to the technical proponent of the specification. A listing of technical proponents, including their organization designation and telephone number, is on the Internet.

Recommended changes to a UFGS should be submitted as a Criteria Change Request (CCR).

Use of electronic communication is encouraged.

Brackets are used in the text to indicate designer choices or locations where text must be supplied by the designer.

PART 1 GENERAL

NOTE: The following information should be shown on the project drawings:

a. Overall site plan, borrow areas, stockpile areas, storage areas, security requirements, special shoring requirements, boring logs, and access routes.

b. Individual site plans of each area of contamination with site features such as buildings, roads, utilities, topography, trees, shrubs, surface conditions, etc.

c. Limits of pavement removal, fence removal, and the location of ancillary equipment to be removed.

All specific chemical testing procedures (including

air emissions analysis) should be addressed in the Sampling and Analysis Plan required by Section 01450 CHEMICAL DATA QUALITY CONTROL.

When applicable, the use of onsite field screening or field analysis (supported at a prescribed frequency by fixed laboratory analysis) should be encouraged to avoid prolonged delays or equipment downtime. Details on the appropriate application and use of field analyses can be found in Appendix H of EM 200-1-3.

1.1 REFERENCES

NOTE: Issue (date) of references included in project specifications need not be more current than provided by the latest guide specification. Use of SpecsIntact automated reference checking is recommended for projects based on older guide specifications.

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D 1556	(2000) Density and Unit Weight of Soil in Place by the Sand-Cone Method
ASTM D 1557	(2002e1) Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/cu. ft. (2,700 kN-m/cu.m.))
ASTM D 2167	(1994; R 2001) Density and Unit Weight of Soil in Place by the Rubber Balloon Method
ASTM D 2487	(2000) Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D 2922	(2004) Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
ASTM D 422	(1963; R 2002) Particle-Size Analysis of Soils
ASTM D 5434	(2003) Field Logging of Subsurface Explorations of Soil and Rock
ASTM D 698	(2000ae1) Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/cu. ft. (600 kN-m/cu. m.))

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1

(2003) Safety -- Safety and Health
Requirements

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1926

Safety and Health Regulations for
Construction

40 CFR 302

Designation, Reportable Quantities, and
Notification

1.2 MEASUREMENT AND PAYMENT

NOTE: These paragraphs should be deleted if the
work is in one lump-sum contract price. Coordinate
requirements of these paragraphs with the bidding
schedule.

1.2.1 Measurement

NOTE: Modify this paragraph if the method of
payment will be on a weight basis.

Measurement for excavation and on-site transportation shall be based on the actual number of cubic meters yards of contaminated material in-place prior to excavation. Determination of the volume of contaminated material excavated shall be based on cross-sectional volume determination reflecting the differential between the original elevations of the top of the contaminated material and the final elevations after removal of the contaminated material. Measurement for backfilling of excavated areas shall be based on in-place cubic meters yards of compacted fill. Measurement for construction of stockpile areas shall be based on the number of square meters yards of stockpile liner constructed.

1.2.2 Payment

1.2.2.1 Excavation and Transportation

Compensation for excavation and onsite transportation of contaminated material will be paid as a unit cost. This unit cost shall include any other items incidental to excavation and handling not defined as having a specific unit cost.

1.2.2.2 Backfilling

Compensation for backfill soil, transportation of backfill, backfill soil conditioning, backfilling, compaction, and geotechnical testing will be paid as a single unit cost.

1.2.2.3 Stockpiling

Compensation for construction of stockpile areas will be paid for as a unit cost. This unit cost shall include all aspects of grading, preparation,

handling, placement, maintenance, removal, treatment, and disposal of stockpile cover materials and liner materials and all other items incidental to construction of stockpiles.

1.3 SUBMITTALS

NOTE: Submittals must be limited to those necessary for adequate quality control. The importance of an item in the project should be one of the primary factors in determining if a submittal for the item should be required.

A "G" following a submittal item indicates that the submittal requires Government approval. Some submittals are already marked with a "G". Only delete an existing "G" if the submittal item is not complex and can be reviewed through the Contractor's Quality Control system. Only add a "G" if the submittal is sufficiently important or complex in context of the project.

For submittals requiring Government approval on Army projects, a code of up to three characters within the submittal tags may be used following the "G" designation to indicate the approving authority. Codes for Army projects using the Resident Management System (RMS) are: "AE" for Architect-Engineer; "DO" for District Office (Engineering Division or other organization in the District Office); "AO" for Area Office; "RO" for Resident Office; and "PO" for Project Office. Codes following the "G" typically are not used for Navy projects.

Submittal items not designated with a "G" are considered as being for information only for Army projects and for Contractor Quality Control approval for Navy projects.

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are [for Contractor Quality Control approval.] [for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government.] The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Surveys[; G][; G, [_____]]

Separate cross-sections of each area before and after excavation and after backfilling.

SD-03 Product Data

Work Plan[; G][; G, [_____]]

Work Plan within [30] [_____] calender days after notice to proceed. No work at the site, with the exception of site inspections and surveys, shall be performed until the Work Plan is approved. The Contractor shall allow [30] [_____] calender days in the schedule for the Government's review. No adjustment for time or money will be made if resubmittals of the Work Plan are required due to deficiencies in the plan. At a minimum, the Work Plan shall include:

- a. Schedule of activities.
- b. Method of excavation and equipment to be used.
- c. Shoring or side-wall slopes proposed.
- d. Dewatering plan.
- e. Storage methods and locations for liquid and solid contaminated material.
- f. Borrow sources and haul routes.
- g. Decontamination procedures.
- h. Spill contingency plan.

Closure Report[; G][; G, [_____]]

[_____] copies of the Closure Report within [14] [_____] calender days of work completion at the site.

SD-06 Test Reports

Backfill[; G][; G, [_____]]
Surveys[; G][; G, [_____]]
Confirmation Sampling and Analysis[; G][; G, [_____]]
Sampling of Stored Material[; G][; G, [_____]]
Sampling Liquid[; G][; G, [_____]]
Compaction[; G][; G, [_____]]

Test results.

1.4 SURVEYS

Surveys shall be performed immediately prior to and after excavation of contaminated material to determine the volume of contaminated material removed. Surveys shall also be performed immediately after backfill of each excavation. The Contractor shall provide cross-sections on [7.6] [_____] meter [25] [_____] foot intervals and at break points for all excavated areas. Locations of confirmation samples shall also be surveyed and shown on the drawings. Surveys shall be performed in accordance with Section: [_____] .

1.5 REGULATORY REQUIREMENTS

1.5.1 Permits and Licenses

NOTE: Include additional site specific requirements

in this paragraph.

The Contractor shall obtain required federal, state, and local permits for excavation and storage of contaminated material. Permits shall be obtained at no additional cost to the Government.

1.5.2 Air Emissions

NOTE: An air pathway analysis should be performed during design to determine what air monitoring and controls are required. Guidance on air pathway analyses is provided in EP 1110-1-21 Air Pathway Analysis for the Design of Hazardous, Toxic, and Radioactive Waste (HTRW) Remedial Action Projects. Specify perimeter air monitoring requirements in Section 01355 ENVIRONMENTAL PROTECTION.

Air emissions shall be monitored and controlled in accordance with Section 01355.

1.6 DESCRIPTION OF WORK

NOTE: Include any pertinent information regarding project/site conditions in this paragraph, the appendices to the specifications, or on the drawings.

If oversize material such as debris and foundations are present, the specification should describe treatment, handling, and disposal requirements for this material. Measurement and payment procedures should also be described for this material.

If clean soil overlies the contaminated material, the specification should describe how this material will be measured, removed, stored, and tested to verify they are clean.

The work shall consist of excavation and temporary storage of approximately [_____] cubic meters yards of contaminated material. Approximate locations of contaminated material are shown on the drawings. Characterization data on the nature and extent of the contaminated material is shown in Appendix [_____] Subsurface conditions are shown [on the drawings] [in Appendix [_____]]. The Contractor shall submit a Work Plan as specified in the Submittals paragraph. The Contracting Officer shall be notified within [24] [_____] hours, and before excavation, if contaminated material is discovered that has not been previously identified or if other discrepancies between data provided and actual field conditions are discovered. Backfill material is [not available onsite] [available onsite and typically consists of [_____]]. Ground water is approximately [_____] meters feet below pre-excavation ground surface.

1.7 CHEMICAL TESTING

Required sampling and chemical analysis shall be conducted in accordance

with Section 01450A CHEMICAL DATA QUALITY CONTROL.

1.8 SCHEDULING

The Contractor shall notify the Contracting Officer [_____] calendar days prior to the start of excavation of contaminated material. The [Contracting Officer will] [Contractor shall] be responsible for contacting regulatory agencies in accordance with the applicable reporting requirements.

PART 2 PRODUCTS

2.1 BACKFILL

NOTE: If contaminated material removal is part of a larger project and a backfilling specification is needed for the project as a whole, refer to another specification such as Section 02315 EXCAVATION, FILLING AND BACKFILLING FOR BUILDINGS for Buildings, for backfill requirements and delete the following paragraphs.

In many cases, the degree of engineering control of the materials used as backfill may not need to be as stringent as described in this paragraph. In other cases, such as under pavements, special compaction and material requirements may apply and the specification will need to be revised to address these special requirements or another specification section should be referenced.

Backfill and topsoil brought in from offsite is usually tested to verify the material is clean. Quality assurance samples taken by the Government may also be prudent to verify the seller's claims by analyzing for target analytes. Backfill is commonly tested for the site specific contaminants being cleaned up and/or is based on suspicion of contamination at the site from which the backfill is originating.

At some sites, previously contaminated material which has been removed from the excavation is reused as backfill following treatment to remove the contaminant of concern.

Backfill material shall be obtained from [the location indicated on the drawings] [offsite sources approved by the Contracting Officer]. Backfill shall be classified in accordance with ASTM D 2487 as GW, GP, GM, GC, SW, SP, SM, SC, ML, MH, CL, or CH and shall be free from roots and other organic matter, trash, debris, snow, ice or frozen materials. Backfill material shall be tested for the parameters listed below at a frequency of once per [3000] [_____] cubic meters yards. A minimum of one set of classification tests shall be performed per borrow source. [One] [_____] backfill sample per borrow source shall also be collected and tested for the chemical parameters listed below.

Physical Parameter	Criteria	Test Method
Grain Size	[_____]	ASTM D 422
Compaction	[_____]	ASTM D 698
[_____]	[_____]	[_____]

Chemical Parameter	Test Frequency	Criteria
[_____]	[_____]	[_____]

Backfill shall not be used until borrow source chemical and physical test results have been submitted and approved.

2.2 SPILL RESPONSE MATERIALS

The Contractor shall provide appropriate spill response materials including, but not limited to the following: containers, adsorbents, shovels, and personal protective equipment. Spill response materials shall be available at all times when contaminated materials/wastes are being handled or transported. Spill response materials shall be compatible with the type of materials and contaminants being handled.

PART 3 EXECUTION

3.1 EXISTING STRUCTURES AND UTILITIES

No excavation shall be performed until site utilities have been field located. The Contractor shall take the necessary precautions to ensure no damage occurs to existing structures and utilities. Damage to existing structures and utilities resulting from the Contractor's operations shall be repaired at no additional cost to the Government. Utilities encountered that were not previously shown or otherwise located shall not be disturbed without approval from the Contracting Officer.

3.2 CLEARING

NOTE: Grubbing is typically not required at sites where contaminated soil is being excavated for treatment and/or disposal. Typically, vegetation that is cut off above a certain height is defined as clean and any stumps and brush below this height are defined as contaminated.

Clearing shall be performed to the limits shown on the drawings in accordance with Section 02231 CLEARING AND GRUBBING.

3.3 CONTAMINATED MATERIAL REMOVAL

NOTE: Excavations should be marked and secured in accordance with the requirements specified in Section 01351 SAFETY, HEALTH, AND EMERGENCY RESPONSE (HTRW/UST).

3.3.2 Excavation

NOTE: For large excavations, more than one
excavation log may be required.

Areas of contamination shall be excavated to the depth and extent shown on the drawings and not more than [60] [_____] mm [0.2] [_____] feet beyond the depth and extent shown on the drawings unless directed by the Contracting Officer. Excavation shall be performed in a manner that will limit spills and the potential for contaminated material to be mixed with uncontaminated material. An excavation log describing visible signs of contamination encountered shall be maintained for each area of excavation. Excavation logs shall be prepared in accordance with ASTM D 5434.

3.3.3 Shoring

If workers must enter the excavation, it shall be evaluated, shored, sloped or braced as required by EM 385-1-1 and 29 CFR 1926 section 650.

3.3.4 Dewatering

NOTE: Dewatering can significantly increase the
cost of a project involving the excavation of
contaminated material and should be carefully
considered during design. TM 5-818-5 Dewatering and
Groundwater Control provides guidance on the design
of dewatering systems.

If water from dewatering operations will be allowed
to discharge on or into the ground, an NPDES permit
for dewatering is required. Reference the permits
paragraph of Section 01355 ENVIRONMENTAL PROTECTION
for permit requirements.

Surface water shall be diverted to prevent entry into the excavation.
[Dewatering shall be limited to that necessary to assure adequate access, a
safe excavation, prevent the spread of contamination, and to ensure that
compaction requirements can be met.] [No dewatering shall be performed
without prior approval of the Contracting Officer.]

3.4 CONFIRMATION SAMPLING AND ANALYSIS

NOTE: Confirmation samples and analyses are used to
verify cleanup criteria have been met. These test
results should be of relatively high quality. For
this reason, the designer should consider the
regulatory requirements, the complexity of the
monitoring needed, and quantitative Data Quality
Objectives in determining the analytical methods
specified.

The number of confirmation samples must be based on
the size of the excavation and regulatory
requirements. For small excavations, a minimum of

one sample should be taken from near the center of the excavation (or where there is the highest potential for contamination). Additional samples may be oriented symmetrically relative to the center sample and the limits of the excavation.

Many military facilities have base-wide sampling and analysis plans which have been approved by the applicable regulatory agencies. These plans may specify the number of confirmation samples which must be taken.

For larger excavations, EPA 230/02-89-042 Methods of Evaluation and Attainment of Cleanup Standards provides guidance on the design of statistically based sampling intervals.

With regulator approval, confirmation sampling and analysis may be accomplished using an averaging technique for comparison to cleanup criteria. This is based on the fact that most soil risk exposure scenarios do not model contamination as existing in discrete hot spots but as a more disperse phenomenon. Two ways to accomplish this averaging technique are to take discrete samples and average the data or by compositing sample material before analysis. A composite sample typically consists of 4 to 6 samples which are mixed together. One sample is then obtained from the composite sample for analysis. EM 200-1-3 provides guidance on compositing samples. Composite samples are not applicable to volatile organic contaminants because the compositing process will result in volatilization of contaminants. If composite samples are required, Section 01450 CHEMICAL DATA QUALITY CONTROL should be edited by a qualified chemist to describe procedures for compositing samples.

Confirmation sampling at a site with radioactive contamination in surface soils or on building surfaces will be performed in accordance with the Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM), NUREG-1575, EPA 402-R-97-016. This manual is a guide for confirmation survey design (planning) and for data evaluation. Its primary purpose is to acquire legally defensible data concerning the post excavation residual radioactivity at the site to demonstrate that the site meets release criteria.

The Contracting Officer shall be present to inspect the removal of contaminated material from each site. After all material suspected of being contaminated has been removed, the excavation shall be examined for evidence of contamination. If the excavation appears to be free of contamination, field analysis shall be used to determine the presence of [_____] contamination using [a real time vapor monitoring instrument] [immunoassay field kits] [_____]. Excavation of additional material shall

be as directed by the Contracting Officer. After all suspected contaminated material is removed, confirmation samples shall be collected and analyzed for the following contaminants:

Chemical Parameter	Action Level
[_____]	[_____]

Samples shall be collected at a frequency of one per [_____] square meters yards from the bottom [and each of the side walls] or as directed by the Contracting Officer. A minimum of one sample shall be collected from the bottom [and each side wall] of the excavation. Based on test results, the Contractor shall propose any additional excavation which may be required to remove material which is contaminated above action levels. Additional excavation shall be subject to approval by the Contracting Officer. Locations of samples shall be marked in the field and documented on the as-built drawings.

3.5 CONTAMINATED MATERIAL STORAGE

NOTE: For CERCLA sites, permits are not required to store hazardous waste in a stockpile. However, storage structures and conditions must be in compliance the Applicable, Relevant, and Appropriate Regulations (ARARs). For RCRA sites, permits are required to store hazardous waste in a stockpile. However, for RCRA sites, hazardous waste can be stored in a drum or roll-off unit for up to 90 days without a permit.

For temporary storage of more than 90 days, dual containment of hazardous liquid and some hazardous solids may be required. Containment system requirements are described in 40 CFR 264.175. For stock piles that meet the definition of a waste pile, see 40 CFR 264.250.

To provide secondary containment, tanks and roll-off units are sometimes stored on lined areas similar in design to what is described in paragraph Stockpiles.

Material shall be placed in temporary storage [immediately after excavation] [after treatment while awaiting test results]. The following paragraphs describe acceptable methods of material storage. Storage units shall be in good condition and constructed of materials that are compatible with the material or liquid to be stored. If multiple storage units are required, each unit shall be clearly labeled with an identification number and a written log shall be kept to track the source of contaminated material in each temporary storage unit.

3.5.1 Stockpiles

NOTE: Check state regulations to determine the minimum requirements for stockpiles and modify this paragraph accordingly. For contaminated material with high moisture content, the subgrade for the

stockpile must be sloped and a sump should be provided.

Scrim reinforced geomembranes are commonly specified for stockpile covers and liners. Due to their higher strength properties, scrim reinforced geomembranes can generally be thinner than non-reinforced geomembranes.

For post treatment stockpiles, chemical testing is usually required to determine if material is contaminated or clean. Maximum stockpile size should be based on the required frequency of chemical testing. For example, if chemical tests are required at a frequency of one per 1,000 cubic meters (cubic yards), then stockpiles should be no greater than 1,000 cubic meters (cubic yards) in size.

Stockpiles shall be constructed to isolate stored contaminated material from the environment. The maximum stockpile size shall be [_____] cubic meters. yards. Stockpiles shall be constructed to include:

- a. [A chemically resistant geomembrane liner free of holes and other damage. Non-reinforced geomembrane liners shall have a minimum thickness of [0.5] [_____] mm. [20] [_____] mils. Scrim reinforced geomembrane liners shall have a minimum weight of 20 kg/100 square meters. 40 lbs. per 1000 square feet. The ground surface on which the geomembrane is to be placed shall be free of rocks greater than 12 mm 0.5 inches in diameter and any other object which could damage the membrane.] [Pavement shall be used as the liner system. Pavement shall be constructed in accordance with Section [_____]].
- b. Geomembrane cover free of holes or other damage to prevent precipitation from entering the stockpile. Non-reinforced geomembrane covers shall have a minimum thickness of 0.25 mm. 10 mils. Scrim reinforced geomembrane covers shall have a minimum weight of 13 kg/100 square meters 26 lbs. per 1000 square feet. The cover material shall be extended over the berms and anchored or ballasted to prevent it from being removed or damaged by wind.
- c. Berms surrounding the stockpile, a minimum of 300 mm 12 inches in height. Vehicle access points shall also be bermed.
- d. The liner system shall be sloped to allow collection of leachate. Storage and removal of liquid which collects in the stockpile, in accordance with paragraph Liquid Storage.

3.5.2 Roll-Off Units

Roll-off units used to temporarily store contaminated material shall be water tight. A cover shall be placed over the units to prevent precipitation from contacting the stored material. The units shall be located [as shown on the drawings] [_____] . Liquid which collects inside the units shall be removed and stored in accordance with paragraph Liquid Storage.

3.5.3 Liquid Storage

Liquid collected from excavations and stockpiles shall be temporarily stored in [220 L barrels] [[2000] [_____] L tanks]. [55 gallon barrels] [[500] [_____] gallon tanks]. Liquid storage containers shall be water-tight and shall be located [as shown on the drawings] [_____] .

3.6 SAMPLING

3.6.1 Sampling of Stored Material

NOTE: Additional samples are sometimes collected from excavated material to determine the contaminants present prior to treatment or disposal.

Composite samples are often collected from stockpiled material. However, composite samples cannot be taken if the samples are being analyzed for volatile organic contaminants.

At sites with radioactive contamination, ex-situ sampling of excavated material is typically performed to ensure that the material meets disposal facility acceptance criteria and, in some cases, to assist with the preparation of shipping papers. The ex-situ sampling regime is site-specific. It is usually determined in consultation with the disposal facility and its regulatory agency.

Samples of stored material shall be collected at a frequency of once per [_____] cubic meters. yards. Samples shall be tested for the following:

Chemical Parameter	Action Level
[_____]	[_____]

Stored material with contaminant levels that exceed the action levels shall be treated [offsite. Analyses for contaminated material to be taken to an offsite treatment facility shall conform to local, state, and federal criteria as well as to the requirements of the treatment facility. Documentation of all analyses performed shall be furnished to the Contracting Officer. Additional sampling and analyses to the extent required by the approved offsite treatment, storage or disposal (TSD) facility shall be the responsibility of the Contractor and shall be [performed at no additional cost to the Government] [subject to approval by the Contracting Officer].] [onsite. Treatment shall be in accordance with Section [_____] .]

3.6.2 Sampling Liquid

NOTE: Liquid should generally be tested for the same contaminants as are found in the contaminated solid material being removed. The frequency of testing should be determined on a site specific basis. Offsite disposal will generally require additional testing and analysis prior to disposal.

NPDES requirements must be considered for onsite disposal of liquids.

Liquid collected from [excavations] [storage areas] [decontamination facilities] shall be sampled at a frequency of once for every [2,000] [_____] L [500] [_____] gallons of liquid collected. Samples shall be tested for the following:

Chemical Parameter	Action Level
[_____]	[_____]

Liquid with contaminant levels that exceed action levels shall be treated [offsite. Analyses for contaminated liquid to be taken to an offsite treatment facility shall conform to local, state, and federal criteria as well as to the requirements of the treatment facility. Documentation of all analyses performed shall be furnished to the Contracting Officer. Additional sampling and analysis to the extent required by the approved offsite treatment, storage or disposal (TSD) facility receiving the material shall be the responsibility of the Contractor and shall be [performed at no additional cost to the Government] [subject to approval by the Contracting Officer].] [onsite. Treatment shall be in accordance with Section [_____]].]

3.6.3 Sampling Beneath Storage Units

NOTE: At some sites, samples are collected to verify the soil on which a storage unit is placed has not become contaminated.

Sampling along any connecting pipelines that transport contaminated liquid may also be appropriate. A standard practice is to sample at 6 m (20 foot) intervals under piping and at connections such as bends, elbows, or tees.

Samples from beneath each storage unit shall be collected prior to construction of and after removal of the storage unit. Samples shall be collected at a frequency of one per each [_____] square meters yards from a depth interval of [0 to 0.15] [_____] m [0 to 0.5] [_____] feet and shall be tested for the following:

Chemical Parameter	Action Level
[_____]	[_____]

Based on test results, soil which has become contaminated above action levels shall be removed at no additional cost to the Government. Contaminated material which is removed from beneath the storage unit shall be handled in accordance with paragraph Sampling of Stored Material. As directed by the Contracting Officer and at no additional cost to the Government, additional sampling and testing shall be performed to verify areas of contamination found beneath stockpiles have been cleaned up to below action levels.

3.7 SPILLS

NOTE: Regarding preestablished spill reporting procedures, the designer should consult CEMP-RT memorandum of 20 July 1995, Subject: Spill Reporting Procedures for USACE Personnel Involved in HTRW Projects.

Evaluate whether a contingency plan is needed per 40 CFR 262.34. This regulation is a potential requirement for large quantity generators of hazardous waste. At military installations, a plan is typically already in place.

In the event of a spill or release of a hazardous substance (as designated in 40 CFR 302), pollutant, contaminant, or oil (as governed by the Oil Pollution Act (OPA), 33 U.S.C. 2701 et seq.), the Contractor shall notify the Contracting Officer immediately. If the spill exceeds the reporting threshold, the Contractor shall follow the pre-established procedures as described in the [RCRA Contingency Plan] [Base Wide Contingency Plan] [_____] for immediate reporting and containment. Immediate containment actions shall be taken to minimize the effect of any spill or leak. Cleanup shall be in accordance with applicable federal, state, and local regulations. As directed by the Contracting Officer, additional sampling and testing shall be performed to verify spills have been cleaned up. Spill cleanup and testing shall be done at no additional cost to the Government.

3.8 BACKFILLING

NOTE: If allowed by the regulatory authority, field analyses should be used to reduce laboratory turn-around time and minimize the duration an excavation must be left open.

After completion of backfilling, a 0.15 meter (6 inch) layer of top soil is typically placed in areas that are not paved. The topsoil is placed in a single lift to the lines and grades shown on the drawings. Top soil and seeding requirements should be described in a different section of the specification package.

3.8.1 Confirmation Test Results

Excavations shall be backfilled immediately after all contaminated materials have been removed and confirmation test results have been approved. Backfill shall be placed and compacted to the lines and grades shown on the drawings.

3.8.2 Compaction

NOTE: The following paragraph outlines density requirements for in-place backfill. If the density

of the backfill is not critical, modify this paragraph by replacing the density testing requirements with procedural requirements for compaction.

Approved backfill shall be placed in lifts with a maximum loose thickness of [200] [_____] mm. [8] [_____] inches. Soil shall be compacted to [90] [_____] percent of [ASTM D 698] [ASTM D 1557] maximum dry density. Density tests shall be performed at a frequency of once per [930] [_____] square meters [10,000] [_____] square feet per lift. A minimum of [one density test] [[_____] density tests] shall be performed on each lift of backfill placed. Field in-place dry density shall be determined in accordance with ASTM D 1556, ASTM D 2167, or ASTM D 2922. If ASTM D 2922 is used, a minimum of one in ten tests shall be checked using ASTM D 1556 or ASTM D 2167. Test results from ASTM D 1556 or ASTM D 2167 shall govern if there is a discrepancy with the ASTM D 2922 test results.

3.9 DISPOSAL REQUIREMENTS

Offsite disposal of contaminated material shall be in accordance with Section 02120 TRANSPORTATION AND DISPOSAL OF HAZARDOUS MATERIALS.

3.10 CLOSURE REPORT

NOTE: In addition to progress photos, video tapes have been used at some sites to record site activities.

[_____] copies of a Closure Report shall be prepared and submitted within [14] [_____] calendar days of completing work at the site. The report shall be labeled with the contract number, project name, location, date, name of general contractor, and the Corps of Engineers District contracting for the work. The Closure Report shall include the following information as a minimum:

- a. A cover letter signed by a [responsible company official] [Professional Engineer registered in the State of [_____] who is a responsible company official] certifying that all services involved have been performed in accordance with the terms and conditions of the contract documents and regulatory requirements.
- b. A narrative report including, but not limited to, the following:
 - (1) site conditions, ground water elevation, and cleanup criteria;
 - (2) excavation logs;
 - (3) field screening readings;
 - (4) quantity of materials removed from each area of contamination;
 - (5) quantity of water/product removed during dewatering;

- (6) sampling locations and sampling methods;
- (7) sample collection data such as time of collection and method of preservation;
- (8) sample chain-of-custody forms; and
- (9) source of backfill.
- c. Copies of all chemical and physical test results.
- d. Copies of all manifests and land disposal restriction notifications.
- e. Copies of all certifications of final disposal signed by the responsible disposal facility official.
- f. Waste profile sheets.
- g. Scale drawings showing limits of each excavation, limits of contamination, known underground utilities within 15 m 50 feet of excavation, sample locations, and sample identification numbers. On-site stockpile, storage, treatment, loading, and disposal areas shall also be shown on the drawings.
- h. Progress Photographs. Color photographs shall be used to document progress of the work. A minimum of four views of the site showing the location of the area of contamination, entrance/exit road, and any other notable site conditions shall be taken before work begins. After work has been started, activities at each work location shall be photographically recorded [daily] [weekly]. Photographs shall be a minimum of 76.2 x 127.0 mm 3 x 5 inches and shall include:
 - (1) Soil removal and sampling.
 - (2) Dewatering operations.
 - (3) Unanticipated events such as spills and the discovery of additional contaminated material.
 - (4) Contaminated material/water storage, handling, treatment, and transport.
 - (5) Site or task-specific employee respiratory and personal protection.
 - (6) Fill placement and grading.
 - (7) Post-construction photographs. After completion of work at each site, the Contractor shall take a minimum of four views of each excavation site.

A digital version of all photos shown in the report shall be included with the Closure Report. Photographs shall be a minimum of 76mm by 127 mm 3 inches by 5 inches and shall be mounted back-to-back in double face plastic sleeves punched to fit standard three ring binders. Each print shall have an information box attached. The box shall be typewritten and arranged as follows:

Project Name:
Location:
Photograph No.:

Direction of View:
Date/Time:
Description of View:

-- End of Section --