

\*\*\*\*\*  
USACE / NAVFAC / AFCEA / NASA            UFGS-01 50 00.00 20 (April 2006)  
-----  
Preparing Activity:    NAVFAC            Replacing without change  
   UFGS-01500N (October 2005)

## UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UML dated 1 April 2006

Latest change indicated by CHG tags

\*\*\*\*\*

### SECTION TABLE OF CONTENTS

#### DIVISION 01 - GENERAL REQUIREMENTS

##### SECTION 01 50 00.00 20

#### TEMPORARY FACILITIES AND CONTROLS

04/06

#### PART 1    GENERAL

- 1.1    REFERENCES
- 1.2    SUBMITTALS
- 1.3    CONSTRUCTION SITE PLAN
- 1.4    BACKFLOW PREVENTERS CERTIFICATE
  - 1.4.1    Backflow Prevention Training Certificate
- 1.5    TEMPORARY UTILITIES
  - 1.5.1    Contractor Utilities
  - 1.5.2    Utilities at Special Locations
    - 1.5.2.1    Utilities at Guam Provided by Contractor for Special Projects
    - 1.5.2.2    Utility Services at Midway
  - 1.5.3    Utility Services for Diego Garcia Projects
    - 1.5.3.1    Contractor-Owned and Operated Radio Telecommunications
    - 1.5.3.2    Off-Island
  - 1.5.4    Utility Services for Wake Island
  - 1.5.5    Telephones at Midway, Wake, and Diego Garcia
- 1.6    BACKFLOW TESTER CERTIFICATION
- 1.7    WEATHER PROTECTION
  - 1.7.1    Building and Site Storm Protection
    - 1.7.1.1    [Typhoon] [Hurricane] Condition of Readiness
- 1.8    STATION OPERATION AFFECT ON CONTRACTOR OPERATIONS
  - 1.8.1    Restricted Access Areas
  - 1.8.2    Special Restrictions Regarding Access of Vehicles and Parking
    - 1.8.2.1    Interruption of Vehicular Traffic
    - 1.8.2.2    Commercial Vehicles In/Out of NAVSTA/NAS Norfolk, VA
- 1.9    STORAGE AREAS
  - 1.9.1    Storage Size and Location
  - 1.9.2    Storage in Existing Buildings
- 1.10    TEMPORARY SANITARY FACILITIES
- 1.11    TEMPORARY BUILDINGS
  - 1.11.1    Maintenance of Temporary Facilities
  - 1.11.2    Navy Construction Representative's Office

- 1.11.3 Quality Control Manager Records and Field Office
- 1.11.4 Trailers or Storage Buildings
  - 1.11.4.1 LANTNAVFACENGCOM Trailer Sign

## PART 2 PRODUCTS

- 2.1 Backflow Preventers

## PART 3 EXECUTION

- 3.1 TEMPORARY PHYSICAL CONTROLS
  - 3.1.1 Access Controls
    - 3.1.1.1 Temporary Barricades
    - 3.1.1.2 Fencing
    - 3.1.1.3 Signs
    - 3.1.1.4 Traffic Work
- 3.2 TEMPORARY WIRING
- 3.3 REDUCED PRESSURE BACKFLOW PREVENTERS
- 3.4 GRASS CUTTING

-- End of Section Table of Contents --

\*\*\*\*\*  
USACE / NAVFAC / AFCEA / NASA           UFGS-01 50 00.00 20 (April 2006)  
-----  
Preparing Activity:   NAVFAC           Replacing without change  
  UFGS-01500N (October 2005)

## UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UMRL dated 1 April 2006

Latest change indicated by CHG tags

\*\*\*\*\*

SECTION 01 50 00.00 20

### TEMPORARY FACILITIES AND CONTROLS 04/06

\*\*\*\*\*

NOTE: This guide specification covers the requirements for temporary construction facilities and controls over contractor operations required for use in all projects.

Comments and suggestions on this guide specification are welcome and should be directed to the technical proponent of the specification. A listing of technical proponents, including their organization designation and telephone number, is on the Internet.

Recommended changes to a UFGS should be submitted as a Criteria Change Request (CCR).

Use of electronic communication is encouraged.

This guide specification includes tailoring options for EFD and EFA regional requirements. Selection or deselection of a tailoring option will include or exclude that option in the section, but editing the resulting section to fit the project is still required.

Brackets are used in the text to indicate designer choices or locations where text must be supplied by the designer.

\*\*\*\*\*

\*\*\*\*\*

NOTE: TO DOWNLOAD UFGS GRAPHICS

Go to <http://www.wbdg.org/ccb/NAVGRAPH/graphdoc.pdf>.

\*\*\*\*\*

\*\*\*\*\*

NOTE: On the drawings, show:

1. Location of temporary buildings and storage areas, if specified;

2. Location of temporary utility connections, if specified.

\*\*\*\*\*

PART 1 GENERAL

1.1 REFERENCES

\*\*\*\*\*

NOTE: This paragraph is used to list the publications cited in the text of the guide specification. The publications are referred to in the text by basic designation only and listed in this paragraph by organization, designation, date, and title.

Use the Reference Wizard's Check Reference feature when you add a RID outside of the Section's Reference Article to automatically place the reference in the Reference Article. Also use the Reference Wizard's Check Reference feature to update the issue dates.

References not used in the text will automatically be deleted from this section of the project specification when you choose to reconcile references in the publish print process.

\*\*\*\*\*

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C511 (1997) Reduced-Pressure Principle Backflow Prevention Assembly

FOUNDATION FOR CROSS-CONNECTION CONTROL AND HYDRAULIC RESEARCH (FCCCHR)

FCCCHR List (continuously updated) List of Approved Backflow Prevention Assemblies

FCCCHR Manual (1988e9) Manual of Cross-Connection Control

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 241 (2004) Safeguarding Construction, Alteration, and Demolition Operations

NFPA 70 (2005) National Electrical Code

U.S. FEDERAL HIGHWAY ADMINISTRATION (FHWA)

FHWA SA-89-006 (1988) Manual on Uniform Traffic Control Devices for Streets and Highways

## 1.2 SUBMITTALS

\*\*\*\*\*

NOTE: Review submittal description (SD) definitions in Section 01 33 00 SUBMITTAL PROCEDURES and edit the following list to reflect only the submittals required for the project. Submittals should be kept to the minimum required for adequate quality control.

A "G" following a submittal item indicates that the submittal requires Government approval. Some submittals are already marked with a "G". Only delete an existing "G" if the submittal item is not complex and can be reviewed through the Contractor's Quality Control system. Only add a "G" if the submittal is sufficiently important or complex in context of the project.

For submittals requiring Government approval on Army projects, a code of up to three characters within the submittal tags may be used following the "G" designation to indicate the approving authority. Codes for Army projects using the Resident Management System (RMS) are: "AE" for Architect-Engineer; "DO" for District Office (Engineering Division or other organization in the District Office); "AO" for Area Office; "RO" for Resident Office; and "PO" for Project Office. Codes following the "G" typically are not used for Navy, Air Force, and NASA projects.

Choose the first bracketed item for Navy, Air Force and NASA projects, or choose the second bracketed item for Army projects.

\*\*\*\*\*

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are [for Contractor Quality Control approval.][for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government.] The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

### SD-01 Preconstruction Submittals

[ Traffic control plan; G]

\*\*\*\*\*

NOTE: Include the following submittal for SOUTH DIV projects at the Charleston Air Force Base and for other SOUTH DIV projects as determined by the Contracting Officer based on project size, scope, complexity, and visibility.

\*\*\*\*\*

[ Construction site plan; G]

### SD-03 Product Data

\*\*\*\*\*  
NOTE: Include the following for all projects  
connecting to a potable water supply.  
\*\*\*\*\*

Backflow preventers

SD-06 Test Reports

Backflow Preventer Tests; G

SD-07 Certificates

Backflow Tester Certification; G

\*\*\*\*\*  
NOTE: Include the following for all projects  
connecting to a potable water supply.  
\*\*\*\*\*

[ Backflow Preventers Certificate of Full Approval]

#### [1.3 CONSTRUCTION SITE PLAN

\*\*\*\*\*  
NOTE: Use this paragraph for SOUTHDIV projects at  
Charlestown Air Force Base only  
\*\*\*\*\*

Prior to the start of work, submit a site plan showing the locations of temporary facilities (including layouts and details, equipment and material storage area (onsite and offsite), and access and haul routes used for this contract. Show locations of safety and construction fences, site trailers, construction entrances, trash dumpsters, temporary sanitary facilities, and worker parking areas.

#### ]1.4 BACKFLOW PREVENTERS CERTIFICATE

Certificate of Full Approval from FCCCHR List, University of Southern California, attesting that the design, size and make of each backflow preventer has satisfactorily passed the complete sequence of performance testing and evaluation for the respective level of approval. Certificate of Provisional Approval will not be acceptable.

##### 1.4.1 Backflow Prevention Training Certificate

The Contractor shall submit a certificate recognized by the State or local authority that states the Contractor has completed at least 10 hours of training in backflow preventer installations. The certificate must be current.

#### 1.5 TEMPORARY UTILITIES

\*\*\*\*\*  
NOTE: This paragraph must be coordinated with the  
Contracting Officer. Coordinate with FAR Clause  
52.236-14. Choose one of the following options.  
For LANTNAVFACENGCOM, delete the article if utility

service is covered in a Section "Special Conditions for Projects at (\_\_\_\_)"; used for some stations on a regional basis.

\*\*\*\*\*

\*\*\*\*\*

NOTE: Government utilities listed in this paragraph may be furnished, if available without interfering with Government needs. These services shall not be made free of charge except: (1) on Air Force projects; (2) on other projects when administrative costs exceed the value of the services; or (3) when otherwise advantageous to the Government. The general layout plan or other appropriate drawing shall indicate the point at which the Government will deliver each utility specified and should show pertinent data such as voltage, L/min gal/min, and pipe sizes. Information regarding the types of utilities available, the rates, the points of connection' and the quantities available should be obtained from the Government.

\*\*\*\*\*

[Reasonable amounts of the following utilities will be made available to the Contractor [without charge.] [at the prevailing rates.] [at the following rates:]

[Electricity - [: \$\_\_\_\_\_ per \_\_\_\_\_]]  
[Potable Water - [: \$\_\_\_\_\_ per \_\_\_\_\_]]  
[Salt Water - [: \$\_\_\_\_\_ per \_\_\_\_\_]]  
[Compressed Air - [: \$\_\_\_\_\_ per \_\_\_\_\_]]  
[Steam - [: \$\_\_\_\_\_ per \_\_\_\_\_]]  
[Natural Gas - [: \$\_\_\_\_\_ per \_\_\_\_\_]]  
[Sanitary Sewer - [: \$\_\_\_\_\_ per \_\_\_\_\_]]

The point at which the Government will deliver such utilities or services and the quantity available is as indicated. The Contractor shall pay all costs incurred in connecting, converting, and transferring the utilities to the work. The Contractor shall make connections, including [providing backflow-preventing devices on connections to domestic water lines;] [providing meters;] and providing transformers; and make disconnections.] [Under no circumstances will taps to base fire hydrants be allowed for obtaining domestic water.]

#### [1.5.1 Contractor Utilities

The Contractor shall provide his own utilities.

#### ] [1.5.2 Utilities at Special Locations

\*\*\*\*\*

NOTE: For LANTNAVFACENGCOM projects choose one of the following options. For the first option, in the first set of brackets, insert the name of the activity to which application should be made. Include the second bracketed expression for projects located at MCAS Cherry Point.

\*\*\*\*\*

[Reasonable amounts of utilities will be made available to the Contractor at the prevailing Government rates. These rates may be obtained upon application to the Commanding Officer, [\_\_\_\_\_,] by way of the Contracting Officer. The Contractor will be responsible for making connections, providing transformers and meters, and making disconnections; and for providing backflow preventer devices on connections to domestic water lines. [Neither potable water nor sanitary facilities will be available at the main Contractor laydown area at Marine Corps Air Station (MCAS), Cherry Point, NC.]]

\*\*\*\*\*  
NOTE: Use the following option for projects located  
in Argentina and the Azores and for Air Force  
projects in the Atlantic Division. Use this  
paragraph for other activities only when approved by  
the activity.  
\*\*\*\*\*

[Reasonable amounts of utilities will be made available without charge. The Contractor will be responsible for making connections, providing transformers and meters, and making disconnections; and for providing backflow preventer devices on connections to domestic water lines. Under no circumstances will taps to base fire hydrants be allowed for obtaining domestic water.]

\*\*\*\*\*  
NOTE: Use the following option only for MCON funded  
and non-appropriated funds projects at Marine Corps  
Base, Camp Lejeune and Marine Corps Air Station  
(Helicopter (H)), New River.  
\*\*\*\*\*

[Reasonable amounts of utilities will be made available to the Contractor at the prevailing Government rates and may be obtained upon application to the Base Maintenance Officer, Bldg. 1202, Marine Corps Base, Camp Lejeune. A refundable security deposit to the Resident Officer in Charge of Construction shall be made prior to application for services. The Contractor shall be responsible for providing transformers, meter bases, electrical service poles and drops for electrical services, and backflow preventer devices on connections to domestic water lines. Final taps and tie-ins to the Government utility grid will be made by Base Maintenance who will also provide and seal a 120 or 208 volt, three-wire kWh meter. Tap-in cost, if any, shall be the responsibility of the Contractor. Tampering or movement of a sealed meter without notification to base maintenance is grounds for discontinuance of electrical service. The Contractor shall be responsible for providing larger meters required if not available from the Government. The Contractor shall be responsible for the cost of utility services required until the date of Government acceptance. Under no circumstances will taps to base fire hydrants be allowed for obtaining domestic water.]

[1.5.2.1 Utilities at Guam Provided by Contractor for Special Projects

Contact the Government of Guam for water and electricity.

] [1.5.2.2 Utility Services at Midway

- a. Potable water is rationed during dry periods and not available for construction purposes during the months of June and July.



- b. Electrical power available, primary voltage is 2400 volt 3 phase, 3 wire, 60 cycle AC. Secondary voltages may be 120/208 or 120/240 volts.
- c. Provide new meters for potable water, brackish water and electricity. The cost of utility services furnished may be reduced by the cost the Government would normally pay for comparable meters if, at the end of the job, the meters are delivered to the Government in good condition.

][1.5.3 Utility Services for Diego Garcia Projects

- a. Potable water will be made available to Contractor's office and housing. The prevailing rate for potable water is \$2.07 per thousand gallons.
- b. No charge for brackish water.
- c. Electrical power available is primary, 2400 volt 3 phase, 3 wire, 60 cycle AC, secondary voltages may be 120/208 or 120/240 volts. The prevailing rate for electricity is \$0.0647 per kilowatt hour (KWH).
- d. Sewage costs at \$1.09 per 3800 L KGAL.
- e. Provide new meters for potable water and electricity. The cost of utility services furnished may be reduced by the cost the Government would normally pay for comparable meters if, at the end of the job, the meters are delivered to the Government in good condition.

[1.5.3.1 Contractor-Owned and Operated Radio Telecommunications

\*\*\*\*\*  
**NOTE: Use for Diego Garcia projects.**  
 \*\*\*\*\*

If approved, the Contractor may erect a transmitter/receiver and antenna. Submit for approval, 30 calendar days prior to the use of the equipment, the type of radio equipment power and band width of the equipment.

] [1.5.3.2 Off-Island

\*\*\*\*\*  
**NOTE: Use for Diego Garcia projects.**  
 \*\*\*\*\*

The Government will provide military message communication from Diego Garcia at no cost. The Contractor is responsible for the cost of retransmitting messages through commercial sources. Process messages through the Contracting Officer. Messages will be screened and limited use of communication facilities will be permitted. Private messages will be permitted only for emergencies. The Navy voice communication system will not be available for use by the Contractor. A local vendor provides commercial voice and teletype services for [\$3.32] per minute.

]1.5.4 Utility Services for Wake Island

[a. Potable water may not be available for construction during dry periods. Desalinized water available during dry periods at \$1300.00 per day for 114-150 kL 30,000-40,000 gallons per day.

b. Available primary voltage is 4160 volts, 3 phase, 3 wire, 60 cycle. Secondary is 120/208 volts, 3 phase, 60 cycle.]

[1.5.5 Telephones at Midway, Wake, and Diego Garcia

On-Island service may be obtained if lines are available. Make arrangements through the Contracting Officer. The prevailing rate for cable or wireless is \$100.00 per phone. There is no charge for on-island telephone service. [Current rates are [\$\_\_\_\_\_] per month for each private telephone line plus an installation charge of [\$\_\_\_\_\_] for each instrument and [\$\_\_\_\_\_] per month for two-party lines plus [\$\_\_\_\_\_] per month for each extension. Pay for the cost of the wiring on runs in excess of two spans].

Long distance services are usually available at commercial rates. The Navy Radio Communication System or Defense Switch Network will not be available for use. [Limited teletypewriter circuit service is available.]

] [1.6 BACKFLOW TESTER CERTIFICATION

Prior to testing, submit to the Contracting Officer certification issued by the State or local regulatory agency attesting that the backflow tester has successfully completed a certification course sponsored by the regulatory agency. Tester shall not be affiliated with any company participating in any other phase of this Contract.

\*\*\*\*\*  
NOTE: Use for SOUTHWESTNAVFACENGCOM only.  
\*\*\*\*\*

Certified by the City of San Diego.

]1.7 WEATHER PROTECTION

Take necessary precautions to ensure that roof openings and other critical openings in the building are monitored carefully. Take immediate actions required to seal off such openings when rain or other detrimental weather is imminent, and at the end of each workday. Ensure that the openings are completely sealed off to protect materials and equipment in the building from damage.

1.7.1 Building and Site Storm Protection

When a warning of gale force winds is issued, take precautions to minimize danger to persons, and protect the work and nearby Government property. Precautions shall include, but are not limited to, closing openings; removing loose materials, tools and equipment from exposed locations; and removing or securing scaffolding and other temporary work. Close openings in the work when storms of lesser intensity pose a threat to the work or any nearby Government property.

[1.7.1.1 [Typhoon] [Hurricane] Condition of Readiness

Unless directed otherwise, comply with:

- a. Condition FOUR (Sustained winds of 93 km/hr 50 knots or greater expected within 72 hours): Normal daily jobsite cleanup and good housekeeping practices. Collect and store in piles or containers scrap lumber, waste material, and rubbish for removal and disposal at the close of each work day. Maintain the construction site including storage areas, free of accumulation of debris. Stack form lumber in neat piles less than one m 4 feet high. Remove all debris, trash, or objects that could become missile hazards. [Contact Contracting Officer for [Condition Requirements] [Condition of Readiness (COR) updates and completion of required actions].]
- b. Condition THREE (Sustained winds of 93 km/hr 50 knots or greater expected within 48 hours): Maintain "Condition FOUR" requirements and commence securing operations necessary for "Condition ONE" which cannot be completed within 18 hours. Cease all routine activities which might interfere with securing operations. Commence securing and stow all gear and portable equipment. Make preparations for securing buildings. Review requirements pertaining to "Condition TWO" and continue action as necessary to attain "Condition THREE" readiness. Contact Contracting Officer for weather and COR updates and completion of required actions.
- c. Condition TWO (Sustained winds of 93 km/hr 50 knots or greater expected within 24 hours): Curtail or cease routine activities until securing operation is complete. Reinforce or remove form work and scaffolding. Secure machinery, tools, equipment, materials, or remove from the jobsite. Expend every effort to clear all missile hazards and loose equipment from general base areas. Contact Contracting Officer for weather and Condition of Readiness (COR) updates and completion of required actions.
- d. Condition ONE. (Sustained winds of 93 km/hr 50 knots or greater expected within 12 hours): Secure the jobsite, and leave Government premises.

] [1.8 STATION OPERATION AFFECT ON CONTRACTOR OPERATIONS

\*\*\*\*\*  
**NOTE: Use this paragraph on all projects involving potential conflicts with operating conditions other than utilities or where the work must be pursued in a particular sequence. Clearly detail the permissible extent of sequencing or duration of interruptions to station operation. Obtain information from the Government.**  
 \*\*\*\*\*

[\_\_\_\_\_]

[1.8.1 Restricted Access Areas

The Government will monitor work in areas [listed below] [indicated]. Notify Contracting Officer at least 14 calendar days prior to starting work in these areas.

[\_\_\_\_\_]

] [1.8.2 Special Restrictions Regarding Access of Vehicles and Parking

\*\*\*\*\*  
NOTE: Do not add information related to station regulations which are of a routine nature. Unusual access provisions dictated by the needs of a particular project may be included, as directed.  
\*\*\*\*\*

[\_\_\_\_].

] [1.8.2.1 Interruption of Vehicular Traffic

If during the performance of work, it becomes necessary to modify vehicular traffic patterns at any locations, notify the Contracting Officer at least 15 calendar days prior to the proposed modification date, and provide a [Traffic Control Plan](#) detailing the proposed controls to traffic movement for approval. The plan shall be in accordance with State and local regulations and the [FHWA SA-89-006](#), Part VI. [Make all notifications and obtain any permits required for modification to traffic movements outside Station's jurisdiction.] Provide cones, signs, barricades, lights, or other traffic control devices and personnel required to control traffic. Do not use foil-backed material for temporary pavement marking because of its potential to conduct electricity during accidents involving downed power lines.

] [1.8.2.2 Commercial Vehicles In/Out of NAVSTA/NAS Norfolk, VA

\*\*\*\*\*  
NOTE: Use the following paragraphs only for projects located at Naval Station (NAVSTA) or Naval Air Station (NAS), Norfolk, VA.  
\*\*\*\*\*

- a. Definitions. Commercial vans and trucks are differentiated as follows:
  - (1) Closed truck. A truck enclosed on four sides, top, and bottom to which entry can be made only through end or side doors and to which a seal can be applied.
  - (2) Open truck. A truck which is either fully open, such as flatbed, or contained by wooden slats or sideboards; or any truck to which a seal cannot be applied.
  - (3) Commercial vehicles. A common contract or commercial truck without a decal issued by Norfolk, VA.
  - (4) Trailer. A non-self-propelled enclosed cargo container used for the transportation of goods, e.g., a trailer pulled by a truck.
- b. Instructions and directions. Ensure that commercial trucks and trailers follow the instructions below to provide for effective control over their entry and exit from the base, movement within the base, and to reduce congestion both at the gates and within the base. In general, commercial trucks and common carriers are required to enter and exit through specified gates and process immediately to a truck control point for cargo manifest check. The driver shall be issued a Material Movement Control and Gate

Pass, routing instructions, and directions to depart the base via a designated exit point where the pass is to be turned in.

(1) Common contract and commercial trucks going to the area of Building LP-84 (MAC Terminal), NAS Norfolk shall enter and exit Gate 22. Gate 22 hours of operations are 5:30 a.m. through 6:30 p.m. and 10:30 p.m. through 3:00 a.m., 7 days a week. The gate is closed on holidays.

(2) Other common contract and commercial trucks, except as noted below are allowed to enter the Naval Base through any Gate and exit through Gate 2.

(3) Common contract and commercial trucks which enter the base may depart through Gate 5, Gate 4, and Gate 22 only. The exit Truck Control Point at Gate 4 is operated from 7:00 a.m. to 5:00 p.m.

(4) For concrete- and asphalt-carrying trucks, the Resident Officer in Charge of Construction (ROICC), Norfolk VA shall arrange entry and exit through any gate other than Gate 2.

(5) Contractor vehicles with black Norfolk Naval Base decals shall be granted routine access to the base at all times. These trucks shall not enter or exit the base through Gate 2. These trucks are subject to random checks and searches at exit gates like other personal and commercial vehicles to ensure that Government property is not being taken off the base without authorization and documentation.

c. Movement and Exit

(1) Material movement control and gate pass. A Material Movement Control and Gate Pass (5ND GEN 5510/1) is required for the removal of Government, public, or private property from NAVSTA and NAS Norfolk complex via commercial vans and truck.

(a) The Material Movement Control and Gate Pass shall be originated by the Naval Base Police Truck Control Officer, and shall be given to drivers of commercial trucks for retention during transit to intermediate stops and to the exit gates. The pass shall be presented by the driver to the Truck Control Officer at the exit truck stop. If the driver has more than one delivery or pickup point, the driver shall present the pass at each stop so the new activity may fill in appropriate information on the pass. A copy of the pass shall be retained by each activity after appropriate information has been entered; remaining copies of the pass shall be returned to the driver. Passes are subject to review by the Naval Base Police Department during transit and within command areas by activity officials for verification of cargo content and to determine if drivers are transiting promptly and by the proper route. For trailers expecting to be picked up and depart outside normal working hours, pre-prepared passes shall be provided by the activity duty officer or authorized supervising person prior to close of working hours. Trucking companies expecting to pick up trailers after working hours should be instructed to pick up a Material Movement Control and Gate Pass from the responsible activity. The activity duty officer or official shall notify Base Police Headquarters to clear the truck

for exit at Gate 5 if the seal and Material Movement Control and Gate Pass are in order.

(b) When filling out a Material Movement Control and Gate Pass, the last activity where business is conducted on the base is responsible to ensure that the original of the pass is given to the driver to turn in to the Truck Control officer at the truck control stops.

(c) The Material Movement Control and Gate Pass shall be turned in by the vehicle driver to a base police officer at a truck control stop when he departs from the base.

(d) Government or commercial vehicles departing Naval Base, Norfolk with Government, public, or private property shall possess a Material Movement Control and Gate Pass filled out by a naval officer or equivalent grade civilian within the driver's chain of command. The Material Movement Control and Gate Pass shall be inspected and verified during random gate departure searches.

(2) Car Seals

(a) Commercial, sealable, closed trailers and trucks, full, partially full, or empty, destined to leave the base shall be sealed upon departure from any activity. The seal number and trailer or truck number shall be entered on the Material Movement Control and Gate Pass.

(b) Commercial closed trailers and trucks received empty for loading with Government material shall have a Navy car seal affixed to cargo doors after loading and prior to departing through designated gates.

(c) Closed trailers and trucks which have been only partially loaded or off-loaded shall be sealed completely at the end of working hours with a Navy car seal.

(d) Application of Navy car seals is the responsibility of the activity in charge of loading and unloading of trailers and trucks.

(e) The Naval Base Police Department will conduct random checks of contents, seals, and forms of trailers and trucks on the Naval Base complex.

(f) A truck driver whose van or truck does not have a properly completed Material Movement Control and Gate Pass or car seal will be refused exit clearance.

]] [1.9 STORAGE AREAS

\*\*\*\*\*  
**NOTE: The Government will provide the necessary  
Station information. Indicate offsite storage areas  
on the drawings.**  
\*\*\*\*\*

Contractor shall be responsible for security of his property. The Contract Clause entitled "FAR 52.236-10, Operations and Storage Areas" and the following apply:

[1.9.1 Storage Size and Location

The [roofed] [enclosed] [open] site available for storage shall be [confined to the indicated operations area] [within 300 m 1,000 feet of the operations area] [as indicated]. The storage area shall be approximately [\_\_\_\_\_] square meter square feet.

] [1.9.2 Storage in Existing Buildings

The Contractor shall be working [in] [around] existing building[s]; the storage of material [will be allowed in a [\_\_\_\_\_] square meter square foot area] [where indicated] [will not be allowed in the building[s]]. [Provide 2.4 m 8 foot high security fence with a lockable gate around the storage area. Remove at the completion of work.]

]] [1.10 TEMPORARY SANITARY FACILITIES

\*\*\*\*\*  
NOTE: Use the second (optional) paragraph for  
SOUTHDIR projects at the Charleston Air Force Base  
and for other SOUTHDIR projects as determined by the  
Contracting Officer based on project size, scope,  
complexity, and visibility. Consult the Contracting  
Officer for base standard color.  
\*\*\*\*\*

Provide adequate sanitary conveniences of a type approved for the use of persons employed on the work, properly secluded from public observation, and maintained in such a manner as required and approved by the Contracting Officer. Maintain these conveniences at all times without nuisance. Upon completion of the work, remove the conveniences from the premises, leaving the premises clean and free from nuisance. Dispose of sewage through connection to a municipal, district, or station sanitary sewage system. Where such systems are not available, use chemical toilets or comparably effective units, and periodically empty wastes into a municipal, district, or station sanitary sewage system, or remove waste to a commercial facility. Obtain approval from the system owner prior to discharge into any municipal, district, or commercial sanitary sewer system. Any penalties and / or fines associated with improper discharge shall be the responsibility of the Contractor. Coordinate with the Contracting Officer and follow station regulations and procedures when discharging into the station sanitary sewer system. Include provisions for pest control and elimination of odors.

[Provide temporary sewer and sanitation facilities that are self-contained units with both urinals and stool capabilities. Ventilate the units to control odors and fumes and empty and clean them at least once a week or more often if required by the Contracting Officer. The doors shall be self-closing. The exterior of the unit shall match the base standard color. Locate the facility behind the construction fence or out of the public view.]

] [1.11 TEMPORARY BUILDINGS

\*\*\*\*\*  
NOTE: Government will provide the necessary Station  
information. Use paragraphs related to temporary  
facilities only when storage sheds or offices are

anticipated.

\*\*\*\*\*

Temporary facilities( including trailers) shall be in like new condition. Locate these facilities [where indicated.] [where directed and within the indicated operations area.] [within 300 m 1,000 feet of the operations area.] Storage of material/debris under such facilities is prohibited. [Maintenance and repair services are available on a cost reimbursable basis.] Contractor shall be responsible for the security of the stored property.

[1.11.1 Maintenance of Temporary Facilities

\*\*\*\*\*NOTE: For SOUTHDIV projects at the Charleston Air Force Base and for other SOUTHDIV projects as determined by the Contracting Officer, use the first painting option. Consult the Contracting Officer for base paint standards.\*\*\*\*\*

[Paint in accordance with base standards] [Suitably paint] and maintain the temporary facilities. Failure to do so will be sufficient reason to require their removal.

] [1.11.2 Navy Construction Representative's Office

\*\*\*\*\*NOTE: For locations remote from a ROICC office. This provision will be deleted at most stations and for most projects. For specific direction, contact the EFD/EFA Construction Division.\*\*\*\*\*

Provide an office with a minimum of [9] [18] [\_\_\_\_\_] square meter [100] [200] [\_\_\_\_\_] square feet of useful floor area for the exclusive use of Government personnel, in addition to and separate from any other office space provided by the Contractor. Provide a weathertight structure with adequate [heating and cooling,] toilet facilities, lighting, ventilation, a 1200 by 2400 mm 4 by 8 foot plan table, [computer work space] a standard size office desk and chair, and telephone. [Provide either a 1,500 watt radiant heater and a window-mounted air conditioner rated at [1.3] [2.6] kW [4,500] [9,000] Btus minimum or a window-mounted heat pump of the same minimum heating and cooling ratings.] [Include the utilities required to make these items operable.] Provide a door with a cylinder lock and windows with locking hardware. Make utility connections. Locate [as directed] [where indicated]. After completion of the work, remove the entire structure from the site.

] [1.11.3 Quality Control Manager Records and Field Office

\*\*\*\*\*NOTE: Include this paragraph when project has separate QC Manager and project Superintendent. Edit to suit the size and location of the project.\*\*\*\*\*

Provide on the jobsite an office with approximately [9] [18] [\_\_\_\_\_] square meter [100] [200] [\_\_\_\_\_] square feet of useful floor area for the exclusive use of the QC Manager. Provide a weathertight structure with



adequate [heating and cooling,] toilet facilities, lighting, ventilation, a 1200 by 2400 mm 4 by 8 foot plan table, a standard size office desk and chair, computer station, and working communications facilities. [Provide either a 1,500 watt radiant heater and a window-mounted air conditioner rated at 2.6 kW 9,000 Btus minimum or a window-mounted heat pump of the same minimum heating and cooling ratings.] Provide a door with a cylinder lock and windows with locking hardware. Make utility connections. Locate [as directed] [where indicated]. File quality control records in the office and make available at all times to the Government. After completion of the work, remove the entire structure from the site.

#### ] 1.11.4 Trailers or Storage Buildings

\*\*\*\*\*  
NOTE: Use this paragraph for projects located on  
the Naval Base Complex, Norfolk, Virginia.  
\*\*\*\*\*

Trailers or storage buildings will be permitted, where space is available, subject to the approval of the Contracting Officer. The trailers or buildings shall be in good condition, free from visible damage rust and deterioration, and meet all applicable safety requirements. Trailers shall be roadworthy and comply with all appropriate state and local vehicle requirements. Failure to maintain storage trailers or buildings to these standards shall result in the removal of non-complying units at the Contractor's expense. A sign not smaller than 600 by 600 mm 24 by 24 inches shall be conspicuously placed on the trailer depicting the company name, business phone number, and emergency phone number. Trailers shall be anchored to resist high winds and must meet applicable state of local standards for anchoring mobile trailers.

##### 1.11.4.1 LANTNAVFACENGCOM Trailer Sign

A sign that conforms to the following requirements and sketch shall be mounted on the trailer or building that shows the company name, phone number, and emergency phone number.

Sign requirements:

Graphic panel: Aluminum, painted blue

Copy: Screen painted or vinyl die-cut, white

Typeface: Univers 65 u/lc

See Sketch No. 01500 (graphic).

#### ] PART 2 PRODUCTS

##### [2.1 Backflow Preventers

\*\*\*\*\*  
NOTE: Include the following for all projects  
connecting to a potable water supply.  
  
For SOUTHWESTNAVFACENGCOM, information on FCCCHR  
List approved reduced pressure principle backflow  
devices may be obtained from the Navy Public Works  
Center, San Diego, Utilities Department, (619)

556-7964.

\*\*\*\*\*

Reduced pressure principle type conforming to the applicable requirements AWWA C511. Provide backflow preventers complete with [65 kg] [150 pound] [\_\_\_\_\_] flanged [cast iron], [bronze] [brass] mounted gate valve [and strainer], [304] [\_\_\_\_\_] stainless steel or bronze, internal parts. [The particular make, model/design, and size of backflow preventers to be installed shall be included in the latest edition of the List of Approved Backflow Prevention Assemblies issued by the FCCCHR List and shall be accompanied by a Certificate of Full Approval from FCCCHR List.]

]PART 3 EXECUTION

3.1 TEMPORARY PHYSICAL CONTROLS

3.1.1 Access Controls

3.1.1.1 Temporary Barricades

Contractor shall provide for barricading around all work areas to prevent public access.

3.1.1.2 Fencing

\*\*\*\*\*

NOTE: Designer: Fencing requirements must be evaluated based on the exposure potential of the construction site to the public. The public is considered as any non-construction personnel. Minimum fencing may range from nylon fabric (reinforced by a top supporting cable to provide adequate strength to provide needed physical protection) to 2400 mm 8 foot chain link fencing.

\*\*\*\*\*

\*\*\*\*\*

NOTE: Use the second (optional) paragraph for SOUTHDIV projects at the Charleston Air Force Base and for other SOUTHDIV projects as determined by the Contracting Officer based on project size, scope, complexity, and visibility. Consult the Contracting Officer for base temporary fencing standards and for base standard color.

\*\*\*\*\*

Fencing shall be provided along the construction site at all open excavations and tunnels to control access by unauthorized people. Fencing must be installed to be able to restrain a force of at least 114.00 kg 250 pounds against it.

[Enclose the project work area and Contractor lay-down area with a 2400 mm 8 ft high [shadow-box type, wooden fence and gates] [chain link fence and gates with brown, UV light resistant, plastic fabric mesh netting (similar to tennis court or other screening)]. Remove the fence upon completion and acceptance of the work. Intent is to block (screen) public view of the construction.

In addition, prior to the start of work, enclose those areas at the

construction site which are not within the construction fence with a temporary safety fence, including gates and warning signs, to protect the public from construction activities. The safety fence shall match the base standard color (or bright orange where it protects excavated areas), shall be made of [high density polyethylene grid or approved equal] [plastic fence from recovered materials containing 60-100 percent recovered content level plastic], a minimum of 1100 mm 42 inches high, supported and tightly secured to steel posts located on minimum 3000 mm 10 foot centers. Remove the fence from the work site upon completion of the contract.]

#### 3.1.1.3 Signs

Place warning signs at the construction area perimeter designating the presence of construction hazards requiring unauthorized persons to keep out. Signs must be placed on all sides of the project, with at least one sign every 90 m 300 feet. All points of entry shall have signs designating the construction site as a hard hat area.

#### 3.1.1.4 Traffic Work

All work around/involving roadways, to include roadway excavations and utility crossings, will be conducted in accordance with Manual of Traffic Control Devices. Contractors shall provide and ensure appropriate road closure and detour signs are established as necessary for motor traffic management. All road closures shall be coordinated with the Contracting Officer in advance. Self-illuminated (lighted) barricades shall be provided during hours of darkness. Brightly-colored (orange) vests are required for all personnel working in roadways. Road closures shall require a road closure plan showing the location of signage.

### 3.2 TEMPORARY WIRING

Provide temporary wiring in accordance with NFPA 241 and NFPA 70, Article 305-6(b), Assured Equipment Grounding Conductor Program. Program shall include frequent inspection of all equipment and apparatus.

### [3.3 REDUCED PRESSURE BACKFLOW PREVENTERS

\*\*\*\*\*

**NOTE: Include the following for all projects  
connecting to a potable water supply.**

**For SOUTHWESTNAVFACENGCOM, information on FCCCHR  
List approved reduced pressure principle backflow  
devices may be obtained from the Navy Public Works  
Center, San Diego, Utilities Department, (619)  
556-7964.**

\*\*\*\*\*

Provide an approved reduced pressure backflow prevention assembly at each location where the Contractor taps into the Government potable water supply.

A certified tester(s) shall perform testing of backflow preventer(s) for proper installation and operation and provide subsequent tagging. Backflow preventer tests shall be performed using test equipment, procedures, and certification forms conforming to those outlined in the latest edition of the Manual of Cross-Connection Control published by the FCCCHR Manual. Test and tag each reduced pressure backflow preventer upon initial installation (prior to continued water use) and [quarterly] [monthly]

[\_\_\_\_\_] thereafter. Tag shall contain the following information: make, model, serial number, dates of tests, results, maintenance performed, and signature of tester. Record test results on certification forms conforming to requirements cited earlier in this paragraph.

] [3.4 GRASS CUTTING

\*\*\*\*\*  
NOTE: Use the following paragraph for SOUTHDIV  
projects at the Charleston Air Force Base and for  
other SOUTHDIV projects as determined by the  
Contracting Officer based on project size, scope,  
complexity, and visibility.  
\*\*\*\*\*

Cut grass (or annual weeds) within the construction and storage sites to a maximum 100 mm 4 inch height at least once a week during the growing season unless the grass area is not visible to the public. Trim the grass around fences at time of grass cutting. Maintain grass or weeds on stockpiled earth as described above.

]

-- End of Section --