

\*\*\*\*\*  
USACE / NAVFAC / AFCEA / NASA UFGS-01 50 02.00 10 (April 2006)  
-----  
Preparing Activity: USACE Replacing without change  
UFGS-01500A (February 1997)

UNIFIED FACILITIES GUIDE SPECIFICATIONS

\*\*\*\*\*

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 50 02.00 10

TEMPORARY CONSTRUCTION FACILITIES

04/06

- 1.1 GENERAL REQUIREMENTS
  - 1.1.1 Site Plan
  - 1.1.2 Identification of Employees
  - 1.1.3 Employee Parking
- 1.2 AVAILABILITY AND USE OF UTILITY SERVICES
  - 1.2.1 Payment for Utility Services
  - 1.2.2 Meters and Temporary Connections
  - 1.2.3 Advance Deposit
  - 1.2.4 Final Meter Reading
  - 1.2.5 Sanitation
  - 1.2.6 Telephone
- 1.3 BULLETIN BOARD, PROJECT SIGN, AND PROJECT SAFETY SIGN
  - 1.3.1 Bulletin Board
  - 1.3.2 Project and Safety Signs
- 1.4 PROTECTION AND MAINTENANCE OF TRAFFIC
  - 1.4.1 Haul Roads
  - 1.4.2 Barricades
- 1.5 CONTRACTOR'S TEMPORARY FACILITIES
  - 1.5.1 Administrative Field Offices
  - 1.5.2 Storage Area
  - 1.5.3 Supplemental Storage Area
  - 1.5.4 Appearance of Trailers
  - 1.5.5 Maintenance of Storage Area
  - 1.5.6 New Building
  - 1.5.7 Security Provisions
- 1.6 GOVERNMENT FIELD OFFICE
  - 1.6.1 Resident Engineer's Office
  - 1.6.2 Trailer-Type Mobile Office
- 1.7 PLANT COMMUNICATION
- 1.8 TEMPORARY PROJECT SAFETY FENCING
- 1.9 CLEANUP
- 1.10 RESTORATION OF STORAGE AREA

-- End of Section Table of Contents --

\*\*\*\*\*  
USACE / NAVFAC / AFCEA / NASA UFGS-01 50 02.00 10 (April 2006)  
-----  
Preparing Activity: USACE Replacing without change  
UFGS-01500A (February 1997)

UNIFIED FACILITIES GUIDE SPECIFICATIONS

\*\*\*\*\*

SECTION 01 50 02.00 10

TEMPORARY CONSTRUCTION FACILITIES  
04/06

\*\*\*\*\*

NOTE: This guide specification covers the  
requirements for temporary construction facilities.

Comments and suggestions on this guide specification  
are welcome and should be directed to the technical  
proponent of the specification. A listing of  
technical proponents, including their organization  
designation and telephone number, is on the Internet.

Recommended changes to a UFGS should be submitted as  
a Criteria Change Request (CCR).

Use of electronic communication is encouraged.

Brackets are used in the text to indicate designer  
choices or locations where text must be supplied by  
the designer.

\*\*\*\*\*

1.1 GENERAL REQUIREMENTS

\*\*\*\*\*

NOTE: This guide specification includes  
requirements which may be included in projects when  
applicable. Requirements will be added, deleted, or  
modified as necessary to meet project requirements.

\*\*\*\*\*

1.1.1 Site Plan

The Contractor shall prepare a site plan indicating the proposed location  
and dimensions of any area to be fenced and used by the Contractor, the  
number of trailers to be used, avenues of ingress/egress to the fenced area  
and details of the fence installation. Any areas which may have to be  
graveled to prevent the tracking of mud shall also be identified. The  
Contractor shall also indicate if the use of a supplemental or other  
staging area is desired.

1.1.2 Identification of Employees

The Contractor shall be responsible for furnishing to each employee, and  
for requiring each employee engaged on the work to display, identification

as approved and directed by the Contracting Officer. Prescribed identification shall immediately be delivered to the Contracting Officer for cancellation upon release of any employee. When required, the Contractor shall obtain and provide fingerprints of persons employed on the project. Contractor and subContractor personnel shall wear identifying markings on hard hats clearly identifying the company for whom the employee works.

#### 1.1.3 Employee Parking

Contractor employees shall park privately owned vehicles in an area designated by the Contracting Officer. This area will be within reasonable walking distance of the construction site. Contractor employee parking shall not interfere with existing and established parking requirements of the military installation.

### 1.2 AVAILABILITY AND USE OF UTILITY SERVICES

#### 1.2.1 Payment for Utility Services

The Government will make all reasonably required utilities available to the Contractor from existing outlets and supplies, as specified in the contract. Unless otherwise provided in the contract, the amount of each utility service consumed shall be charged to or paid for by the Contractor at prevailing rates charged to the Government or, where the utility is produced by the Government, at reasonable rates determined by the Contracting Officer. The Contractor shall carefully conserve any utilities furnished without charge.

#### 1.2.2 Meters and Temporary Connections

The Contractor, at its expense and in a manner satisfactory to the Contracting Officer, shall provide and maintain necessary temporary connections, distribution lines, and meter bases (Government will provide meters) required to measure the amount of each utility used for the purpose of determining charges. The Contractor shall notify the Contracting Officer, in writing, 5 working days before final electrical connection is desired so that a utilities contract can be established. The Government will provide a meter and make the final hot connection after inspection and approval of the Contractor's temporary wiring installation. The Contractor shall not make the final electrical connection.

#### 1.2.3 Advance Deposit

An advance deposit for utilities consisting of an estimated month's usage or a minimum of \$50.00 will be required. The last monthly bills for the fiscal year will normally be offset by the deposit and adjustments will be billed or returned as appropriate. Services to be rendered for the next fiscal year, beginning 1 October, will require a new deposit. Notification of the due date for this deposit will be mailed to the Contractor prior to the end of the current fiscal year.

#### 1.2.4 Final Meter Reading

Before completion of the work and final acceptance of the work by the Government, the Contractor shall notify the Contracting Officer, in writing, 5 working days before termination is desired. The Government will take a final meter reading, disconnect service, and remove the meters. The Contractor shall then remove all the temporary distribution lines, meter

bases, and associated paraphernalia. The Contractor shall pay all outstanding utility bills before final acceptance of the work by the Government.

#### 1.2.5 Sanitation

The Contractor shall provide and maintain within the construction area minimum field-type sanitary facilities approved by the Contracting Officer. Government toilet facilities will not be available to Contractor's personnel.

#### 1.2.6 Telephone

The Contractor shall make arrangements and pay all costs for telephone facilities desired.

### 1.3 BULLETIN BOARD, PROJECT SIGN, AND PROJECT SAFETY SIGN

#### 1.3.1 Bulletin Board

Immediately upon beginning of work, the Contractor shall provide a weatherproof glass-covered bulletin board not less than 915 by 1220 mm 36 by 48 inches in size for displaying the Equal Employment Opportunity poster, a copy of the wage decision contained in the contract, Wage Rate Information poster, and other information approved by the Contracting Officer. The bulletin board shall be located at the project site in a conspicuous place easily accessible to all employees, as approved by the Contracting Officer. Legible copies of the aforementioned data shall be displayed until work is completed. Upon completion of work the bulletin board shall be removed by and remain the property of the Contractor.

#### 1.3.2 Project and Safety Signs

The requirements for the signs, their content, and location shall be as shown on the drawings. The signs shall be erected within 15 days after receipt of the notice to proceed. The data required by the safety sign shall be corrected daily, with light colored metallic or non-metallic numerals. Upon completion of the project, the signs shall be removed from the site.

### 1.4 PROTECTION AND MAINTENANCE OF TRAFFIC

During construction the Contractor shall provide access and temporary relocated roads as necessary to maintain traffic. The Contractor shall maintain and protect traffic on all affected roads during the construction period except as otherwise specifically directed by the Contracting Officer. Measures for the protection and diversion of traffic, including the provision of watchmen and flagmen, erection of barricades, placing of lights around and in front of equipment and the work, and the erection and maintenance of adequate warning, danger, and direction signs, shall be as required by the State and local authorities having jurisdiction. The traveling public shall be protected from damage to person and property. The Contractor's traffic on roads selected for hauling material to and from the site shall interfere as little as possible with public traffic. The Contractor shall investigate the adequacy of existing roads and the allowable load limit on these roads. The Contractor shall be responsible for the repair of any damage to roads caused by construction operations.

#### 1.4.1 Haul Roads

The Contractor shall, at its own expense, construct access and haul roads necessary for proper prosecution of the work under this contract. Haul roads shall be constructed with suitable grades and widths; sharp curves, blind corners, and dangerous cross traffic shall be avoided. The Contractor shall provide necessary lighting, signs, barricades, and distinctive markings for the safe movement of traffic. The method of dust control, although optional, shall be adequate to ensure safe operation at all times. Location, grade, width, and alignment of construction and hauling roads shall be subject to approval by the Contracting Officer. Lighting shall be adequate to assure full and clear visibility for full width of haul road and work areas during any night work operations. Upon completion of the work, haul roads designated by the Contracting Officer shall be removed.

#### 1.4.2 Barricades

The Contractor shall erect and maintain temporary barricades to limit public access to hazardous areas. Such barricades shall be required whenever safe public access to paved areas such as roads, parking areas or sidewalks is prevented by construction activities or as otherwise necessary to ensure the safety of both pedestrian and vehicular traffic. Barricades shall be securely placed, clearly visible with adequate illumination to provide sufficient visual warning of the hazard during both day and night.

### 1.5 CONTRACTOR'S TEMPORARY FACILITIES

#### 1.5.1 Administrative Field Offices

The Contractor shall provide and maintain administrative field office facilities within the construction area at the designated site. Government office and warehouse facilities will not be available to the Contractor's personnel.

#### 1.5.2 Storage Area

The Contractor shall construct a temporary 1.8 m 6 foot high chain link fence around trailers and materials. The fence shall include plastic strip inserts, colored [green] [brown], so that visibility through the fence is obstructed. Fence posts may be driven, in lieu of concrete bases, where soil conditions permit. Trailers, materials, or equipment shall not be placed or stored outside the fenced area unless such trailers, materials, or equipment are assigned a separate and distinct storage area by the Contracting Officer away from the vicinity of the construction site but within the military boundaries. Trailers, equipment, or materials shall not be open to public view with the exception of those items which are in support of ongoing work on any given day. Materials shall not be stockpiled outside the fence in preparation for the next day's work. Mobile equipment, such as tractors, wheeled lifting equipment, cranes, trucks, and like equipment, shall be parked within the fenced area at the end of each work day.

#### 1.5.3 Supplemental Storage Area

Upon Contractor's request, the Contracting Officer will designate another or supplemental area for the Contractor's use and storage of trailers, equipment, and materials. This area may not be in close proximity of the construction site but shall be within the military boundaries. Fencing of

materials or equipment will not be required at this site; however, the Contractor shall be responsible for cleanliness and orderliness of the area used and for the security of any material or equipment stored in this area. Utilities will not be provided to this area by the Government.

#### 1.5.4 Appearance of Trailers

Trailers utilized by the Contractor for administrative or material storage purposes shall present a clean and neat exterior appearance and shall be in a state of good repair. Trailers which, in the opinion of the Contracting Officer, require exterior painting or maintenance will not be allowed on the military property.

#### 1.5.5 Maintenance of Storage Area

Fencing shall be kept in a state of good repair and proper alignment. Should the Contractor elect to traverse, with construction equipment or other vehicles, grassed or unpaved areas which are not established roadways, such areas shall be covered with a layer of gravel as necessary to prevent rutting and the tracking of mud onto paved or established roadways; gravel gradation shall be at the Contractor's discretion. Grass located within the boundaries of the construction site shall be mowed for the duration of the project. Grass and vegetation along fences, buildings, under trailers, and in areas not accessible to mowers shall be edged or trimmed neatly.

#### 1.5.6 New Building

In the event a new building is constructed for the temporary project field office, it shall be a minimum 3.6 m 12 feet in width, 5 m 16 feet in length and have a minimum of 2.1 m 7 feet headroom. It shall be equipped with approved electrical wiring, at least one double convenience outlet and the required switches and fuses to provide 110-120 volt power. It shall be provided with a work table with stool, desk with chair, two additional chairs, and one legal size file cabinet that can be locked. The building shall be waterproof, shall be supplied with heater, shall have a minimum of two doors, electric lights, a telephone, a battery operated smoke detector alarm, a sufficient number of adjustable windows for adequate light and ventilation, and a supply of approved drinking water. Approved sanitary facilities shall be furnished. The windows and doors shall be screened and the doors provided with dead bolt type locking devices or a padlock and heavy duty hasp bolted to the door. Door hinge pins shall be non-removable. The windows shall be arranged to open and to be securely fastened from the inside. Glass panels in windows shall be protected by bars or heavy mesh screens to prevent easy access to the building through these panels. In warm weather, air conditioning capable of maintaining the office at 50 percent relative humidity and a room temperature 11 degrees C 20 degrees F below the outside temperature when the outside temperature is 35 degrees C 95 degrees F, shall be furnished. Any new building erected for a temporary field office shall be maintained by the Contractor during the life of the contract and upon completion and acceptance of the work shall become the property of the Contractor and shall be removed from the site. All charges for telephone service for the temporary field office shall be borne by the Contractor, including long distance charges up to a maximum of \$75.00 per month.

#### 1.5.7 Security Provisions

Adequate outside security lighting shall be provided at the Contractor's

temporary facilities. The Contractor shall be responsible for the security of its own equipment; in addition, the Contractor shall notify the appropriate law enforcement agency requesting periodic security checks of the temporary project field office.

## 1.6 GOVERNMENT FIELD OFFICE

### 1.6.1 Resident Engineer's Office

The Contractor shall provide the Government Resident Engineer with an office, approximately 19 square meters 200 square feet in floor area, located where directed and providing space heat, electric light and power, and toilet facilities consisting of one lavatory and one water closet complete with connections to water and sewer mains. A mail slot in the door or a lockable mail box mounted on the surface of the door shall be provided. At completion of the project, the office shall remain the property of the Contractor and shall be removed from the site. Utilities shall be connected and disconnected in accordance with local codes and to the satisfaction of the Contracting Officer.

### 1.6.2 Trailer-Type Mobile Office

The Contractor may, at its option, furnish and maintain a trailer-type mobile office acceptable to the Contracting Officer and providing as a minimum the facilities specified above. The trailer shall be securely anchored to the ground at all four corners to guard against movement during high winds.

## 1.7 PLANT COMMUNICATION

Whenever the Contractor has the individual elements of its plant so located that operation by normal voice between these elements is not satisfactory, the Contractor shall install a satisfactory means of communication, such as telephone or other suitable devices. The devices shall be made available for use by Government personnel.

## 1.8 TEMPORARY PROJECT SAFETY FENCING

As soon as practicable, but not later than 15 days after the date established for commencement of work, the Contractor shall furnish and erect temporary project safety fencing at the work site. The safety fencing shall be a high visibility orange colored, high density polyethylene grid or approved equal, a minimum of 1.1 m 42 inches high, supported and tightly secured to steel posts located on maximum 3 m 10 foot centers, constructed at the approved location. The safety fencing shall be maintained by the Contractor during the life of the contract and, upon completion and acceptance of the work, shall become the property of the Contractor and shall be removed from the work site.

## 1.9 CLEANUP

Construction debris, waste materials, packaging material and the like shall be removed from the work site daily. Any dirt or mud which is tracked onto paved or surfaced roadways shall be cleaned away. Materials resulting from demolition activities which are salvageable shall be stored within the fenced area described above or at the supplemental storage area. Stored material not in trailers, whether new or salvaged, shall be neatly stacked when stored.

#### 1.10 RESTORATION OF STORAGE AREA

Upon completion of the project and after removal of trailers, materials, and equipment from within the fenced area, the fence shall be removed and will become the property of the Contractor. Areas used by the Contractor for the storage of equipment or material, or other use, shall be restored to the original or better condition. Gravel used to traverse grassed areas shall be removed and the area restored to its original condition, including top soil and seeding as necessary.

-- End of Section --