
USACE / NAVFAC / AFCEA UFGS-15995A (July 2003)

Preparing Activity: USACE Superseding
UFGS-15995A (December 2001)

UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UMRL dated 22 December 2004

Latest change indicated by CHG tags

SECTION TABLE OF CONTENTS

DIVISION 15 - MECHANICAL

SECTION 15995A

COMMISSIONING OF HVAC SYSTEMS

07/03

PART 1 GENERAL

- 1.1 SUBMITTALS
- 1.2 SEQUENCING AND SCHEDULING

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

- 3.1 COMMISSIONING TEAM AND CHECKLISTS
- 3.2 TESTS
 - 3.2.1 Pre-Commissioning Checks
 - 3.2.2 Functional Performance Tests

-- End of Section Table of Contents --

USACE / NAVFAC / AFCEA UFGS-15995A (July 2003)

Preparing Activity: USACE Superseding
UFGS-15995A (December 2001)

UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UMRL dated 22 December 2004

Latest change indicated by CHG tags

SECTION 15995A

COMMISSIONING OF HVAC SYSTEMS 07/03

NOTE: This guide specification covers the requirements for commissioning of HVAC systems.

Comments and suggestions on this guide specification are welcome and should be directed to the technical proponent of the specification. A listing of technical proponents, including their organization designation and telephone number, is on the Internet.

Recommended changes to a UFGS should be submitted as a Criteria Change Request (CCR).

Use of electronic communication is encouraged.

Brackets are used in the text to indicate designer choices or locations where text must be supplied by the designer.

PART 1 GENERAL

NOTE: Use of this specification is mandatory for all projects. A properly functioning HVAC system assures a comfortable, healthy and productive environment for the user. The "Design Agent's Representative" will be a member of the HVAC design team, i.e. from the AE or Engineering Division. The "Design Agent's Representative" will actively participate in the process, including review of all submittals contained herein.

1.1 SUBMITTALS

NOTE: Submittals must be limited to those necessary for adequate quality control. The importance of an

item in the project should be one of the primary factors in determining if a submittal for the item should be required.

A "G" following a submittal item indicates that the submittal requires Government approval. Some submittals are already marked with a "G". Only delete an existing "G" if the submittal item is not complex and can be reviewed through the Contractor's Quality Control system. Only add a "G" if the submittal is sufficiently important or complex in context of the project.

For submittals requiring Government approval on Army projects, a code of up to three characters within the submittal tags may be used following the "G" designation to indicate the approving authority. Codes for Army projects using the Resident Management System (RMS) are: "AE" for Architect-Engineer; "DO" for District Office (Engineering Division or other organization in the District Office); "AO" for Area Office; "RO" for Resident Office; and "PO" for Project Office. Codes following the "G" typically are not used for Navy projects.

Submittal items not designated with a "G" are considered as being for information only for Army projects and for Contractor Quality Control approval for Navy projects.

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are [for Contractor Quality Control approval.] [for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government.] The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Commissioning Team

List of team members who will represent the Contractor in the pre-commissioning checks and functional performance testing, at least 2 weeks prior to the start of pre-commissioning checks. Proposed revision to the list, prior to the start of the impacted work.

Tests

Detailed procedures for pre-commissioning checks and functional performance tests, at least 4 weeks prior to the start of pre-commissioning checks.

Pre-Commissioning Checks[; G][; G, [____]]

Schedule for pre-commissioning checks and functional performance tests, at least 2 weeks prior to the start of pre-commissioning

checks.

SD-06 Test Reports

Test Reports[; G][; G, [____]]

Completed pre-commissioning checklists and functional performance test checklists organized by system and by subsystem and submitted as one package. The results of failed tests shall be included along with a description of the corrective action taken.

1.2 SEQUENCING AND SCHEDULING

NOTE: Provide seismic requirements, if a Government designer (either Corps office of A/E) is the Engineer of Record, and show on the drawings. Delete the bracketed phrase if seismic details are not included. Sections 13080 and 15070, properly edited, must be included in the contract documents.

The work described in this Section shall begin only after all work required in related Sections, including Section 15951 DIRECT DIGITAL CONTROL FOR HVAC AND OTHER LOCAL BUILDING SYSTEMS and Section 15990A TESTING, ADJUSTING, AND BALANCING OF HVAC SYSTEMS, has been successfully completed, and all test and inspection reports and operation and maintenance manuals required in these Sections have been submitted and approved. Seismic details shall be in accordance with Sections 13080 SEISMIC PROTECTION FOR MISCELLANEOUS EQUIPMENT and 15070A SEISMIC PROTECTION FOR MECHANICAL EQUIPMENT [as indicated]

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 COMMISSIONING TEAM AND CHECKLISTS

NOTE: The "Design Agent's Representative" will be included as a member of the commissioning team for the pre-commissioning checklists and will participate in the functional performance tests.

The checklists provided are to be used as guides for the preparation of project checklists. The appropriate checklist should be included in the project specification for each HVAC equipment component. The designer will add additional checklists for equipment or systems not included in this guide specification or modify the checklists where necessary for specific project requirements. If, for example, a system needs to be tested with certain internal load, each appropriate checklist should be modified to include this requirement along with specifics on how load should be generated.

The Contractor shall designate team members to participate in the pre-commissioning checks and the functional performance testing specified herein. In addition, the Government will be represented by a representative of the Contracting Officer, the Design Agent's Representative, and the Using Agency. The team members shall be as follows:

Designation	Function
Q	Contractor's Chief Quality Control Representative
M	Contractor's Mechanical Representative
E	Contractor's Electrical Representative
T	Contractor's Testing, Adjusting, and Balancing
Representative	
C	Contractor's Controls Representative
D	Design Agent's Representative
O	Contracting Officer's Representative
U	Using Agency's Representative

Appendices A and B are provided as a general checklist and have been prepared to best match the various equipment selected during the design of this project. Each checklist shown in Appendices A and B shall be reviewed and modified as necessary to reflect equipment actually installed during construction of the project. The commissioning team shall review the accuracy and applicability of each item in the checklist and revise as needed. Equipment shown in the checklist but not installed for the project shall be annotated as "NA". Likewise, equipment installed but not listed in the checklist shall be added or revised accordingly. A note as to why it was added or revised shall be inserted with the reviewer's initial. The commissioning team shall also add or modify to any of the equipment checklist items as required and/or specified by the equipment manufacturer.

Acceptance by each commissioning team member of each pre-commissioning checklist item shall be indicated by initials and date, unless an "X" is shown indicating that participation by that individual is not required. Acceptance by each commissioning team member of each functional performance test checklist shall be indicated by signature and date.

3.2 TESTS

The pre-commissioning checks and functional performance tests shall be performed in a manner which essentially duplicates the checking, testing, and inspection methods established in the related Sections. Where checking, testing, and inspection methods are not specified in other Sections, methods shall be established which will provide the information required. Testing and verification required by this section shall be performed during the Commissioning phase. Requirements in related Sections are independent from the requirements of this Section and shall not be used to satisfy any of the requirements specified in this Section. The Contractor shall provide all materials, services, and labor required to perform the pre-commissioning checks and functional performance tests. A pre-commissioning check or functional performance test shall be aborted if any system deficiency prevents the successful completion of the test or if any participating non-Government commissioning team member of which participation is specified is not present for the test. The Contractor shall reimburse the Government for all costs associated with effort lost due to tests that are aborted. These costs shall include salary, travel costs and per diem (where applicable) for Government commissioning team members. The Contractor shall submit Test Reports as specified in the Submittals paragraph.

3.2.1 Pre-Commissioning Checks

Pre-commissioning checks shall be performed for the items indicated on the checklists in Appendix A. Deficiencies discovered during these checks shall be corrected and retested in accordance with the applicable contract requirements.

3.2.2 Functional Performance Tests

Functional performance tests shall be performed for the items indicated on the checklists in Appendix B. Functional performance tests shall begin only after all pre-commissioning checks have been successfully completed. Tests shall prove all modes of the sequences of operation, and shall verify all other relevant contract requirements. Tests shall begin with equipment or components and shall progress through subsystems to complete systems. Upon failure of any functional performance test checklist item, the Contractor shall correct all deficiencies in accordance with the applicable contract requirements. The checklist shall then be repeated until it has been completed with no errors.

APPENDIX A

PRE-COMMISSIONING CHECKLISTS

Pre-commissioning checklist - Piping

For [_____] Piping System

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Piping complete.	___	___	X	___	X	___	___	___
b. As-built shop drawings submitted.	___	___	X	___	X	___	___	___
c. Piping flushed and cleaned.	___	___	X	___	X	___	___	___
d. Strainers cleaned.	___	___	X	___	X	___	___	___
e. Valves installed as required.	___	___	X	___	X	___	___	___
f. Piping insulated as required.	___	___	X	___	X	___	___	___
g. Thermometers and gauges installed as required.	___	___	X	___	X	___	___	___
h. Verify operation of valves.	___	___	X	___	___	___	___	___
i. Air vents installed as specified.	___	___	X	X	X	___	___	___
j. Flexible connectors installed as specified	___	___	X	X	X	___	___	___
k. Verify that piping has been labeled and valves identified as specified.	___	___	X	___	___	___	___	___
Testing, Adjusting, and Balancing (TAB)								
a. Hydrostatic test complete.	___	___	X	___	X	___	___	___
b. TAB operation complete.	___	___	X	___	___	___	___	___

Pre-commissioning Checklist - Ductwork

For Air Handler: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Ductwork complete.	___	___	X	___	X	___	___	___
b. As-built shop drawings submitted.	___	___	X	___	X	___	___	___
c. Ductwork leak test complete.	___	___	X	___	X	___	___	___
NOTE: The first bracketed item d will be used for Army projects, the second for Air Force projects.								
[d. Fire dampers, smoke dampers, and access doors installed as required.	___	___	X	___	X	___	___	___]
[d. Fire dampers, smoke dampers, and access doors installed as required with installation of each verified by the specified team members initialing each location on a copy of the as-built drawings.	___	___	X	___	X	___	___	___]
e. Ductwork insulated as required.	___	___	X	___	X	___	___	___
f. Thermometers and gauges installed as required.	___	___	___	___	___	___	___	___
g. Verify open/closed status of dampers.	___	___	X	___	X	___	___	___
h. Verify smoke and fire damper operation.	___	___	X	___	___	___	___	___
i. Flexible connectors installed as specified	___	___	X	___	X	___	___	___
Testing, Adjusting, and Balancing (TAB)								
a. TAB operation complete.	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - Multizone Air Handling Unit

For Air Handling Unit: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Vibration isolation devices installed [and freed to float with adequate movement and seismic restraint] as specified.	___	___	X	X	X	___	___	___
b. Inspection and access doors are operable and sealed.	___	___	X	___	X	___	___	___
c. Casing undamaged.	___	___	X	X	X	___	___	___
d. Insulation undamaged.	___	___	X	X	X	___	___	___
e. Condensate drainage is unobstructed. (Visually verify pan drains completely by pouring a cup of water into drain pan.)	___	___	X	X	X	___	___	___
f. Fan belt adjusted.	___	___	X	___	X	___	___	___
g. Manufacturer's required maintenance clearance provided.	___	___	X	X	X	___	___	___
Electrical								
a. Power available to unit disconnect.	___	___	___	X	___	___	___	___
b. Power available to unit control panel.	___	___	___	X	___	___	___	___
c. Proper motor rotation verified.	___	___	___	___	X	___	___	___
d. Verify that power disconnect is located within sight of the unit it controls.	___	___	___	X	___	___	___	___
[e. Power available to electric heating coil.	___	___	___	X	___	___	___	___]
Coils								
[a. Chilled water piping properly connected.	___	___	X	X	X	___	___	___]
[a. Refrigerant piping properly connected.	___	___	X	X	X	___	___	___]
[b. Chilled water piping pressure tested.	___	___	X	X	X	___	___	___]
[b. Refrigerant piping pressure tested.	___	___	X	X	X	___	___	___]
[c. Hot water piping properly connected.	___	___	X	X	X	___	___	___]
[c. Steam and condensate piping properly connected.	___	___	X	X	X	___	___	___]
[d. Hot water piping pressure tested.	___	___	X	X	X	___	___	___]

Pre-commissioning Checklist - Multizone Air Handling Unit

For Air Handling Unit: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
[d. Steam and condensate piping pressure tested.	___	___	X	X	X	___	___	___]
e. Air vents installed on water coils [with shutoff valves] as specified.	___	___	X	X	X	___	___	___
f. Any damage to coil fins has been repaired	___	___	X	___	X	___	___	___

Controls

a. Control valves/actuators properly installed.	___	___	X	___	___	___	___	___
b. Control valves/actuators operable.	___	___	X	___	___	___	___	___
c. O.A. dampers/actuators properly installed.	___	___	X	___	___	___	___	___
d. O.A. dampers/actuators operable.	___	___	X	___	___	___	___	___
e. Zone dampers/actuators properly installed.	___	___	X	___	___	___	___	___
f. Zone dampers/actuators operable.	___	___	X	___	___	___	___	___

Testing, Adjusting, and Balancing (TAB)

a. Construction filters removed and replaced.	___	___	X	___	X	___	___	___
b. TAB report submitted.	___	___	X	___	X	___	___	___
c. TAB results within limits specified in Section 15990A	___	___	___	___	___	___	___	___
d. TAB results for outside air intake within limits specified in Section 15990A	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - Variable Volume Air Handling Unit

For Air Handling Unit: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Vibration isolation devices installed.	___	___	X	X	X	___	___	___
b. Inspection and access doors are operable and sealed.	___	___	X	___	X	___	___	___
c. Casing undamaged.	___	___	X	X	X	___	___	___
d. Insulation undamaged.	___	___	X	X	X	___	___	___
e. Condensate drainage is unobstructed. (Visually verify drainage by pouring a cup of water into drain pan.)	___	___	X	X	X	___	___	___
f. Fan belt adjusted.	___	___	X	___	X	___	___	___
g. Manufacturer's required maintenance clearance provided.	___	___	X	X	X	___	___	___
Electrical								
a. Power available to unit disconnect.	___	___	___	X	X	___	___	___
b. Power available to unit control panel.	___	___	___	X	___	___	___	___
c. Proper motor rotation verified.	___	___	___	___	X	___	___	___
d. Verify that power disconnect is located within sight of the unit it controls.	___	___	___	X	___	___	___	___
[e. Power available to electric heating coil.	___	___	___	X	X	___	___	___]
Coils								
[a. Chilled water piping properly connected.	___	___	X	X	X	___	___	___]
[a. Refrigerant piping properly connected.	___	___	X	X	X	___	___	___]
[b. Chilled water piping pressure tested.	___	___	X	X	X	___	___	___]
[b. Refrigerant piping pressure tested.	___	___	X	X	X	___	___	___]
[c. Hot water piping properly connected.	___	___	X	X	X	___	___	___]
[c. Steam and condensate piping properly connected.	___	___	X	X	X	___	___	___]
[d. Hot water piping pressure tested.	___	___	X	X	X	___	___	___]
[d. Steam and condensate piping pressure tested.	___	___	X	X	X	___	___	___]

Pre-commissioning Checklist - Variable Volume Air Handling Unit

For Air Handling Unit: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
[e. Air vents installed on water coils [with shutoff valves] as specified.	___	___	X	X	X	___	___	___]
f. Any damage to coil fins has been repaired.	___	___	X	___	X	___	___	___

Controls

a. Control valves/actuators properly installed.	___	___	X	___	___	___	___	___
b. Control valves/actuators operable.	___	___	X	___	___	___	___	___
c. Dampers/actuators properly installed.	___	___	X	___	___	___	___	___
d. Dampers/actuators operable.	___	___	X	___	___	___	___	___
e. Verify proper location, installation and calibration of duct static pressure sensor.	___	___	X	___	___	___	___	___
f. Fan air volume controller operable.	___	___	X	___	___	___	___	___
g. Air handler controls system operational.	___	___	X	___	___	___	___	___

Testing, Adjusting, and Balancing (TAB)

a. Construction filters removed and replaced.	___	___	X	___	___	___	___	___
b. TAB report submitted.	___	___	X	___	X	___	___	___
c. TAB results within limits specified in Section 15990A	___	___	___	___	___	___	___	___
d. TAB results for outside air intake within limits specified in Section 15990A	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - VAV Terminal

For VAV Terminal: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. VAV terminal in place.	___	___	X	X	X	___	___	___
b. VAV terminal ducted.	___	___	X	X	X	___	___	___
c. VAV terminal connected to controls.	___	___	X	X	___	___	___	___
[d. Reheat coil connected to hot water pipe.	___	___	X	___	X	___	___	___]
[e. Electric reheat coil connected to local disconnect.	___	___	___	___	X	___	___	___]
f. Manufacturer's required maintenance clearance provided.	___	___	X	X	X	___	___	___
Controls								
a. Cooling only VAV terminal controls set.	___	___	X	X	___	___	___	___
b. Cooling only VAV controls verified.	___	___	X	X	___	___	___	___
c. Reheat VAV terminal controls set.	___	___	X	X	___	___	___	___
d. Reheat terminal/coil controls verified.	___	___	X	X	___	___	___	___
Testing, Adjusting, and Balancing (TAB)								
a. Verify terminal maximum air flow set.	___	___	X	___	___	___	___	___
b. Verify terminal minimum air flow set.	___	___	X	___	___	___	___	___
c. TAB operation complete.	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - DX Air Cooled Condensing Unit

For Condensing Unit: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation	___	___	X	X	X	___	___	___
b. Refrigerant pipe leak tested.	___	___	X	X	X	___	___	___
c. Refrigerant pipe evacuated and charged in accordance with manufacturer's instructions.	___	___	X	X	X	___	___	___
d. Check condenser fans for proper rotation.	___	___	X	___	X	___	___	___
e. Any damage to coil fins has been repaired.	___	___	X	___	X	___	___	___
f. Manufacturer's required maintenance/operational clearance provided.	___	___	X	X	X	___	___	___
Electrical								
a. Power available to unit disconnect.	___	___	___	X	X	___	___	___
b. Power available to unit control panel.	___	___	___	X	___	___	___	___
c. Verify that power disconnect is located within sight of the unit it controls	___	___	___	X	___	___	___	___
Controls								
a. Unit safety/protection devices tested.	___	___	X	X	___	___	___	___
b. Control system and interlocks installed.	___	___	X	X	___	___	___	___
c. Control system and interlocks operational.	___	___	X	X	___	___	___	___

Pre-commissioning Checklist - Pumps

For Pump: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Pumps grouted in place.	___	___	X	X	X	___	___	___
b. Pump vibration isolation devices functional.	___	___	X	X	X	___	___	___
c. Pump/motor coupling alignment verified.	___	___	X	X	X	___	___	___
d. Piping system installed.	___	___	X	X	X	___	___	___
e. Piping system pressure tested.	___	___	X	X	X	___	___	___
f. Pump not leaking.	___	___	X	X	X	___	___	___
g. Field assembled couplings aligned to meet manufacturer's prescribed tolerances. _____	___	___	X	X	X	___	___	___
Electrical								
a. Power available to pump disconnect.	___	___	___	X	X	___	___	___
b. Pump rotation verified.	___	___	___	X	X	___	___	___
c. Control system interlocks functional.	___	___	___	X	___	___	___	___
d. Verify that power disconnect is located within sight of the unit it controls.	___	___	___	X	___	___	___	___
Testing, Adjusting, and Balancing (TAB)								
a. Pressure/temperature gauges installed.	___	___	X	___	X	___	___	___
b. Piping system cleaned.	___	___	X	X	X	___	___	___
c. Chemical water treatment complete.	___	___	X	X	X	___	___	___
d. Water balance complete.	___	___	X	___	X	___	___	___
e. Water balance with design maximum flow.	___	___	X	___	X	___	___	___
f. TAB Report submitted.	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - Packaged Air Cooled Chiller

For Chiller: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Chiller properly piped.	___	___	X	___	___	___	___	___
b. Chilled water pipe leak tested.	___	___	X	X	X	___	___	___
c. Verify that refrigerant used complies with specified requirements.	___	___	X	X	X	___	___	___
d. Any damage to coil fins has been repaired.	___	___	X	___	X	___	___	___
e. Manufacturer's required maintenance clearance provided.	___	___	X	X	X	___	___	___
Electrical								
a. Power available to unit disconnect.	___	___	___	X	___	___	___	___
b. Power available to unit control panel.	___	___	___	X	___	___	___	___
c. Separate power is supplied to electric heating tape.	___	___	___	X	___	___	___	___
d. Verify that power disconnect is located within sight of the unit it controls.	___	___	___	X	___	___	___	___
Controls								
a. Factory startup and checkout complete.	___	___	X	X	___	___	___	___
b. Chiller safety/protection devices tested.	___	___	X	X	___	___	___	___
c. Chilled water flow switch installed.	___	___	X	X	___	___	___	___
d. Chilled water flow switch tested.	___	___	X	X	___	___	___	___
e. Chilled water pump interlock installed.	___	___	X	X	X	___	___	___
f. Chilled water pump interlock tested.	___	___	___	X	___	___	___	___

Pre-commissioning Checklist - Centrifugal Chiller

For Chiller: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Chilled water connections properly piped.	___	___	X	___	___	___	___	___
b. Condenser water connections properly piped	___	___	X	___	___	___	___	___
c. Chilled water pipe leak tested.	___	___	X	X	X	___	___	___
d. Condenser water pipe leak tested.	___	___	X	X	X	___	___	___
e. High efficiency purge unit installed and operating as specified.	___	___	X	X	X	___	___	___
f. Refrigerant leak detector installed.	___	___	___	___	___	___	___	___
g. Oxygen sensor installed and tested.	___	___	___	___	___	___	___	___
h. Mechanical room ventilation installed as specified.	___	___	___	___	___	___	___	___
i. Manufacturer's required maintenance clearance provided.	___	___	X	X	___	___	___	___
j. Field assembled couplings aligned to meet manufacturer's prescribed tolerances.	___	___	X	X	X	___	___	___
Electrical								
a. Power available to unit starter.	___	___	___	X	___	___	___	___
b. Power available to unit control panel.	___	___	___	X	___	___	___	___
c. Verify that power disconnect is located within sight of the unit it controls.	___	___	___	X	___	___	___	___
Controls								
a. Factory startup and checkout complete.	___	___	X	X	___	___	___	___
b. Chiller safety/protection devices tested.	___	___	___	X	___	___	___	___
c. Chilled water flow switch installed.	___	___	X	X	___	___	___	___
d. Chilled water flow switch tested.	___	___	X	X	___	___	___	___
e. Chilled water pump interlock installed.	___	___	___	X	___	___	___	___
f. Chilled water pump interlock tested.	___	___	___	X	___	___	___	___
g. Condenser water flow switch installed.	___	___	X	___	___	___	___	___
h. Condenser water flow switch tested.	___	___	___	X	___	___	___	___

Pre-commissioning Checklist - Centrifugal Chiller

For Chiller: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
i. Condenser water pump interlock installed.	___	___	___	X	___	___	___	___
j. Condenser water pump interlock tested.	___	___	___	X	___	___	___	___

Pre-commissioning Checklist - Cooling Tower

For Cooling Tower: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Cooling tower in place.	___	___	X	___	___	___	___	___
b. Cooling tower piped.	___	___	X	X	___	___	___	___
c. Cooling tower fan drive adjusted.	___	___	___	___	X	___	___	___
d. Cooling tower makeup water supply piped.	___	___	X	X	___	___	___	___
e. Verify makeup control valve shutoff.	___	___	X	___	X	___	___	___
f. Fan lubricated and blade pitch adjusted.	___	___	X	___	X	___	___	___
g. Manufacturer's required maintenance/ operational clearance provided.	___	___	X	X	X	___	___	___
Electrical								
a. Power available to tower disconnect.	___	___	___	X	___	___	___	___
b. Power available to electric sump heater and heater functional.	___	___	___	X	___	___	___	___
c. Control system interlocks functional.	___	___	___	X	___	___	___	___
d. Motor and fan rotation checked.	___	___	___	X	___	___	___	___
e. Verify that power disconnect is located within sight of the unit's controls.	___	___	___	X	___	___	___	___
Piping								
a. Tower basin is clean and filled.	___	___	X	X	X	___	___	___
b. Condenser water treatment functional.	___	___	X	X	X	___	___	___
c. Water balance with design flow verified.	___	___	X	___	X	___	___	___
d. Water distribution headers balanced.	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - Hot Water Boiler

For Boiler: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Boiler flue installed.	___	___	X	___	___	___	___	___
b. Boiler hot water piping installed.	___	___	X	___	___	___	___	___
c. Boiler hot water piping tested.	___	___	X	X	___	___	___	___
d. Boiler makeup water piping installed.	___	___	X	___	___	___	___	___
e. Boiler fuel oil piping installed.	___	___	X	X	X	___	___	___
f. Boiler fuel oil piping tested.	___	___	X	X	X	___	___	___
g. Boiler gas piping installed.	___	___	X	X	X	___	___	___
h. Boiler gas piping tested.	___	___	X	X	X	___	___	___
i. Manufacturer's required maintenance clearance provided.	___	___	X	___	___	___	___	___
Startup								
a. Boiler system cleaned and filled with treated water.	___	___	X	___	___	___	___	___
b. Boiler safety/protection devices, including high temperature burner shut-off, low water cutoff, flame failure, pre and post purge, have been tested.	___	___	___	X	___	___	___	___
c. Verify that PRV rating conforms to boiler rating.	___	___	___	X	___	___	___	___
d. Boiler water treatment system functional.	___	___	X	X	___	___	___	___
e. Boiler startup and checkout complete.	___	___	X	X	___	___	___	___
f. Combustion efficiency demonstrated.	___	___	X	___	X	___	___	___
Electrical								
a. Verify that power disconnect is located within sight of the unit served.	___	___	___	X	___	___	___	___
Controls								
a. Hot water pump interlock installed.	___	___	___	X	___	___	___	___
b. Hot water pump interlock tested.	___	___	___	X	___	___	___	___
c. Hot water heating system balanced.	___	___	X	X	___	___	___	___

Pre-commissioning Checklist - Hot Water Boiler

For Boiler: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
d. Hot water heating controls operational.	___	___	X	X	___	___	___	___

Pre-commissioning Checklist - Steam Boiler

For Boiler: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Boiler flue installed.	___	___	X	X	X	___	___	___
b. Boiler steam piping installed.	___	___	X	X	X	___	___	___
c. Boiler steam piping tested.	___	___	X	X	X	___	___	___
d. Boiler makeup water piping installed.	___	___	X	___	X	___	___	___
e. Boiler makeup water piping tested.	___	___	X	X	X	___	___	___
f. Boiler fuel oil piping installed.	___	___	X	X	X	___	___	___
g. Boiler fuel oil piping tested.	___	___	X	X	X	___	___	___
h. Boiler gas piping installed.	___	___	X	X	X	___	___	___
i. Boiler gas piping tested.	___	___	X	X	X	___	___	___
j. Manufacturer's required maintenance clearance provided.	___	___	X	X	X	___	___	___
Startup								
a. Boiler system cleaned and filled with treated water.	___	___	X	X	X	___	___	___
b. Boiler safety/protection devices, including high temperature burner shut-off, low water cutoff, flame failure, pre and post purge, have been tested.	___	___	___	X	___	___	___	___
c. Verify that PRV rating conforms to boiler rating.	___	___	___	X	___	___	___	___
d. Boiler feed water system operational.	___	___	___	X	___	___	___	___
e. Boiler water treatment system functional.	___	___	X	X	X	___	___	___
f. Boiler startup and checkout complete.	___	___	___	X	___	___	___	___
g. All steam traps operational.	___	___	X	X	X	___	___	___
h. All condensate return pumps operational.	___	___	___	___	X	___	___	___
i. Combustion efficiency demonstrated.	___	___	X	___	X	___	___	___
Electrical								
a. Verify that power disconnect is located within sight of the unit served.	___	___	___	X	___	___	___	___

Pre-commissioning Checklist - Steam/Hot Water Converter

For Converter: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Converter steam piping installed.	___	___	X	___	X	___	___	___
b. Converter steam piping tested.	___	___	X	X	X	___	___	___
c. Hot water piping installed.	___	___	X	___	___	___	___	___
d. Hot water piping tested.	___	___	X	X	X	___	___	___
e. Makeup water piping installed.	___	___	X	X	X	___	___	___
f. Vacuum breaker installed on shell of shell and tube unit.	___	___	X	X	X	___	___	___
g. Air vent installed as specified.	___	___	X	X	X	___	___	___
h. Manufacturer's required maintenance clearance provided.	___	___	X	X	X	___	___	___
Startup								
a. Hot water system cleaned and filled.	___	___	X	X	X	___	___	___
b. All steam traps operational.	___	___	X	X	X	___	___	___
c. All condensate return pumps operational.	___	___	___	X	___	___	___	___
d. Converter safety/protection devices tested.	___	___	X	X	X	___	___	___
e. Converter startup and checkout complete.	___	___	X	X	X	___	___	___
Controls								
a. Control valves/actuators properly installed.	___	___	X	___	___	___	___	___
b. Control valves/actuators operable.	___	___	X	___	___	___	___	___

Pre-commissioning Checklist - Fan Coil Unit

For Fan Coil Unit: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Vibration isolation devices installed.	___	___	X	X	X	___	___	___
b. Access doors/removable panels are operable and sealed.	___	___	X	___	X	___	___	___
c. Casing undamaged.	___	___	X	X	X	___	___	___
d. Insulation undamaged.	___	___	X	X	X	___	___	___
e. Condensate drainage is unobstructed.	___	___	X	X	X	___	___	___
f. Fan belt adjusted.	___	___	X	___	X	___	___	___
g. Any damage to coil fins has been repaired.	___	___	X	___	X	___	___	___
h. Manufacturer's required maintenance clearance provided.	___	___	X	X	X	___	___	___
Electrical								
a. Power available to unit disconnect.	___	___	___	X	___	___	___	___
b. Power available to unit control panel.	___	___	___	X	___	___	___	___
c. Proper motor rotation verified.	___	___	___	___	X	___	___	___
d. Verify that power disconnect is located within sight of the unit it controls.	___	___	___	X	___	___	___	___
[e. Power available to electric heating coil.	___	___	___	X	X	___	___	___]
Coils								
[a. Dual temperature piping properly connected.	___	___	X	___	___	___	___	___]
[a. Chilled water piping properly connected.	___	___	X	X	X	___	___	___]
[b. Dual temperature piping pressure tested.	___	___	X	___	___	___	___	___]
[b. Chilled water piping pressure tested.	___	___	X	X	X	___	___	___]
[c. Hot water piping properly connected.	___	___	X	___	___	___	___	___]
[d. Hot water piping pressure tested.	___	___	X	___	___	___	___	___]
Controls								
a. Control valves/actuators properly installed.	___	___	X	___	___	___	___	___

Pre-commissioning Checklist - Fan Coil Unit

For Fan Coil Unit: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
b. Control valves/actuators operable.	___	___	X	X	___	___	___	___
c. Verify proper location and installation of thermostat.	___	___	X	___	___	___	___	___
Testing, Adjusting, and Balancing (TAB)								
a. Construction filters removed and replaced.	___	___	X	___	___	___	___	___
b. TAB results within limits specified in Section 15990A								
c. TAB Report submitted.	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - Unit Heater

For Unit Heater: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
[a. Hot water piping properly connected.	___	___	X	___	___	___	___	___]
[a. Steam and condensate piping properly connected.	___	___	X	X	X	___	___	___]
[b. Hot water piping pressure tested.	___	___	X	___	___	___	___	___]
[b. Steam and condensate piping pressure tested.	___	___	X	X	X	___	___	___]
c. Air vent installed on hot water coil with shutoff valve as specified.	___	___	X	X	X	___	___	___
d. Any damage to coil fins has been repaired.	___	___	X	___	X	___	___	___
e. Manufacturer's required maintenance/operational clearance provided.	___	___	X	X	X	___	___	___
Electrical								
a. Power available to unit disconnect.	___	___	___	X	___	___	___	___
b. Proper motor rotation verified.	___	___	___	X	X	___	___	___
c. Verify that power disconnect is located within sight of the unit it controls.	___	___	___	X	___	___	___	___
d. Power available to electric heating coil.	___	___	___	X	___	___	___	___
Controls								
a. Control valves properly installed.	___	___	X	___	___	___	___	___
b. Control valves operable.	___	___	X	X	___	___	___	___
c. Verify proper location and installation of thermostat.	___	___	X	___	___	___	___	___
Testing, Adjusting, and Balancing (TAB)								
a. TAB Report submitted.	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - Exhaust Fan

For Exhaust Fan: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Fan belt adjusted.	___	___	X	___	X	___	___	___
Electrical								
a. Power available to fan disconnect.	___	___	___	X	___	___	___	___
b. Proper motor rotation verified.	___	___	___	___	X	___	___	___
c. Verify that power disconnect is located within sight of the unit it controls.	___	___	___	X	___	___	___	___
Controls								
a. Control interlocks properly installed.	___	___	___	X	___	___	___	___
b. Control interlocks operable.	___	___	___	X	___	___	___	___
c. Dampers/actuators properly installed.	___	___	X	___	___	___	___	___
d. Dampers/actuators operable.	___	___	X	___	___	___	___	___
e. Verify proper location and installation of thermostat.	___	___	X	___	___	___	___	___
Testing, Adjusting, and Balancing (TAB)								
a. TAB results within limits specified in Section 15990A	___	___	X	___	X	___	___	___
b. TAB Report submitted.	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - Computer Room Unit

For Computer Room Unit: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Unit properly supported.	___	___	X	X	X	___	___	___
b. Access doors are operable and sealed.	___	___	X	___	X	___	___	___
c. Casing undamaged.	___	___	X	X	X	___	___	___
d. Insulation undamaged.	___	___	X	X	X	___	___	___
e. Condensate drainage is unobstructed and routed to floor drain.	___	___	X	X	X	___	___	___
f. Fan belt adjusted.	___	___	X	___	X	___	___	___
g. Manufacturer's required maintenance operational clearance provided.	___	___	X	X	X	___	___	___
Electrical								
a. Power available to unit disconnect.	___	___	___	X	X	___	___	___
b. Proper motor rotation verified.	___	___	___	___	X	___	___	___
c. Proper motor rotation verified.	___	___	___	___	X	___	___	___
d. Verify that power disconnect is located within sight of the unit it controls.	___	___	___	X	___	___	___	___
[e. Power available to reheat coils.	___	___	___	___	X	___	___	___]
Coils/Humidifier								
[a. Chilled water piping properly connected.	___	___	X	___	___	___	___	___]
[a. Refrigerant piping properly connected.	___	___	X	X	X	___	___	___]
[b. Chilled water piping pressure tested.	___	___	X	X	X	___	___	___]
[b. Refrigerant piping pressure tested.	___	___	X	X	X	___	___	___]
[c. Hot water piping properly connected.	___	___	X	___	___	___	___	___]
[c. Steam piping properly connected.	___	___	X	X	X	___	___	___]
[d. Hot water piping pressure tested.	___	___	X	X	___	___	___	___]
[d. Steam piping pressure tested.	___	___	X	X	X	___	___	___]
e. Humidifier makeup water connected.	___	___	X	X	X	___	___	___
Controls								

Pre-commissioning Checklist - Computer Room Unit

For Computer Room Unit: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
a. Control valves operable.	___	___	X	X	___	___	___	___
b. Unit control system operable and verified.	___	___	___	X	___	___	___	___
c. Verify proper location and installation of thermostat and humidistat.	___	___	X	___	___	___	___	___
Testing, Adjusting, and Balancing (TAB)								
a. Construction filters removed and replaced.	___	___	X	___	X	___	___	___
b. TAB results within limits specified in Section 15990A	___	___	X	___	X	___	___	___
c. TAB Report submitted.	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - HVAC System Controls

For HVAC System: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. As-built shop drawings submitted.	___	___	X	X	___	___	___	___
b. Layout of control panel matches drawings.	___	___	X	X	___	___	___	___
c. Framed instructions mounted in or near control panel.	___	___	X	X	___	___	___	___
d. Components properly labeled (on inside and outside of panel).	___	___	X	X	___	___	___	___
e. Control components piped and/or wired to each labeled terminal strip.	___	___	X	X	___	___	___	___
f. EMCS connection made to each labeled terminal strip as shown.	___	___	X	X	___	___	___	___
g. Control wiring and tubing labeled at all terminations, splices, and junctions.	___	___	X	X	___	___	___	___
h. Shielded wiring used on electronic sensors.	___	___	X	X	___	___	___	___
i. Air dryer installed as specified.	___	___	X	X	___	___	___	___
j. Water drain installed as specified.	___	___	X	X	___	___	___	___
Main Power and Control Air								
a. 110 volt AC power available to panel.	___	___	___	X	___	___	___	___
b. 138 kPa gauge (20 psig) 20 psig compressed air available to panel.	___	___	X	X	___	___	___	___
Testing, Commissioning, and Balancing								
a. Testing, Commissioning, and Balancing Report submitted.	___	___	X	___	___	___	___	___

Pre-commissioning Checklist - Single Zone Air Handling Unit

For Air Handling Unit: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Vibration isolation devices installed.	__	__	X	X	X	__	__	__
b. Inspection and access doors are operable and sealed.	__	__	X	__	X	__	__	__
c. Casing undamaged.	__	__	X	X	X	__	__	__
d. Insulation undamaged.	__	__	X	X	X	__	__	__
e. Condensate drainage is unobstructed.	__	__	X	X	X	__	__	__
f. Fan belt adjusted.	__	__	X	__	X	__	__	__
g. Any damage to coil fins has been repaired.	__	__	X	__	X	__	__	__
h. Manufacturer's required maintenance clearance provided.	__	__	X	X	X	__	__	__
Electrical								
a. Power available to unit disconnect.	__	__	__	X	X	__	__	__
b. Power available to unit control panel.	__	__	__	X	__	__	__	__
c. Proper motor rotation verified.	__	__	__	__	X	__	__	__
d. Verify that power disconnect is located within sight of the unit it controls.	__	__	__	X	__	__	__	__
e. Power available to electric heating coil.	__	__	__	X	__	__	__	__
Coils								
[a. Chilled water piping properly connected.	__	__	X	__	__	__	__	__]
[a. Refrigerant piping properly connected.	__	__	X	X	X	__	__	__]
[b. Chilled water piping pressure tested.	__	__	X	X	X	__	__	__]
[b. Refrigerant piping pressure tested.	__	__	X	X	X	__	__	__]
[c. Hot water piping properly connected.	__	__	X	__	__	__	__	__]
[c. Steam and condensate piping properly connected.	__	__	X	X	X	__	__	__]
[d. Hot water piping pressure tested.	__	__	X	X	__	__	__	__]
[d. Steam and condensate piping pressure tested.	__	__	X	X	X	__	__	__]

Pre-commissioning Checklist - Single Zone Air Handling Unit

For Air Handling Unit: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
[e. Air vents installed on water coils [with shutoff valves] as specified.	___	___	X	X	X	___	___	___
f. Any damage to coil fins has been repaired.	___	___	X	___	X	___	___	___
Controls								
a. Control valves/actuators properly installed.	___	___	X	___	___	___	___	___
b. Control valves/actuators operable.	___	___	X	___	___	___	___	___
c. Dampers/actuators properly installed.	___	___	X	___	___	___	___	___
d. Dampers/actuators operable.	___	___	X	___	___	___	___	___
e. Verify proper location and installation of thermostat.	___	___	X	___	___	___	___	___
Testing, Adjusting, and Balancing (TAB)								
a. Construction filters removed and replaced.	___	___	X	___	X	___	___	___
b. TAB results within limits specified in Section 15990A	___	___	X	___	X	___	___	___
c. TAB Report submitted.	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - Energy Recovery System

For Energy Recovery System: [_____]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Recovery system piping installed.	___	___	X	___	X	___	___	___
b. Recovery system piping tested.	___	___	X	X	X	___	___	___
c. Air vent installed as specified.	___	___	X	X	X	___	___	___
d. Manufacturer's required maintenance clearance provided.	___	___	X	X	X	___	___	___
Startup								
a. Recovery system piping cleaned and filled.	___	___	X	X	X	___	___	___
b. Converter startup and checkout complete.	___	___	X	X	X	___	___	___
Controls								
a. Control valves/actuators properly installed.	___	___	X	___	___	___	___	___
b. Control valves/actuators operable.	___	___	X	___	___	___	___	___

APPENDIX B
FUNCTIONAL PERFORMANCE TESTS CHECKLISTS

Functional Performance Test Checklist - Pumps

For Pump: [_____]

Prior to performing this checklist, ensure that for closed loop systems, system is pressurized and the make-up water system is operational or, for open loop systems, that the sumps are filled to the proper level.

1. Activate pump start using control system commands (all possible combination, on/auto, etc.). ON _____ AUTO _____ OFF _____

a. Verify pressure drop across strainer:

Strainer inlet pressure _____	kPa (_____ psig)
Strainer outlet pressure _____	kPa (_____ psig)
Strainer inlet pressure _____	psig
Strainer outlet pressure _____	psig

b. Verify pump inlet/outlet pressure reading, compare to Testing, Adjusting, and Balancing (TAB) Report, pump design conditions, and pump manufacturer's performance.

	DESIGN	SYSTEM TEST	ACTUAL
Pump inlet pressure (kPa gauge)	_____	_____	_____
Pump outlet pressure (kPa gauge)	_____	_____	_____

	DESIGN	SYSTEM TEST	ACTUAL
Pump inlet pressure (psig)	_____	_____	_____
Pump outlet pressure (psig)	_____	_____	_____

c. Operate pump at shutoff and at 100 percent of designed flow when all components are in full flow. Plot test readings on pump curve and compare results against readings taken from flow measuring devices.

	SHUTOFF	100 percent
Pump inlet pressure (kPa gauge)	_____	_____
Pump outlet pressure	_____	_____
Pump flow rate (L/s)	_____	_____

	SHUTOFF	100 percent
Pump inlet pressure (psig)	_____	_____
Pump outlet pressure	_____	_____
Pump flow rate (gpm)	_____	_____

d. Operate pump at shutoff and at minimum flow or when all components are in full by-pass. Plot test readings on pump curve and compare results against readings taken from flow measuring devices.

	SHUTOFF	100 percent
Pump inlet pressure (kPa gauge)	_____	_____
Pump outlet pressure	_____	_____
Pump flow rate (L/s)	_____	_____

	SHUTOFF	100 percent
Pump inlet pressure (kPa gauge)	_____	_____
Pump outlet pressure	_____	_____
Pump flow rate (L/s)	_____	_____

Functional Performance Test Checklist - Pumps

For Pump: [_____]

Pump inlet pressure (psig)	_____	_____
Pump outlet pressure	_____	_____
Pump flow rate (gpm)	_____	_____

2. Verify motor amperage each phase and voltage phase to phase and phase to ground for both the full flow and the minimum flow conditions.

a. Full flow:

	PHASE 1	PHASE 2	PHASE 3
Amperage	_____	_____	_____
Voltage	_____	_____	_____
Voltage	_____	_____	_____
Voltage to ground	_____	_____	_____

b. Minimum flow:

	PHASE 1	PHASE 2	PHASE 3
Amperage	_____	_____	_____
Voltage	_____	_____	_____
Voltage	_____	_____	_____
Voltage to ground	_____	_____	_____

3. Unusual vibration, noise, etc.

4. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative

Contractor's Mechanical Representative

Contractor's Electrical Representative

Contractor's Testing, Adjusting and Balancing Representative

Contractor's Controls Representative

Contracting Officer's Representative

Using Agency's Representative

Functional Performance Test Checklist - Centrifugal Chiller

For Chiller: [_____]

1. Functional Performance Test: Contractor shall demonstrate operation of chilled water system as per specifications including the following: Start building air handler to provide load for chiller. Activate controls system chiller start sequence as follows:

- a. Time of day startup program initiates chiller start: _____
- b. Start condenser water pump and establish condenser water flow. Verify chiller condenser water proof-of-flow switch operation. _____
- c. Start chilled water pump and establish chilled water flow. Verify chiller chilled water proof-of-flow switch operation. _____
- d. Verify control system energizes chiller start sequence. _____
- e. Verify chiller senses chilled water temperature above set point and control system activates chiller start. _____
- f. Verify functioning of "soft start" sequence. _____
- g. Shut off air handling equipment to remove load on chilled water system. Verify chiller shutdown sequence is initiated and accomplished after load is removed. _____
- h. Restart air handling equipment one minute after chiller shut down. Verify condenser water pump, cooling tower, and chiller restart sequence. _____

2. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative

Contractor's Mechanical Representative

Contractor's Electrical Representative

Contractor's Testing, Adjusting and Balancing Representative

Contractor's Controls Representative

Contracting Officer's Representative

Using Agency's Representative

Functional Performance Test Checklist - Cooling Tower

For Cooling Tower: [_____]

1. Functional Performance Test: Contractor shall demonstrate operation of the cooling tower as per specification and the following:

a. Activate cooling tower fan start using control system command. This should first start condenser water pump, establish flow, delay fan start, as specified, to equalize flow in distribution basin and sump. Verify fan start after timed delay. _____

b. After chiller startup, control system should modulate bypass valve and two-speed fan motor to maintain condenser water set point. Verify function of bypass valve under varying loads. _____

c. Verify cooling tower interlock with chiller. _____

d. Verify makeup water float valve is functioning: _____
Activate chemical treatment feed valve, verify makeup of chemical treatment system, pump, and controls: _____

e. Entering water temperature [_____] degrees C
Leaving water temperature: [_____] degrees C
Air volume measured: [_____] L/s
Air volume calculated: [_____] L/s
Entering wet bulb temperature: [_____] degrees C
Measured water flow: [_____] L/s

e. Entering water temperature [_____] degrees F
Leaving water temperature: [_____] degrees F
Air volume measured: [_____] cfm
Air volume calculated: [_____] cfm
Entering wet bulb temperature: [_____] degrees F
Measured water flow: [_____] gpm

2. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative

Contractor's Mechanical Representative

Contractor's Electrical Representative

Contractor's Testing, Adjusting and Balancing Representative

Contractor's Controls Representative

Contracting Officer's Representative

Using Agency's Representative

Functional Performance Test Checklist - Cooling Tower

For Cooling Tower: [_____]

Functional Performance Test Checklist - VAV Terminals

The Contracting officer will select VAV terminals to be spot-checked during the functional performance test. The number of terminals shall not exceed [2] [10] [10 percent].

1. Functional Performance Test: Contractor shall demonstrate operation of selected VAV boxes as per specifications including the following:

a. Cooling only VAV boxes:

(1) Verify VAV box response to room temperature set point adjustment. Turn thermostat to 5 degrees F above ambient and measure maximum air flow. Turn thermostat to 5 degrees F below ambient and measure minimum air flow.

Maximum flow [] L/s
Minimum flow [] L/s

Maximum flow [] cfm
Minimum flow [] cfm

(2) Check damper maximum/minimum flow settings.

Maximum flow setting [] L/s
Minimum flow setting [] L/s

Maximum flow setting [] cfm
Minimum flow setting [] cfm

b. Cooling with reheat VAV boxes:

(1) Verify VAV box response to room temperature set point adjustment. Turn thermostat to 3 degrees C 5 degrees F above ambient and measure maximum air flow. Turn thermostat to 3 degrees C 5 degrees F below ambient and measure minimum air flow.

Maximum flow [] L/s
Minimum flow [] L/s

Maximum flow [] cfm
Minimum flow [] cfm

(2) Check damper maximum/minimum flow settings.

Maximum flow setting [] L/s
Minimum flow setting [] L/s

Maximum flow setting [] cfm
Minimum flow setting [] cfm

Reheat coil operation range (full open to full closed) _____

c. Fan powered VAV boxes:

(1) Verify VAV box response to sensor call for heating via set

Functional Performance Test Checklist - VAV Terminals

point adjustment. Changes to be cooling setpoint to heating set point and return to cooling set point. _____ Verify cooling damper closes to minimum position, blower fan energizes according to sequence of operation, and upon further drop in space temperature, heating coil activation and deactivation. _____

(2) Check primary air damper maximum/minimum flow settings.

Maximum flow setting [_____] L/s

Minimum flow setting [_____] L/s

(3) Check blower fan flow. [_____] L/s

Maximum flow setting [_____] cfm

Minimum flow setting [_____] cfm

(3) Check blower fan flow. [_____] cfm

(4) Verify free operation of fan backdraft damper (insure no primary air is being discharged through the recirculated air register).

(5) Verify that no recirculated air is being induced when box is in full cooling. _____

2. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative

Contractor's Mechanical Representative

Contractor's Electrical Representative

Contractor's Testing, Adjusting and Balancing Representative

Contractor's Controls Representative

Contracting Officer's Representative

Using Agency's Representative

Functional Performance Test Checklist - Variable Volume Air Handling Unit

For Air Handling Unit: [_____]

Ensure that a slight negative pressure exists on inboard side of the outside air dampers throughout the operation of the dampers. Modulate OA, RA, and EA dampers from fully open to fully closed positions.

1. Functional Performance Test: Contractor shall verify operation of air handling unit as per specification including the following:

a. The following shall be verified when the [supply fan operating] [supply and return fans operating] mode is initiated:

(1) All dampers in normal position [and fan inlet vanes modulate to maintain the required static pressure]. _____

(2) All valves in normal position. _____

(3) System safeties allow start if safety conditions are met. _____

(4) VAV fan controller shall "soft-start" fan. _____

(5) Modulate all VAV boxes to minimum air flow and verify that the static pressure does not exceed the design static pressure Class shown.

b. Occupied mode of operation - economizer de-energized.

(1) Outside air damper at minimum position. _____

(2) Return air damper open. _____

(3) Relief air damper [at minimum position] [closed]. _____

(4) Chilled water control valve modulating to maintain leaving air temperature set point. _____

(5) Fan VAV controller receiving signal from duct static pressure sensor and modulating fan to maintain supply duct static pressure set point.

c. Occupied mode of operation - economizer energized.

(1) Outside air damper modulated to maintain mixed air temperature set point. _____

(2) Relief air damper modulates with outside air damper according to sequence of operation. _____

(3) Chilled water control valve modulating to maintain leaving air temperature set point. _____

(4) Hot water control valve modulating to maintain leaving air temperature set point. _____

(5) Fan VAV controller receiving signal from duct static pressure sensor and modulating fan to maintain supply duct static pressure set point.

Functional Performance Test Checklist - Variable Volume Air Handling Unit

For Air Handling Unit: [_____]

d. Unoccupied mode of operation

(1) All dampers in normal position. _____

(2) Verify low limit space temperature is maintained as specified in sequence of operation. _____

e. The following shall be verified when the [supply fan off] [supply and return fans off] mode is initiated:

(1) All dampers in normal position. _____

(2) All valves in normal position. _____

(3) Fan de-energizes. _____

f. Verify the chilled water coil control valve operation by setting all VAV's to maximum and minimum cooling.

	Max cooling	Min cooling
Supply air volume (_____ L/s)	_____	_____

Supply air temp. (_____ degrees C)	_____	_____
------------------------------------	-------	-------

	Max cooling	Min cooling
Supply air volume _____ cfm)	_____	_____

Supply air temp. (_____ degrees F)	_____	_____
------------------------------------	-------	-------

g. Verify safety shut down initiated by smoke detectors. _____

h. Verify safety shut down initiated by low temperature protection thermostat. _____

2. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative

Contractor's Mechanical Representative

Contractor's Electrical Representative

Contractor's Testing, Adjusting and Balancing Representative

Contractor's Controls Representative

Functional Performance Test Checklist - Variable Volume Air Handling Unit

For Air Handling Unit: [_____]
Contracting Officer's Representative _____

Using Agency's Representative _____

Functional Performance Test Checklist - Single Zone Air Handling Unit

For Air Handling Unit: [_____]

1. Functional Performance Test: Contractor shall verify operation of air handling unit as per specification including the following:

a. The following shall be verified when the [supply fan operating] [supply and return fans operating] mode is initiated:

(1) All dampers in normal position. _____

(2) All valves in normal position. _____

(3) System safeties allow start if safety conditions are met. _____

b. Occupied mode of operation - economizer de-energized.

(1) Outside air damper at minimum position. _____

(2) Return air damper open. _____

(3) Relief air damper [at minimum position] [closed]. _____

(4) Chilled water control valve modulating to maintain space cooling temperature set point. _____

(5) Hot water control valve modulating to maintain space heating temperature set point input from outside air temperature controller. _____

c. Occupied mode of operation - economizer energized.

(1) Outside air damper modulated to maintain mixed air temperature set point. _____

(2) Relief air damper modulates with outside air damper according to sequence of operation. _____

(3) Chilled water control valve modulating to maintain space cooling temperature set point. _____

d. Unoccupied mode of operation

(1) All dampers in normal position. _____

(2) Verify low limit space temperature is maintained as specified in sequence of operation. _____

e. The following shall be verified when the [supply fan off] [supply and return fans off] mode is initiated:

Functional Performance Test Checklist - Single Zone Air Handling Unit

For Air Handling Unit: [_____]

(1) All dampers in normal position. _____

(2) All valves in normal position. _____

(3) Fan de-energizes. _____

f. Verify cooling coil and heating coil operation by varying thermostat set point from cooling set point to heating set point and returning to cooling set point. _____

g. Verify safety shut down initiated by smoke detectors. _____

h. Verify safety shut down initiated by low temperature protection thermostat. _____

2. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative _____

Contractor's Mechanical Representative _____

Contractor's Electrical Representative _____

Contractor's Testing, Adjusting and Balancing Representative _____

Contractor's Controls Representative _____

Contracting Officer's Representative _____

Using Agency's Representative _____

Functional Performance Test Checklist - Multizone Air Handling Unit

For Air Handling Unit: [_____]

Ensure that a slight negative pressure exists on inboard side of the outside air dampers throughout the operation of the dampers. Modulate OA, RA, and EA dampers from fully open to fully closed positions.

1. Functional Performance Test: Contractor shall verify operation of air handling unit as per specification including the following:

a. The following shall be verified when the supply and return fans operating mode is initiated:

(1) All dampers in normal position. _____

(2) All valves in normal position. _____

(3) System safeties allow start if safety conditions are met. _____

b. Occupied mode of operation - economizer de-energized.

(1) Outside air damper at minimum position. _____

(2) Return air damper open. _____

(3) Relief air damper [at minimum position] [closed]. _____

(4) Chilled water control valve modulating to maintain cold deck supply air temperature set point. _____

(5) Hot water control valve modulating to maintain hot deck supply air temperature set point input from outside air temperature controller.

c. Occupied mode of operation - economizer energized.

(1) Outside air damper modulates to maintain mixed air temperature set point. _____

(2) Relief air damper modulates with outside air damper according to sequence of operation. _____

(3) Chilled water control valve modulating to maintain cold deck supply air temperature set point. _____

(4) Hot water control valve modulating to maintain hot deck supply air temperature set point input from outside air temperature controller.

d. Unoccupied mode of operation

(1) All dampers in normal position. _____

(2) Verify low limit space temperature is maintained as specified in sequence of operation. _____

e. The following shall be verified when the supply and return fans off

Functional Performance Test Checklist - Multizone Air Handling Unit

For Air Handling Unit: [_____] mode is initiated:

- (1) All dampers in normal position. _____
- (2) All valves in normal position. _____
- (3) Fan de-energizes. _____

f. Verify zone damper operation by varying zone thermostat set points from cooling set point to heating set point and returning to cooling set point. _____

g. Verify safety shut down initiated by smoke detectors. _____

h. Verify safety shut down initiated by low temperature protection thermostat. _____

i. Index room thermostats to full cooling then to full heating. Measure and record cold deck, hot deck, and supply air temperatures and determine damper leakage for a minimum of 2 zones.

Cold deck temperature _____ degrees C (_____ degrees F)
Hot deck temperature _____ degrees C (_____ degrees F)

Cold deck temperature _____ degrees F
Hot deck temperature _____ degrees F

Zone _____
Cooling temperature _____ degrees C (_____ degrees F)
Heating temperature _____ degrees C (_____ degrees F)
Damper leakage cooling _____ degrees C (_____ degrees F)
Damper leakage heating _____ degrees C (_____ degrees F)

Zone _____
Cooling temperature _____ degrees F
Heating temperature _____ degrees F
Damper leakage cooling _____ degrees F
Damper leakage heating _____ degrees

Zone _____
Cooling temperature _____ degrees C (_____ degrees F)
Heating temperature _____ degrees C (_____ degrees F)
Damper leakage cooling _____ degrees C (_____ degrees F)
Damper leakage heating _____ degrees C (_____ degrees F)

Zone _____
Cooling temperature _____ degrees F
Heating temperature _____ degrees F
Damper leakage cooling _____ degrees F
Damper leakage heating _____ degrees F

Functional Performance Test Checklist - Multizone Air Handling Unit

For Air Handling Unit: [_____]

2. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative

Contractor's Mechanical Representative

Contractor's Electrical Representative

Contractor's Testing, Adjusting and Balancing Representative

Contractor's Controls Representative

Contracting Officer's Representative

Using Agency's Representative

Functional Performance Test Checklist - Packaged Air Cooled Chiller

For Chiller: [_____]

1. Functional Performance Test: Contractor shall demonstrate operation of chilled water system as per specifications including the following: Start building air handler to provide load for chiller. Activate controls system chiller start sequence as follows.

a. Start chilled water pump and establish chilled water flow. Verify chiller-chilled water proof-of-flow switch operation. _____

b. Verify control system energizes chiller start sequence. _____

c. Verify chiller senses chilled water temperature above set point and control system activates chiller start. _____

d. Verify functioning of "soft start" sequence. _____

e. Shut off air handling equipment to remove load on chilled water system. Verify chiller shutdown sequence is initiated and accomplished after load is removed. _____

f. Restart air handling equipment one minute after chiller shut down. Verify chiller restart sequence. _____

2. Verify chiller inlet/outlet pressure reading, compare to Testing, Adjusting, and Balancing (TAB) Report, chiller design conditions, and chiller manufacturer's performance data.

		DESIGN	SYSTEM TEST	ACTUAL
Chiller inlet pressure	(kPa gauge)	_____	_____	_____
Chiller inlet pressure	(psig)	_____	_____	_____
Chiller outlet pressure	(kPa gauge)	_____	_____	_____
Chiller outlet pressure	(psig)	_____	_____	_____

3. Verify chiller amperage each phase and voltage phase-to-phase and phase-to-ground.

	PHASE 1	PHASE 2	PHASE 3
Amperage	_____	_____	_____
Voltage	_____	_____	_____
Voltage	_____	_____	_____
Voltage to ground	_____	_____	_____

4. Record the following information:

Ambient dry bulb temperature _____ degrees C
Ambient wet bulb temperature _____ degrees C
Entering chilled water temperature _____ degrees C
Leaving chilled water temperature _____ degrees C

Ambient dry bulb temperature _____ degrees F
Ambient wet bulb temperature _____ degrees F
Entering chilled water temperature _____ degrees F
Leaving chilled water temperature _____ degrees F

Functional Performance Test Checklist - Packaged Air Cooled Chiller

For Chiller: [_____]

5. Unusual vibration, noise, etc.

6. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative

Contractor's Mechanical Representative

Contractor's Electrical Representative

Contractor's Testing, Adjusting and Balancing Representative

Contractor's Controls Representative

Contracting Officer's Representative

Using Agency's Representative

Functional Performance Test Checklist - Air Cooled Condensing Unit

For Condensing Unit: [_____]

1. Functional Performance Test: Contractor shall demonstrate operation of refrigeration system as per specifications including the following: Start building air handler to provide load for condensing unit. Activate controls system start sequence as follows.

a. Start air handling unit. Verify control system energizes condensing unit start sequence. _____

b. Shut off air handling equipment to verify condensing unit de-energizes. _____

c. Restart air handling equipment one minute after condensing unit shut down. Verify condensing unit restart sequence. _____

2. Verify condensing unit amperage each phase and voltage phase to phase and phase to ground.

	PHASE 1	PHASE 2	PHASE 3
Amperage	_____	_____	_____
Voltage	_____	_____	_____
Voltage	_____	_____	_____
Voltage to ground	_____	_____	_____

3. Record the following information:

Ambient dry bulb temperature	_____	degrees C
Ambient wet bulb temperature	_____	degrees C
Suction pressure	_____	kPa gauge
Discharge pressure	_____	kPa gauge

Ambient dry bulb temperature	_____	degrees F
Ambient wet bulb temperature	_____	degrees F
Suction pressure	_____	psig
Discharge pressure	_____	psig

4. Unusual vibration, noise, etc.

5. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative

Contractor's Mechanical Representative

Contractor's Electrical Representative Representative

Contractor's Testing, Adjusting and Balancing

Functional Performance Test Checklist - Air Cooled Condensing Unit

For Condensing Unit: [_____]

Contractor's Controls Representative

Contracting Officer's Representative

Using Agency's Representative

Functional Performance Test Checklist - Hot Water Boiler

For Boiler: [_____]

1. Functional Performance Test: Contractor shall demonstrate operation of hot water system as per specifications including the following: Start building heating equipment to provide load for boiler. Activate controls system boiler start sequence as follows.

a. Start hot water pump and establish hot water flow. Verify boiler hot water proof-of-flow switch operation. _____

b. Verify control system energizes boiler start sequence. _____

c. Verify boiler senses hot water temperature below set point and control system activates boiler start. _____

d. Shut off building heating equipment to remove load on hot water system. Verify boiler shutdown sequence is initiated and accomplished after load is removed. _____

2. Verify boiler inlet/outlet pressure reading, compare to Test and Balance (TAB) Report, boiler design conditions, and boiler manufacturer's performance data.

	DESIGN	SYSTEM TEST	ACTUAL
Boiler inlet pressure (kPa gauge)	_____	_____	_____
Boiler outlet pressure (kPa gauge)	_____	_____	_____
Boiler flow rate (L/s)	_____	_____	_____
Flue-gas temperature at boiler outlet		_____	_____
Percent carbon dioxide in flue-gas		_____	_____
Draft at boiler flue-gas exit		_____	_____
Draft or pressure in furnace		_____	_____
Stack emission pollutants concentration	_____	_____	_____
Fuel type	_____	_____	_____
Combustion efficiency	_____	_____	_____

	DESIGN	SYSTEM TEST	ACTUAL
Boiler inlet pressure (psig)	_____	_____	_____
Boiler outlet pressure (psig)	_____	_____	_____
Boiler flow rate (gpm)	_____	_____	_____
Flue-gas temperature at boiler outlet		_____	_____
Percent carbon dioxide in flue-gas		_____	_____
Draft at boiler flue-gas exit		_____	_____
Draft or pressure in furnace		_____	_____
Stack emission pollutants concentration	_____	_____	_____
Fuel type	_____	_____	_____
Combustion efficiency	_____	_____	_____

3. Record the following information:

Ambient temperature	_____	degrees C
Entering hot water temperature	_____	degrees C
Leaving hot water temperature	_____	degrees C

Functional Performance Test Checklist - Hot Water Boiler

For Boiler: [_____]

Ambient temperature	_____	degrees F
Entering hot water temperature	_____	degrees F
Leaving hot water temperature	_____	degrees F

4. Verify temperatures in item 3 are in accordance with the reset schedule. _____

5. Verify proper operation of boiler safeties. _____

6. Unusual vibration, noise, etc. _____

7. Visually check refractory for cracks or spalling and refractory and tubes for flame impingement. _____

8. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative _____

Contractor's Mechanical Representative _____

Contractor's Electrical Representative _____

Contractor's Testing, Adjusting and Balancing Representative _____

Contractor's Controls Representative _____

Contracting Officer's Representative _____

Using Agency's Representative _____

Functional Performance Test Checklist - Steam Boiler

For Boiler: [_____]

1. Functional Performance Test: Contractor shall demonstrate operation of steam heating system as per specifications including the following: Start building heating equipment to provide load for boiler. Activate controls system boiler start sequence as follows.

a. Start steam heating system. Verify control system energizes boiler start sequence. _____

b. Verify boiler senses steam pressure below set point and control system activates boiler start. _____

c. Shut off building heating equipment to remove load on steam heating system. Verify boiler shutdown sequence is initiated and accomplished after load is removed. _____

d. Verify that water level and makeup water system are operational. _____

2. Verify boiler inlet/outlet pressure reading, compare to boiler design conditions and manufacturer's performance data.

	DESIGN	SYSTEM TEST	ACTUAL
Boiler inlet water temp (degrees F)	_____	_____	_____
Boiler outlet pressure (kPa gauge)	_____	_____	_____
Flue-gas temperature at boiler outlet (degrees C)	_____	_____	_____
Percent carbon dioxide in flue-gas	_____	_____	_____
Draft at boiler flue-gas exit	_____	_____	_____
Draft or pressure in furnace	_____	_____	_____
Stack emission pollutants concentration	_____	_____	_____
Fuel type	_____	_____	_____
Combustion efficiency	_____	_____	_____

	DESIGN	SYSTEM TEST	ACTUAL
Boiler inlet water temp (degrees F)	_____	_____	_____
Boiler outlet pressure (psig)	_____	_____	_____
Flue-gas temperature at boiler outlet (degrees F)	_____	_____	_____
Percent carbon dioxide in flue-gas	_____	_____	_____
Draft at boiler flue-gas exit	_____	_____	_____
Draft or pressure in furnace	_____	_____	_____
Stack emission pollutants concentration	_____	_____	_____
Fuel type	_____	_____	_____
Combustion efficiency	_____	_____	_____

3. Record the following information:

Ambient temperature _____ degrees C
Ambient temperature _____ degrees F

4. Verify proper operation of boiler safeties. _____

5. Unusual vibration, noise, etc.

Functional Performance Test Checklist - Steam Boiler

For Boiler: [_____]

6. Visually check refractory for cracks or spalling and refractory and tubes for flame impingement. _____

7. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative

Contractor's Mechanical Representative

Contractor's Electrical Representative

Contractor's Testing, Adjusting and Balancing Representative

Contractor's Controls Representative

Contracting Officer's Representative

Using Agency's Representative

Functional Performance Test Checklist - Fan Coil Units

The Contracting Officer will select fan coil units to be spot-checked during the functional performance test. The number of terminals shall not exceed [2] [10] [10 percent].

1. Functional Performance Test: Contractor shall demonstrate operation of selected fan coils as per specifications including the following:

a. Cooling only fan coils:

- (1) Verify fan coil unit response to room temperature set point adjustment. Changes to be cooling set point to cooling set point minus 10 degrees and return to cooling set point. _____
- (2) Check blower fan air flow. _____ L/s
Check blower fan air flow. _____ cfm
- (3) Check cooling coil water flow. _____ L/s
Check cooling coil water flow. _____ gpm
- (4) Verify proper operation of cooling water control valve. _____

b. Cooling/heating fan coils:

- (1) Verify fan coil unit response to room temperature set point adjustment. Changes to be cooling set point to heating set point and return to cooling set point. _____
- (2) Check blower fan air flow. _____ L/s
Check blower fan air flow. _____ cfm
- (3) Check cooling coil water flow. _____ L/s
Check cooling coil water flow. _____ cfm
- (4) Verify proper operation of cooling water control valve. _____
- (5) Check cooling mode inlet air temperature. _____ degrees C
Check cooling mode inlet air temperature. _____ degrees F
- (6) Check cooling mode outlet air temperature. _____ degrees C
Check cooling mode outlet air temperature. _____ degrees F
- (7) Check heating coil water flow. _____ L/s
Check heating coil water flow. _____ gpm
- (8) Verify proper operation of heating water control valve. _____
- (9) Check heating mode inlet air temperature. _____ degrees C
Check heating mode inlet air temperature. _____ degrees F
- (10) Check heating mode outlet air temperature. _____ degrees C
Check heating mode outlet air temperature. _____ degrees F

2. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Functional Performance Test Checklist - Fan Coil Units

Signature and Date

Contractor's Chief Quality Control Representative

Contractor's Mechanical Representative

Contractor's Electrical Representative

Contractor's Testing, Adjusting and Balancing Representative

Contractor's Controls Representative

Contracting Officer's Representative

Using Agency's Representative

Functional Performance Test Checklist - Unit Heaters

The Contracting Officer will select unit heaters to be spot-checked during the functional performance test. The number of terminals shall not exceed [2] [10] [10 percent].

1. Functional Performance Test: Contractor shall demonstrate operation of selected unit heaters as per specifications including the following:

a. Verify unit heater response to room temperature set point adjustment. Changes to be heating set point to heating set point minus 10 degrees and return to heating set point. _____

b. Check blower fan speed. _____rpm

c. Check heating mode inlet air temperature. _____ degrees C Check heating mode inlet air temperature. _____ degrees F

d. Check heating mode outlet air temperature. _____ degrees C Check heating mode outlet air temperature. _____ degrees F

2. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative

Contractor's Mechanical Representative

Contractor's Electrical Representative

Contractor's Testing, Adjusting and Balancing Representative

Contractor's Controls Representative

Contracting Officer's Representative

Using Agency's Representative

Functional Performance Test Checklist - Steam/Hot Water Converter

For Converter: [_____]

1. Functional Performance Test: Contractor shall demonstrate operation of heating system as per specifications including the following: Start building heating equipment to provide load for converter.

- a. Verify control system energizes. _____
- b. Verify converter senses hot water temperature below set point and control system modulates steam valve. _____
- c. Shut off building heating equipment to remove load on heating system. Verify converter steam valve closes after load is removed. _____

2. Verify converter inlet/outlet pressure reading, compare to converter design conditions and manufacturer's performance data.

	DESIGN	ACTUAL
Converter inlet water temp (degrees C)	_____	_____
Converter outlet water temp (degrees F)	_____	_____
Converter inlet steam pressure (psig)	_____	_____
Determine water flow rate based on pressure drop through converter	_____	_____
Determine water flow rate with flow measuring device	_____	_____
Verify that temperature of water is in accordance with outdoor air reset schedule	_____	_____

	DESIGN	ACTUAL
Converter inlet water temp (degrees F)	_____	_____
Converter outlet water temp (degrees F)	_____	_____
Converter inlet steam pressure (psig)	_____	_____
Determine water flow rate based on pressure drop through converter	_____	_____
Determine water flow rate with flow measuring device	_____	_____
Verify that temperature of water is in accordance with outdoor air reset schedule	_____	_____

- 3. Verify proper operation of converter safeties. _____
- 4. Check and report unusual vibration, noise, etc. _____

5. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Contractor's Chief Quality Control Representative _____ Signature and Date _____

Functional Performance Test Checklist - Steam/Hot Water Converter

For Converter: [_____]

Contractor's Mechanical Representative _____

Contractor's Electrical Representative _____

Contractor's Testing, Adjusting and Balancing Representative _____

Contractor's Controls Representative _____

Contracting Officer's Representative _____

Using Agency's Representative _____

Functional Performance Test Checklist - Computer Room Unit

For Computer Room Unit: [_____]

1. Functional Performance Test: Contractor shall verify operation of computer room unit as per specification including the following:

- a. System safeties allow start if safety conditions are met. _____
- b. Verify cooling and heating operation by varying thermostat set point from space set point to space set point plus 10 degrees, space set point minus 10 degrees, and returning to space set point. _____
- c. Verify humidifier operation by varying humidistat set point from space set point to space set point plus 20 percent RH, and returning to space set point. _____
- d. Verify that airflow is within +10/-0 percent of design airflow. _____
- e. Verify unit shut down during fire event initiated by smoke/heat sensors. _____

2. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative _____

Contractor's Mechanical Representative _____

Contractor's Electrical Representative _____

Contractor's Testing, Adjusting and Balancing Representative _____

Contractor's Controls Representative _____

Contracting Officer's Representative _____

Using Agency's Representative _____

Functional Performance Test Checklist - HVAC Controls

For HVAC System: [_____]

The Contracting Officer will select HVAC control systems to undergo functional performance testing. The number of systems shall not exceed [2] [10] [10 percent].

1. Functional Performance Test: Contractor shall verify operation of HVAC controls by performing the following tests:

a. Verify that controller is maintaining the set point by manually measuring the controlled variable with a thermometer, sling psychrometer, inclined manometer, etc.

b. Verify sensor/controller combination by manually measuring the controlled medium. Take readings from control panel display and compare readings taken manually. Record all readings.

Sensor _____
Manual measurement _____
Panel reading value _____

c. Verify system stability by changing the controller set point as follows:

- (1) Air temperature - 10 degrees F
- (2) Water temperature - 10 degrees F
- (3) Static pressure - 10 percent of set point
- (4) Relative humidity - percent (RH)

The control system shall be observed for 10 minutes after the change in set point. Instability or excessive hunting will be unacceptable.

d. Verify interlock with other HVAC controls.

e. Verify interlock with fire alarm control panel.

f. Verify interlock with EMCS.

[g. Change controller set point 10 percent with EMCS and verify correct response.]

2. Verify that operation of control system conforms to that specified in the sequence of operation.

3. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative _____

Contractor's Mechanical Representative _____

Functional Performance Test Checklist - HVAC Controls

For HVAC System: [_____]

Contractor's Electrical Representative _____

Contractor's Testing, Adjusting and Balancing Representative

Contractor's Controls Representative

Contractor's Officer's Representative

Using Agency's Representative

Functional Performance Test Checklist - Energy Recovery System

For Energy Recovery System: [_____]

1. Functional Performance Test: Contractor shall demonstrate operation of energy recovery system as per specifications including the following: Start equipment to provide energy source for recovery system.

- a. Verify energy source is providing recoverable energy. _____
- b. Verify recovery system senses available energy and activates. _____
- c. Verify that recovery system deactivates when recoverable energy is no longer available. _____

2. Verify recovery system inlet/outlet readings, compare to design conditions and manufacturer's performance data.

	Design	Actual
Primary loop inlet temp (degrees C)	_____	_____
Primary loop outlet temp (degrees F)	_____	_____
Primary loop flow rate	_____	_____
Secondary loop inlet temp (degrees)	_____	_____
Secondary loop outlet temp (degrees C)	_____	_____
Energy recovered (kJ)	_____	_____

	Design	Actual
Primary loop inlet temp (degrees F)	_____	_____
Primary loop outlet temp (degrees F)	_____	_____
Primary loop flow rate	_____	_____
Secondary loop inlet temp (degrees F)	_____	_____
Secondary loop outlet temp (degrees F)	_____	_____
Energy recovered BTU's)	_____	_____

3. Check and report unusual vibration, noise, etc.

4. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative _____

Contractor's Mechanical Representative _____

Contractor's Electrical Representative _____

Contractor's Testing , Adjusting and Balancing Representative _____

Contractor's Controls Representative _____

Functional Performance Test Checklist - Energy Recovery System

For Energy Recovery System: [_____]

Contractor's Officer's Representative

Using Agency's Representative

-- End of Section --