
USACE / NAVFAC / AFCEC / NASA UFGS-23 22 23.00 40 (February 2011)
Change 2 - 11/12

Preparing Activity: NASA Superseding
UFGS-23 22 23 (August 2008)

UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UMRL dated April 2015

SECTION TABLE OF CONTENTS

DIVISION 23 - HEATING, VENTILATING, AND AIR CONDITIONING

SECTION 23 22 23.00 40

STEAM CONDENSATE PUMPS

02/11

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 GENERAL REQUIREMENTS
- 1.4 QUALITY ASSURANCE
 - 1.4.1 Factory Tests
 - 1.4.2 Product Installation

PART 2 PRODUCTS

- 2.1 CONDENSATE RETURN PUMP UNITS
 - 2.1.1 Pumps
 - 2.1.2 Motor Requirements
 - 2.1.3 Receiver
 - 2.1.4 Controls
- 2.2 CONDENSATE RECEIVER
 - 2.2.1 Materials and Construction
 - 2.2.2 Accessories
- 2.3 RECIPROCATING STEAM PUMPS (RSP)
 - 2.3.1 Construction
 - 2.3.2 Tools and Accessories
 - 2.3.3 Steam-Cylinder Drainage

PART 3 EXECUTION

- 3.1 INSTALLATION
- 3.2 TESTING
 - 3.2.1 Vibration Analyzer
 - 3.2.2 Acceptance Testing

-- End of Section Table of Contents --

the text by basic designation only and listed in this paragraph by organization, designation, date, and title.

Use the Reference Wizard's Check Reference feature when you add a RID outside of the Section's Reference Article to automatically place the reference in the Reference Article. Also use the Reference Wizard's Check Reference feature to update the issue dates.

References not used in the text will automatically be deleted from this section of the project specification when you choose to reconcile references in the publish print process.

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASME INTERNATIONAL (ASME)

ASME BPVC SEC VIII D1 (2010) BPVC Section VIII-Rules for Construction of Pressure Vessels Division 1

HYDRAULIC INSTITUTE (HI)

HI M100 (2009) HI Pump Standards Set

INTERNATIONAL ORGANIZATION FOR STANDARDIZATION (ISO)

ISO 1940-1 (2003; Cor 2005) Mechanical Vibration - Balance Quality Requirements for Rotors in a Constant (Rigid) State - Part 1: Specification and Verification of Balance

ISO 2858 (1975) End Suction Centrifugal Pump (Rating 16 Bar) Designation Nominal Duty Point and Dimensions - International Restrictions

ISO 5199 (2002) Technical Specifications for Centrifugal Pumps, Class II

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA MG 1 (2014) Motors and Generators

1.2 SUBMITTALS

NOTE: Review Submittal Description (SD) definitions in Section 01 33 00 SUBMITTAL PROCEDURES and edit the following list to reflect only the submittals required for the project.

The Guide Specification technical editors have designated those items that require Government

approval, due to their complexity or criticality, with a "G." Generally, other submittal items can be reviewed by the Contractor's Quality Control System. Only add a "G" to an item, if the submittal is sufficiently important or complex in context of the project.

For submittals requiring Government approval on Army projects, a code of up to three characters within the submittal tags may be used following the "G" designation to indicate the approving authority. Codes for Army projects using the Resident Management System (RMS) are: "AE" for Architect-Engineer; "DO" for District Office (Engineering Division or other organization in the District Office); "AO" for Area Office; "RO" for Resident Office; and "PO" for Project Office. Codes following the "G" typically are not used for Navy, Air Force, and NASA projects.

An "S" following a submittal item indicates that the submittal is required for the Sustainability Notebook to fulfill federally mandated sustainable requirements in accordance with Section 01 33 29 SUSTAINABILITY REPORTING.

Choose the first bracketed item for Navy, Air Force and NASA projects, or choose the second bracketed item for Army projects.

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are [for Contractor Quality Control approval.][for information only. When used, a designation following the "G" designation identifies the office that review the submittal for the Government.] Submittals with an "S" are for inclusion in the Sustainability Notebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Connection Diagrams[; G[, [____]]]

Control Diagrams[; G[, [____]]]

Fabrication Drawings[; G[, [____]]]

Installation Drawings[; G[, [____]]]

SD-03 Product Data

Condensate Pumps[; G[, [____]]]

SD-06 Test Reports

Pump Flow Capacity Tests[; G[, [____]]]

Efficiency Tests[; G[, [____]]]

Vibration Tests[; G[, [____]]]

Final Test Reports[; G[, [____]]]

SD-07 Certificates

Condensate Return Pump Units[; G[, [____]]]

Condensate Receiver[; G[, [____]]]

Reciprocating Steam Pumps[; G[, [____]]]

1.3 GENERAL REQUIREMENTS

NOTE: If Section 23 00 00 AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEMS is not included in the project specification, applicable requirements therefrom should be inserted and the following paragraph deleted. If Section 23 05 48.00 40 VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT is not included in the project specification, applicable requirements therefrom should be inserted and the second paragraph deleted. If Section 26 60 13.00 40 LOW-VOLTAGE MOTORS is not included in the project specification, applicable requirements therefrom should be inserted and the third paragraph deleted.

[Section 23 00 00 AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEMS applies to work specified in this section.

][Section 23 05 48.00 40 VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT applies to work specified in this section.

][Section 26 60 13.00 40 LOW-VOLTAGE MOTORS applies to this section.

] Submit connection diagrams for condensate pumps showing details of cable and motor connections.

Submit control diagrams for condensate pumps showing motor starters, relays, or any other component necessary for safe operation.

Submit fabrication drawings for condensate pumps indicating size, type, and efficiency rating.

Submit installation drawings for condensate pumps in accordance with the manufacturer's recommended instructions.

Submit manufacturer's catalog data for condensate pumps showing equipment foundation data and equipment and performance data including performance curves and indicating brake power, head (liter per minute) (gpm), and NPSH.

1.4 QUALITY ASSURANCE

1.4.1 Factory Tests

Ensure the manufacturer tests the pump. Submit prior to shipment of the finished pump the following test data:

Pump flow capacity tests - Conform pump flow to requirements listed in accordance with paragraph CONDENSATE-RETURN PUMP UNITS.

Efficiency tests - Conform pump efficiency to the approved design documents.

Vibration tests - Conform vibration tests to requirements listed in accordance with paragraph TESTING.

1.4.2 Product Installation

Submit a listing of product installations for the following items:

- a. Condensate Return Pump Units
- b. Condensate Receiver
- c. Reciprocating Steam Pumps

Include identification of five installed units similar to those proposed for use, that have been in successful service for a minimum period of five years. Include within list, purchaser, address of installation, service organization, and date of installation.

PART 2 PRODUCTS

2.1 CONDENSATE RETURN PUMP UNITS

NOTE: Revise part title as necessary to include pump number series.

Drawing schedules should indicate data selected from the following to completely define the grimp (grp) low-pressure systems:

Nominal Equivalent Direct Radiation Square Metre	Pump Capacity Litre Per Minute	Approximate Gallons Stored Between Start/Stop	Storage Capacity Litre
93	5.7	3.79	38
186	11.4	5.68	38
372	22.7	17.03	53
557	34.1	17.03	53
744	45.4	24.61	61

930	56.8	28.39	95
1394	85.2	42.59	114
1858	113.6	56.78	133
2322	41.9	70.98	151
2787	170.3	85.17	170
3716	227.1	113.56	189
4645	283.9	141.95	227
6968	425.8	212.93	303
9300	567.8	283.91	568

Nominal
Equivalent
Direct
Radiation
Square
Feet

Pump
Capacity
GPM

Approximate
Gallons
Stored Between
Start/Stop

Storage
Capacity
Gal

1,000	1.5	1.0	10
2,000	3.0	1.5	10
4,000	6.0	4.5	14
6,000	9.0	4.5	14
8,000	12.0	6.5	16
10,000	15.0	7.5	25
15,000	22.5	11.25	30
20,000	30.0	15.0	35
25,000	37.5	18.75	40
30,000	45.0	22.5	45
40,000	60.0	30.0	50
50,000	75.0	37.5	60
75,000	112.5	56.25	80
100,000	150.0	75.0	150

Units should be selected to handle a minimum of three times the normal condensate from the system. Normal condensate means, for the purposes of this specification, 6 kilogram per square meter per hour 1/4 pound per hour per square foot equivalent direct

radiation (edr) or 2 liter per minute per 100 square meter 0.5 Gallon per minute per 1,000 square feet edr except when small boilers are involved. Discharge pressures and pump revolutions per minute should be indicated.

Receiver capacity should be indicated as nominal.

NOTE: Conform Pump and Motor balance to ISO Std. 1940/1 - (1986) Balance Quality Requirements of Rigid Rotors - Determination of Permissible Residual Unbalance unless otherwise noted. Conform motor vibration levels to NEMA Specification MG-1, Motors and Generators, Part 7 unless otherwise noted.

Factory assemble condensate-return pump units and include condensate receivers, motor-driven pump(s), manual and automatic liquid-level controls, and other accessories as specified herein or which may be necessary for complete and satisfactorily operating units(s).

Ensure pump(s) and all accessories mounted on the receiver and unit(s) are complete with all intercomponent piping and wiring. Ensure receiver and unit(s) are complete with all intercomponent piping and wiring. Provide receiver with integral cast lugs for securing to mounting surface. Ensure pump suction piping contains a shutoff valve for pump servicing.

NOTE: When more than one unit is involved, rewrite to include unit identification or indicate on the drawing schedule.

Provide [simplex] [duplex] condensate-return pump units.

Factory test condensate-return pump unit for capacity and pressure.

2.1.1 Pumps

Pumps are close coupled or flexible coupled with guard centrifugal volute vertically or horizontally mounted on or next to receiver. Ensure pumps conform to applicable requirements of ISO 2858 and ISO 5199 HI M100 standards and are bronze mounted. Casing is close-grained cast iron with renewable wearing ring. Provide tapped openings for automatic venting, draining, and pressure-gage connection. Pump shaft meets AISI Type 300 series corrosion-resistant steel. Pump seal is manufacturer's standard for continuous service at 121 degrees C 250 degrees F, minimum, at seal rotating and stationary members interface and 98 degrees C 209-degree F pumped fluid. Compensate impeller for hydraulic thrust, balance rotating assembly, and ensure strength of shafting such that when pump is operating at its worst hydraulic condition, vibration readings conform to ISO 1940-1,[G6.3] [G2.5] [G1.0][_____]. Select pumps capable of handling 98 degrees C 209-degree F condensate without cavitation or vapor binding while delivering specified capacity.

2.1.2 Motor Requirements

Motors are vertical or horizontal and conform to NEMA MG 1, requirements specified under the electrical sections of the specifications and to the following additional requirements.

Motor insulation is Class H or manufacturer's standard and be suitable for satisfactory operation under the following conditions:

NOTE: Rewrite following temperatures to suit project.

- a. Still air at 65 percent relative humidity, with service-location temperatures to 50 degrees C 122 degrees F
- b. Thermal conduction along motor shaft immersed in 98 degrees C 209-degree F water
- c. Proximity of motor to receiver surfaces at 98 degrees C 209 degrees F

Ensure lubricants are specifically suitable for high-temperature service.

2.1.3 Receiver

Condensate receiver is a single tank constructed of close-grained cast iron with a minimum receiver wall thickness of 8 millimeter 5/16 inch or steel with a rust-resistant interior coating.

Fit each receiver with:

- a. Redline borosilicate gage glass and nonferrous shutoff valve assembly for use in case of glass breakage.
- b. External inlet strainer with removable basket for pump protection.
- c. Thermometer with separable well conforming to requirements specified elsewhere in this section.
- d. Receiver top-vent connection and drain at lowest point. Assemble drain closures with tetrafluoroethylene tape.

2.1.4 Controls

Simplex-unit control consists of a float-operated switch UL rated for the load imposed and wired to the motor. Float and float arm are AISI Type 304 or 316 corrosion-resistant steel. Copper float mechanisms are not acceptable.

Duplex-unit control consists of a float-operated automatic mechanical alternator controlling at two levels with double-pole alternating switches and operated by a single float. Control automatically alternates operation of two pumps to deliver total capacity of two pumps under peak-load conditions, and automatically operate a second pump should on-line pump fail. Use UL rated switches for the load imposed and be wired to motors. Float and float arm are AISI Type 304 or 316 corrosion-resistant steel. Copper float mechanisms are not acceptable.

Duplex unit control consists of an automatic electric sequence controller used in conjunction with two motor controllers, two selector switches, and two float switches, complete with intercomponent wiring, installed in a NEMA Type 1 enclosure mounted on the receiver. Provide selector switches with automatic OFF positions. Provide a momentary-contact test pushbutton. One float switch controls the alternator to provide automatic alternation of the two pumps. Second float switch provides simultaneous operation of two pumps to deliver total capacity of two pumps under peak-load conditions and automatically operate second pump should on-line pump fail. Use UL rated switches for the load imposed. Floats and float arms are AISI Type 304 or 316 corrosion-resistant steel. Copper float mechanisms are not acceptable.

2.2 CONDENSATE RECEIVER

NOTE: Select for built-up units where crp series capacities are inadequate.

Built-up units may utilize reciprocating steam pumps or centrifugal pumps with respective pumping-equipment specifications supplemented to suit project requirements.

If an ASME vessel is required, choose the first paragraph; if a manufacturer's standard vessel is sufficient, choose the second paragraph.

Design and construct receiver in accordance with ASME BPVC SEC VIII D1 for operation under atmospheric conditions but certified as hydrostatically tested at 690 kilopascal 100 pounds per square inch, gage.

Receiver is manufacturer's standard vessel.

2.2.1 Materials and Construction

Construct receiver of either cast iron or galvanized steel [and be a standard item of the manufacturer] with dished heads, indicated openings including those for vent, inlets, discharge, drain, gage-glass connections, and level-control devices. Minimum tank opening is 25 millimeter 1-inch iron pipe size. Couplings are forged carbon steel. Use Schedule 80 pipe for nozzle piping. Ensure piping, flanges, and fittings conform to specifications for connecting condensate piping system.

Mount receiver as indicated.

Provide one 280 by 380 millimeter 11- by 15-inch gasketed manhole at a point in the head or shell for access when receiver is in place.

Sandblast receiver internal surfaces, including nozzles, to white metal, to a profile required by the coating manufacturer. Coat internal surfaces with a multiple-coat baked or air-dry phenolic system to produce, in not less than three coats, a dry-film thickness of not less than 0.175 millimeter 7 mils. Ensure coating is certified as suitable for continuous service when immersed in condensate at a temperature not less than 149 degrees C 300 degrees F.

2.2.2 Accessories

**NOTE: Supplement following text with specifications
for control devices to suit pumps selected.**

Provide receiver with a shutoff-valve-equipped gage-glass assembly to indicate liquid level over not less than 80 percent of receiver diameter from the bottom. Use red-lined borosilicate gage glass and fitted with wire or sheet-metal guards.

2.3 RECIPROCATING STEAM PUMPS (RSP)

**NOTE: Select for remote-location condensate pumping
applications, where no electrical power is
available. Coordinate with specification of
condensate receiver. Weighted or pilot
float-operated steam control valve, piped-cylinder
end drains, and traps for continuous condensate
removal, steam pressure-reducing or speed-governor
valve as necessary, and discharge line-relief valves.**

Show size or capacity on drawings.

Pump is horizontal duplex double-acting reciprocating type.

Ensure pump speed, capacity, materials construction, and installation conforms to applicable requirements of ISO 2858 and ISO 5199 HI M100 Standards, as modified and supplemented herein.

Ensure steam end is rated at not less than 1725 kilopascal 250 pounds per square inch (psi) working steam pressure.

Ensure liquid end is rated at not less than 860 kilopascal at 100 degrees C 125 psi at 212 degrees F.

2.3.1 Construction

Pump construction is fully bronze-fitted, except that piston rods are AISI Type 304 corrosion-resistant steel with alumina-ceramic coating in the packing box area where optionally available.

Ensure steam-end cylinders have sufficient thickness to permit up to 4 millimeter 1/8-inch reborings.

Insulate steam end cylinders and lag with sheet-metal.

Liquid end is valve-plate type.

Fit liquid-end cylinder with a replaceable bronze liner.

Cylinder openings are manufacturer's standard, flanged whenever optionally available.

2.3.2 Tools and Accessories

Provide one set of special tools.

Provide one set of nonmetallic rings and packing for steam- and liquid-end cylinders and one set of steam-end cylinder rings.

Provide pump-actuated mechanical lubricator with sufficient lubricant feed points and lubricant storage capacity to permit once-per-week lubrication.

2.3.3 Steam-Cylinder Drainage

Provide all cylinder end drains with check valves and Type TOD steam traps.

PART 3 EXECUTION

3.1 INSTALLATION

Install equipment in accordance with manufacturer's recommendations.

Based on the motor nominal operating speed, align the Pump and driver to the following specifications:

Speed(RPM)	angle(mils)	offset(mils/inch)
600	6.0	2.0
900	5.0	1.5
1200	4.0	1.0
1800	3.0	0.5
3600	1.5	0.4
7200	1.0	.03

3.2 TESTING

3.2.1 Vibration Analyzer

Use an FFT analyzer to measure vibration levels with the following characteristics: A dynamic range greater than 70 dB; a minimum of 400 line resolution; a frequency response range of 5 Hz-10 KHz(300-600000 cpm); the capacity to perform ensemble averaging, the capability to use a Hanning window; auto-ranging frequency amplitude; a minimum amplitude accuracy over the selected frequency range of plus or minus 20 percent or plus or minus 1.5 dB.

Use an accelerometer, either stud-mounted or mounted using a rare earth, low mass magnet and sound disk(or finished surface) with the FFT analyzer to collect data. Ensure the mass of the accelerometer and its mounting have minimal influence on the frequency response of the system over the selected measurement range.

3.2.2 Acceptance Testing

Prior to pump final acceptance, use vibration analysis to demonstrate that pump and motor are aligned as specified, and ensure misalignment does not impart more than .04 inches per second vibration level at 2 times run speed.

Use vibration analysis to also verify pump conformance to specifications. Ensure vibration levels are not more than .075 in/sec at 1 times run speed and at pump frequency, and .04 in/sec at other multiples of run speed.

Demonstration that the pump is non-overloading at any operating point and that the flow capacity is as specified.

Provide final test reports to the Contracting Officer. Provide reports with a cover letter/sheet clearly marked with the System name, Date, and the words "Final Test Reports - Forward to the Systems Engineer/Condition Monitoring Office/Predictive Testing Group for inclusion in the Maintenance Database."

-- End of Section --