
USACE / NAVFAC / AFCEA / NASA UFGS-01 75 00.00 40 (April 2006)

Preparing Activity: NASA Superseding
 NASA-01750S (December 2005)

UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UMRL dated 18 July 2006

Revised throughout - changes not indicated by CHG tags

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 75 00.00 40

STARTING AND ADJUSTING

04/06

PART 1 GENERAL

- 1.1 SUMMARY
- 1.2 REFERENCES
- 1.3 SUBMITTALS
 - 1.3.1 Tests Required
 - 1.3.2 Factory Tests
 - 1.3.3 Functional Test
 - 1.3.4 Final Acceptance Test
 - 1.3.5 Test Procedures

PART 2 PRODUCTS

PART 3 EXECUTION

-- End of Section Table of Contents --

USACE / NAVFAC / AFCEA / NASA UFGS-01 75 00.00 40 (April 2006)

Preparing Activity: NASA Superseding
 NASA-01750S (December 2005)

UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UMRL dated 18 July 2006

Revised throughout - changes not indicated by CHG tags

SECTION 01 75 00.00 40

STARTING AND ADJUSTING
04/06

NOTE: Delete, revise, or add to the text in this section to cover project requirements. Notes are for designer information and will not appear in the final project specification.

This broadscope section establishes requirements for system testing and acceptance. This section must be coordinated with the project requirements and technical sections.

Comments and suggestions on this guide specification are welcome and should be directed to the technical proponent of the specification. A listing of technical proponents, including their organization designation and telephone number, is on the Internet.

Recommended changes to a UFGS should be submitted as a Criteria Change Request (CCR).

Use of electronic communication is encouraged.

Brackets are used in the text to indicate designer choices or locations where text must be supplied by the designer.

PART 1 GENERAL

1.1 SUMMARY

Requirements of this Section apply to, and are a component part of, each section of the specifications.

1.2 REFERENCES

Not Used

1.3 SUBMITTALS

NOTE: Review Submittal Description (SD) definitions in Section 01 33 00 SUBMITTAL PROCEDURES and edit the following list to reflect only the submittals required for the project. Submittals should be kept to the minimum required for adequate quality control.

A "G" following a submittal item indicates that the submittal requires Government approval. Some submittals are already marked with a "G". Only delete an existing "G" if the submittal item is not complex and can be reviewed through the Contractor's Quality Control system. Only add a "G" if the submittal is sufficiently important or complex in context of the project.

For submittals requiring Government approval on Army projects, a code of up to three characters within the submittal tags may be used following the "G" designation to indicate the approving authority. Codes for Army projects using the Resident Management System (RMS) are: "AE" for Architect-Engineer; "DO" for District Office (Engineering Division or other organization in the District Office); "AO" for Area Office; "RO" for Resident Office; and "PO" for Project Office. Codes following the "G" typically are not used for Navy, Air Force, and NASA projects.

Choose the first bracketed item for Navy, Air Force and NASA projects, or choose the second bracketed item for Army projects.

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are [for Contractor Quality Control approval.] [for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government.] Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-06 Test Reports

Test reports shall be submitted in accordance with the paragraphs entitled, "Factory Tests", "Functional Test" and "Final Acceptance Test," of this section.

Test procedures and the recording forms shall be submitted according to paragraph entitled, "Test Procedures."

1.3.1 Tests Required

Tests shall be performed to verify proper functioning of fire protection, fire suppression, HVAC, compressed air, electrical switchgear, protective relaying, fluid and gas systems, pump/motor combinations, boiler systems, hydraulic and pneumatic control, condition/performance monitoring systems, energy control and monitoring systems, and other assemblies and components

that need to be tested as an interrelated whole.

1.3.2 Factory Tests

Tests shall be performed at the factory to verify proper build. These test results will be used in the "Final Acceptance Test" section to verify no shipping damage and proper installation.

1.3.3 Functional Test

Contractor shall perform an "in-house" test to verify that the system and components have been properly installed and are functioning properly. Test shall be performed in the presence of the Contracting Officer. Test shall be completed and found acceptable when system has performed per other sections and referenced industry standards.

1.3.4 Final Acceptance Test

Contractor shall perform a formal test with full documentation using the approved recording form. Contracting Officer will witness this test and issue a written final acceptance. Final test data shall be provided to the Contracting Officer. Data shall have a cover letter/sheet clearly marked with the system name, date, and the words "Final Test Data - Forward to the Systems Engineer/Condition Monitoring Office/Predictive Testing Group for inclusion in the Maintenance Database."

1.3.5 Test Procedures

Test procedure and recording forms that document the test steps shall be submitted for approval to the Contracting Officer 21 calendar days prior to the proposed test date. Procedure shall consist of step by step instruction to verify system parameters, components, and functions.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --