

\*\*\*\*\*  
USACE / NAVFAC / AFCEC / NASA UFGS-32 01 19.61 (April 2006)  
-----  
Preparing Activity: NAVFAC Replacing without change  
UFGS-02982 (August 2004)

## UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UMRL dated July 2013

\*\*\*\*\*

### SECTION TABLE OF CONTENTS

#### DIVISION 32 - EXTERIOR IMPROVEMENTS

#### SECTION 32 01 19.61

#### RESEALING OF JOINTS IN RIGID PAVEMENT

04/06

#### PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 DELIVERY, STORAGE, AND HANDLING
- 1.4 ENVIRONMENTAL REQUIREMENTS
- 1.5 TRAFFIC CONTROL
- 1.6 EQUIPMENT
  - 1.6.1 Joint Cleaning Equipment
    - 1.6.1.1 Routing Tool
    - 1.6.1.2 Concrete Saw
    - 1.6.1.3 Sandblasting Equipment
    - 1.6.1.4 Air Compressor
    - 1.6.1.5 Vacuum Sweeper
    - 1.6.1.6 Hand Tools
  - 1.6.2 Joint Sealing Equipment
    - 1.6.2.1 Hot-Poured Liquid Sealant
    - 1.6.2.2 Two-Component Cold-Applied Liquid Sealants
    - 1.6.2.3 Equipment for Silicone Sealant
- 1.7 SAFETY PROVISIONS

#### PART 2 PRODUCTS

- 2.1 MATERIALS
  - 2.1.1 Joint Sealant
    - 2.1.1.1 Two Component Cold-Applied Sealing Compound
    - 2.1.1.2 Sealant, Joint, Jet-Fuel Resistant, Hot-Applied
    - 2.1.1.3 Sealant, Joint, Non-Jet Fuel Resistant, Hot Applied
    - 2.1.1.4 Single Component Cold-Applied Silicone
  - 2.1.2 Primers
  - 2.1.3 Bond Breakers
    - 2.1.3.1 Blocking Media
    - 2.1.3.2 Separating Tape

#### PART 3 EXECUTION

- 3.1 JOINT PREPARATION
  - 3.1.1 Removal of Existing Material
  - 3.1.2 Refacing of Joints
    - 3.1.2.1 Joint Widening (Except Expansion Joints)
  - 3.1.3 Final Cleaning of Joints
    - 3.1.3.1 Sandblasting Cleaning
  - 3.1.4 Bond Breaker
    - 3.1.4.1 Blocking Media (Backer Rod) (Except for Expansion Joints)
    - 3.1.4.2 Separating Tape
  - 3.1.5 Rate of Progress
  - 3.1.6 Disposal of Debris
- 3.2 PREPARATION OF SEALANT
  - 3.2.1 Hot-Poured Type
  - 3.2.2 Cold-Applied, Two Component Type
- 3.3 INSTALLATION OF SEALANT
  - 3.3.1 Test Section
  - 3.3.2 Time of Application
  - 3.3.3 Sealing the Joints
- 3.4 FIELD QUALITY CONTROL
  - 3.4.1 Sampling Joint Seal
  - 3.4.2 Joints
  - 3.4.3 Joint Seal Test Section
  - 3.4.4 Joint Sealer
- 3.5 ACCEPTANCE

-- End of Section Table of Contents --

\*\*\*\*\*  
USACE / NAVFAC / AFCEC / NASA UFGS-32 01 19.61 (April 2006)  
-----  
Preparing Activity: NAVFAC Replacing without change  
UFGS-02982 (August 2004)

## UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UMRL dated July 2013

\*\*\*\*\*

### SECTION 32 01 19.61

#### RESEALING OF JOINTS IN RIGID PAVEMENT 04/06

\*\*\*\*\*

NOTE: This guide specification covers the requirements for removal of old sealing materials from existing joints of portland cement concrete pavement and resealing of joints.

Adhere to [UFC 1-300-02](#) Unified Facilities Guide Specifications (UFGS) Format Standard when editing this guide specification or preparing new project specification sections. Edit this guide specification for project specific requirements by adding, deleting, or revising text. For bracketed items, choose applicable items(s) or insert appropriate information.

Remove information and requirements not required in respective project, whether or not brackets are present.

Comments, suggestions and recommended changes for this guide specification are welcome and should be submitted as a [Criteria Change Request \(CCR\)](#).

\*\*\*\*\*

\*\*\*\*\*

NOTE: For joints in new pavement, use Section [32 13 73](#) COMPRESSION JOINT SEALS FOR CONCRETE PAVEMENTS. When crack repair is involved, edit accordingly, including the section title. This specification should not be used for liquid oxygen compatible joint seals.

\*\*\*\*\*

\*\*\*\*\*

NOTE: The following information shall be shown on the project drawings:

1. Spacing, width, and type of joints in concrete pavements to be sealed.
2. Typical details of existing joints.

3. Depth of existing sealant to be removed for each type of joint, if not specified.

4. Detail of type of joint to be refaced or widened with a concrete saw. Show extent of new width and depth of sawing to provide the proper shape factor of the void space in the joint. For materials, other than silicone, the ratio of the depth to width (d/w) of the sealant reservoir should generally be not less than 1 nor greater than 1.5. For silicone sealant a depth to width ratio of approximately 0.5 is preferred. Depending upon the width of the refaced joint, the thickness of the sealant bead should be between 6 and 13 mm 1/4 and 1/2 inch. Following are the recommended details for silicone sealants:

<u>Refaced Joint Width</u>	<u>10 mm</u>	<u>13 mm</u>	<u>19 mm</u>	<u>25 mm</u>
Recess Below Surface	6 mm	6 mm	6 mm	13 mm
Thickness of Sealant	6 mm	6 mm	10 mm	13 mm
Backer Rod Diameter	13 mm	16 mm	22 mm	31 mm
Total Depth of Joint	25 mm	28 mm	38 mm	56 mm

<u>Refaced Joint Width</u>	<u>3/8"</u>	<u>1/2"</u>	<u>3/4"</u>	<u>1"</u>
Recess Below Surface	1/4"	1/4"	1/4"	1/2"
Thickness of Sealant	1/4"	1/4"	3/8"	1/2"
Backer Rod Diameter	1/2"	5/8"	7/8"	1 1/4"
Total Depth of Joint	1"	1 1/8"	1 1/2"	2 1/4"

5. Location and type of bond breaker or back-up.

6. Identify type of sealant based on proposed use of pavements. (See note in paragraph entitled "Joint Sealant.")

7. For joint details see MIL-HDBK-1021/4.

\*\*\*\*\*

## PART 1 GENERAL

### 1.1 REFERENCES

\*\*\*\*\*

NOTE: This paragraph is used to list the publications cited in the text of the guide specification. The publications are referred to in the text by basic designation only and listed in this paragraph by organization, designation, date,

and title.

Use the Reference Wizard's Check Reference feature when you add a RID outside of the Section's Reference Article to automatically place the reference in the Reference Article. Also use the Reference Wizard's Check Reference feature to update the issue dates.

References not used in the text will automatically be deleted from this section of the project specification when you choose to reconcile references in the publish print process.

\*\*\*\*\*

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C603	(2004; R 2008) Extrusion Rate and Application Life of Elastomeric Sealants
ASTM C639	(2001; R 2011) Rheological (Flow) Properties of Elastomeric Sealants
ASTM C661	(2006; R 2011) Indentation Hardness of Elastomeric-Type Sealants by Means of a Durometer
ASTM C679	(2003; E 2009; R 2009) Tack-Free Time of Elastomeric Sealants
ASTM C719	(1993; R 2010) Adhesion and Cohesion of Elastomeric Joint Sealants Under Cyclic Movement (Hockman Cycle)
ASTM C792	(2004; R 2008) Effects of Heat Aging on Weight Loss, Cracking, and Chalking of Elastomeric Sealants
ASTM C793	(2005; R 2010) Effects of Accelerated Weathering on Elastomeric Joint Sealants
ASTM D412	(2006a; R 2013) Standard Test Methods for Vulcanized Rubber and Thermoplastic Elastomers - Tension

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FS SS-S-1401	(Rev C; Am 1; Notices 1, 2) Sealant, Joint, Non-Jet-Fuel-Resistant, Hot-Applied, for Portland Cement and Asphalt Concrete Pavements
FS SS-S-1614	(Rev A; Am 1; Notices 1, 2) Sealants, Joint, Jet-Fuel-Resistant, Hot-Applied, for Portland Cement and Tar Concrete Pavements

## 1.2 SUBMITTALS

\*\*\*\*\*

NOTE: Review Submittal Description (SD) definitions in Section 01 33 00 SUBMITTAL PROCEDURES and edit the following list to reflect only the submittals required for the project.

The Guide Specification technical editors have designated those items that require Government approval, due to their complexity or criticality, with a "G". Generally, other submittal items can be reviewed by the Contractor's Quality Control System. Only add a "G" to an item, if the submittal is sufficiently important or complex in context of the project.

For submittals requiring Government approval on Army projects, a code of up to three characters within the submittal tags may be used following the "G" designation to indicate the approving authority. Codes for Army projects using the Resident Management System (RMS) are: "AE" for Architect-Engineer; "DO" for District Office (Engineering Division or other organization in the District Office); "AO" for Area Office; "RO" for Resident Office; and "PO" for Project Office. Codes following the "G" typically are not used for Navy, Air Force, and NASA projects.

Choose the first bracketed item for Navy, Air Force and NASA projects, or choose the second bracketed item for Army projects.

\*\*\*\*\*

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are [for Contractor Quality Control approval.] [for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government.] The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

### SD-03 Product Data

#### Joint sealant

Submit catalog cuts, specifications, material Safety Data Sheets and other information documenting conformance to contract requirements.

### SD-04 Samples

\*\*\*\*\*

NOTE: Liquid joint sealer proposed for use in airfield pavements should be tested by the U.S. Army Corps of Engineer, Waterways Experiment Station, P. O. Box 631, Vicksburg, MS 39180, Attn: Larry Lynch, telephone: (601) 634-4274, before acceptance. Project Managers should assure that sufficient funds (approximately \$1500) are available and that the 45 day testing time requirement has been taken into account when establishing contract completion time. For small projects involving approximately less than 3,000 m 10,000 linear feet of joint sealing, the requirement for testing may be waived provided that a Factory Test Report is submitted. In no case should materials not meeting the applicable specification be accepted.

\*\*\*\*\*

Joint filler

Separating tape

Joint backer rod

Joint sealant

Furnish for testing a five gallon sample of each joint seal with associated primer to the Contracting Officer a minimum of 60 days prior to its use on the job. Each container shall be factory sealed and must contain a factory applied label showing the following information:

Name of sealant

Identification of component, or primer

Specification number and type

Manufacturer's name

Manufacturer's lot and batch number

Date of Manufacture (month and year)

Shelf life retest date (month and year)

List of hazardous components

Quantity of material in container (volume)

Storage instructions

Instructions for use

SD-06 Test Reports

\*\*\*\*\*

NOTE: Liquid joint sealer proposed for use in airfield pavements should be tested by the U.S. Army Corps of Engineer, Waterways Experiment Station, P.

O. Box 631, Vicksburg, MS 39180, Attn: Larry Lynch,  
telephone: (601) 634-4274, before acceptance.  
Project Managers should assure that sufficient funds  
(approximately \$1500) are available and that the 45  
day testing time requirement has been taken into  
account when establishing contract completion time.  
For small projects involving approximately less than  
3,000 m 10,000 linear feet of joint sealing, the  
requirement for testing may be waived provided that  
a Factory Test Report is submitted. In no case  
should materials not meeting the applicable  
specification be accepted.

\*\*\*\*\*

\*\*\*\*\*

NOTE: Factory test report should be required for  
joint seals on projects when the Government testing  
is waived.

\*\*\*\*\*

[ Joint sealant]

SD-07 Certificates

Equipment list

SD-08 Manufacturer's Instructions

Joint sealant

Instructions shall include, but not be limited to: storage  
requirements, ambient temperature and humidity ranges, and  
moisture condition of joints for successful installation;  
requirements for preparation of joints; safe heating temperature;  
mixing instructions; installation equipment and procedures;  
application and disposal requirements; compatibility of sealant  
with filler material; curing requirements; and restrictions to be  
adhered to in order to reduce hazards to personnel or to the  
environment. Submit instructions at least 30 days prior to use.

### 1.3 DELIVERY, STORAGE, AND HANDLING

Inspect materials delivered to the site for visible damage, and unload and  
store with a minimum of handling. Joint materials shall be delivered in  
original sealed containers and shall be protected from freezing or  
overheating. Provide jobsite storage facilities capable of maintaining  
temperature ranges within manufacturers recommendations.

### 1.4 ENVIRONMENTAL REQUIREMENTS

Work shall not proceed when weather conditions detrimentally affect the  
quality of cleaning joints or applying joint sealants. Joint preparation  
and sealing shall proceed only when weather conditions are in accordance  
with manufacturer's instructions. During installation, surfaces shall be  
dry and sealant and bond breakers shall be protected from moisture.

### 1.5 TRAFFIC CONTROL

Do not permit vehicular or heavy equipment traffic on the pavement in the



area of the joints being sealed during the protection and curing period of the joint sealant. At the end of the curing period, traffic may be permitted on the pavement when approved.

## 1.6 EQUIPMENT

Submit a [equipment list](#) and description of the equipment to be used and a statement from the supplier of the joint sealant that the proposed equipment is acceptable for installing the specified sealant. Equipment for heating, mixing, and installing joint seals shall be in accordance with the instructions provided by the joint seal manufacturer. Furnish equipment, tools, and accessories necessary to clean existing joints and install liquid joint sealants. Maintain machines, tools, and other equipment in proper working condition.

### 1.6.1 Joint Cleaning Equipment

#### 1.6.1.1 Routing Tool

To remove old sealant from joints, select rectangular shaped routing tool that is adjustable to varying widths and depths required. The equipment shall be capable of maintaining accurate cutting depth and width control. The joint plow shall be equipped with a spring or hydraulic mechanism to release pressure on the tool prior to spalling the concrete.

#### 1.6.1.2 Concrete Saw

Self-propelled power saw with diamond saw blades designed for sawing, refacing, widening, or deepening existing joints as specified without damaging the sides, bottom, or top edge of joints. Blades may be single or gang type with one or more blades mounted in tandem for fast cutting. Select saw adequately powered and sized to cut specified opening with not more than two passes of the saw through the joint.

#### 1.6.1.3 Sandblasting Equipment

Commercial type capable of removing residual sealer, oil, or other foreign material. Equipment shall include an air compressor, hose and nozzles of proper size, shape, and opening. Attach an adjustable guide that will hold the nozzles aligned with the joint to effectively and efficiently clean without damage to concrete edges. Adjust height, angle of inclination, or size of nozzles to sandblast joint faces and not bottom of joint.

#### 1.6.1.4 Air Compressor

Portable air compressor capable of operating the sandblasting equipment and capable of blowing out sand, water, dust adhering to sidewalls of concrete, and other objectionable materials from the joints. The compressor shall furnish air at a pressure not less than [620 kPa 90 psi](#) and a minimum rate of [0.07 cubic meter of air per second 150 cubic feet of air per minute](#) at the nozzles and free of oil.

#### 1.6.1.5 Vacuum Sweeper

Self-propelled, vacuum pickup sweeper capable of completely removing loose sand, water, joint material, and debris from pavement surface.

#### 1.6.1.6 Hand Tools

When approved, hand tools such as brooms and chisels may be used in small areas for removing old sealant from joints and repairing or cleaning the joint faces.

#### 1.6.2 Joint Sealing Equipment

Joint sealing equipment shall be of a type required by the joint seal manufacturer's installation instructions. Equipment shall be capable of installing sealant to the depths, widths and tolerances indicated. When malfunctions are noted, joint sealing shall not proceed until they are corrected.

##### 1.6.2.1 Hot-Poured Liquid Sealant

Install hot-poured sealant materials with unit applicators which will heat and extrude the sealant. Equip the mobile units with double-wall agitator type kettles with an oil medium in the outer space for heat transfer, a direct-connected pressure-type extruding device with nozzles shaped for insertion in the joints to be filled, and a positive device for controlling the temperature of oil and sealer. Design the applicator so that the sealant will circulate through the delivery hose and return to the kettle when not sealing a joint. Insulate the applicator wand from the kettle to the nozzle. Select dimensions of the nozzles such that the tip of the nozzle will easily feed sealant into the void space of the joint. Equip the nozzle tip with a metal cross-bar to ensure that the top of the sealant fed into the joint is level and within the indicated tolerance below the pavement surface.

##### 1.6.2.2 Two-Component Cold-Applied Liquid Sealants

For two component cold applied machine mixed sealants the equipment shall be capable of delivering each component within an accuracy of 5 percent. Equip reservoirs for each component with mechanical agitation devices. Equip equipment with thermostatically controlled indirect heating of components when required. Equipment shall include screens over each reservoir to eliminate foreign particles or partially polymerized material which may clog lines. Equipment shall be capable of intimately mixing the two components through a range of application rates from 0.011 to 0.63 liter per second 10 to 60 gallons per hour and through a range of pressures from 345 to 1034 kPa 50 to 150 pounds per square inch. [Hand-mixing of cold-applied two component sealant may be done at the option of the Contractor for sealants conforming to FS SS-S-200, Type H].

##### 1.6.2.3 Equipment for Silicone Sealant

Equipment for silicone sealant shall be air powered pump, components, and hoses as recommended by the sealant manufacturer. Hoses and seals shall be lined to prevent moisture penetration and withstand pumping pressures. Equipment shall be free of contamination from previously used or other type sealant.

#### 1.7 SAFETY PROVISIONS

\*\*\*\*\*

**NOTE: Specify sandblasting of joint walls as a light cleaning method following sawing of joints. Sandblasting may cause some minor deterioration**

around the joint area. Secure station permission before sandblasting. If necessary, insert a cross-reference to Section 01 57 19.00 20 TEMPORARY ENVIRONMENTAL CONTROLS.

\*\*\*\*\*

In accordance with the provisions of the contract respecting "Accident Prevention," the Contractor shall take appropriate measures to control worker exposure to toxic substances during the work. Provide personnel protective equipment as required. Material Safety Data Sheets (Department of Labor Form OSHA-20 or comparable form) shall be available on the site. [Sandblasting operations shall conform to paragraph entitled "Abrasive Blasting" of Section 01 57 19.00 20 TEMPORARY ENVIRONMENTAL CONTROLS.]

## PART 2 PRODUCTS

### 2.1 MATERIALS

#### 2.1.1 Joint Sealant

\*\*\*\*\*

NOTE: Select joint sealants based on service conditions of pavements. Joint sealants may be either two-component cold applied, single component cold applied (silicone), or hot-applied. Silicone sealants may be exclusively specified at the option of the design engineer when supported by lower life cycle costs.

Single Component Cold Applied Silicone: Silicone sealant may be used for general purpose sealing and re-sealing of joints in concrete pavements not subject to severe jet fuel or lubricant spillage. Silicone will swell up under fuel spills. This may result in an unsatisfactory seal in aircraft or vehicle servicing areas where spillage is frequent and severe. Laboratory test data has shown that silicone seals possess resistance to the heat and velocity of jet engines and they may be used as an alternative to FS SS-S-200 material in the end 305 m 1000 ft. of runways.

FS SS-S-200 - For sealing joints in portland-cement concrete pavements subjected to the spillage of lubricating oils, hydraulic fluids, jet fuel and to the heat and blast of jet aircraft engines including simulated aircraft carrier decks within standard runways.

FS SS-S-1614 - For sealing joints and cracks in pavements subject to the spillage of lubricating oils and jet fuel. It is not intended to be resistant to the heat and blast of jet aircraft engines except when the aircraft is moving at moderate speeds.

FS SS-S-1401 - For sealing joints and cracks in pavements not subjected to the spillage of lubricating oils, hydraulic fluids, and fuels. This

material may also be used to seal cracks in asphalt concrete pavements. It is not intended to be resistant to the heat and blast of jet aircraft engines except when the aircraft is moving at moderate speeds.

\*\*\*\*\*

#### 2.1.1.1 Two Component Cold-Applied Sealing Compound

\*\*\*\*\*

NOTE: Either choose Type H (hand mixed, retarded cure) or M (machine mixed, fast curing), or indicate both and permit the Contractor to exercise the option depending on field conditions or scheduling constraints. Restrict use of Type H to small projects or limited areas of large projects.

\*\*\*\*\*

[FS SS-S-200, Type [H] [M]].

#### 2.1.1.2 Sealant, Joint, Jet-Fuel Resistant, Hot-Applied

[FS SS-S-1614, for portland cement and tar concrete pavements.]

#### 2.1.1.3 Sealant, Joint, Non-Jet Fuel Resistant, Hot Applied

[FS SS-S-1401, for portland cement and asphalt concrete pavements.]

#### 2.1.1.4 Single Component Cold-Applied Silicone

Silicone sealant shall be self leveling, non-acid curing, and meet the following requirements:

TEST	TEST METHOD	REQUIREMENTS
Weight Loss	ASTM C792 Modified (see note 1 below)	10 percent max.
Flow	ASTM C639 (Type I)	smooth and level
Extrusion Rate	ASTM C603	30 sec. max.
Tack Free Time	ASTM C679	5 hours max.
Hardness (Shore 00) (see note 2 below)	ASTM C661	30 - 80
Tensile Stress at 150 Percent Elongation (see note 2 below)	ASTM D412 (Die C)	207 kPa max. 30 psi max.
Percent Elongation (see note 2 below)	ASTM D412 (Die C)	700 min.
Accelerated Weathering	ASTM C793	pass 5000 hours

Bond and Movement Capability	ASTM C719	pass 10 cycles at <u>plus</u> 50 percent movement (no adhesion or cohesion failure)
Flame Resistance	FS SS-S-200	pass
Notes: 1. Percent weight loss of wet (uncured) sample after placing in forced-draft oven maintained at 70 degrees <u>plus</u> 2 degrees C 158 degrees <u>plus</u> 1 degrees F for two hours. 2. Specimen cured 21 days at 23 degrees C <u>plus</u> 2 degrees C 73 degrees <u>plus</u> 1 degree F and 50 percent <u>plus</u> 5 percent humidity.		

ACCELERATED WEATHERING FACTORY TEST REPORT. For the Accelerated Weathering test, in lieu of testing of actual joint sealant to be used on the project, a report of a factory test, performed within two years of contract award, may be submitted.

#### 2.1.2 Primers

Select concrete primer recommended by the manufacturer of the proposed liquid joint sealant.

#### 2.1.3 Bond Breakers

##### 2.1.3.1 Blocking Media

Compressible, nonshrinkable, nonreactive with joint sealant and nonabsorption type such as plastic backer rod, free of oils or bitumens. Blocking media shall be consistent with the joint seal manufacturer's installation instructions and be at least 25 percent larger in diameter than the width of the cleaned and re-faced joints as shown.

##### 2.1.3.2 Separating Tape

Polyethylene or polyester tape, 0.075 mm 3 mil minimum thickness, or masking tape, nonreactive, nonabsorptive, adhesive-back tape, width equal to width of cleaned and refaced joints as indicated. Separating tape shall be consistent with the joint seal manufacturer's installation instructions.

### PART 3 EXECUTION

#### 3.1 JOINT PREPARATION

\*\*\*\*\*  
**NOTE: Provide details of the existing joints and the required depth of removal of old sealant on the drawings.**  
\*\*\*\*\*

Unless otherwise indicated, remove existing material, saw, clean and reseal joints. Do not proceed with final cleaning operations by more than one working day in advance of sealant. Thoroughly clean joints by removing

existing joint sealing compound, bond-breakers, dirt, and other foreign material with the equipment specified herein, but not limited thereto. Cleaning procedures which damage joints or previously repaired patches by chipping or spalling will not be permitted. Remove existing sealant to the required depth as indicated. Precise shape and size of existing joints vary, and conditions of joint walls and edges vary and include but are not limited to rounding, square edges, sloping, chips, voids, depressions, and projections.

#### 3.1.1 Removal of Existing Material

\*\*\*\*\*  
**NOTE: Specify and show on the plans the depth to  
remove the old sealant from all types of joints.  
Show typical existing joint dimensions.**  
\*\*\*\*\*

Remove from the joint the existing sealants by using the specified routing tool. After cutting free the existing sealant from both joint faces, remove sealant to the depth required to accommodate the bond breaking material and to maintain the specified depth for the new sealant. For expansion joints, remove existing sealant to a depth of not less than [the indicated depth.] **25 mm one inch**. When existing preformed expansion-joint material is more than **25 mm one inch** below the surface of the pavement, remove existing sealant to the top of the preformed **joint filler**. For joints other than expansion joints, remove in-place sealant to the depth as indicated. At the completion of routing operations, clean pavement surface with vacuum sweeper and clean the joint opening by blowing with compressed air. Protect previously cleaned joints from being contaminated by subsequent cleaning operations.

#### 3.1.2 Refacing of Joints

\*\*\*\*\*  
**NOTE: Specify refacing of joints by sawing for the  
following reasons:**  
  
1. To widen the joint space or change the shape  
factor.  
  
2. To straighten the vertical walls inside the  
joints and remove old sealant.  
\*\*\*\*\*

Reface concrete joint walls. [Re-saw joint grooves to the dimensions indicated.] Refacing shall be by power-driven concrete saw specified herein to remove residual sealant and a minimum of concrete. Removal shall provide exposure of newly clean concrete. Remove burrs and irregularities from sides of joint faces. Immediately after sawing each joint, thoroughly clean saw cut and adjacent concrete surface. Flush with water under pressure, simultaneously blowing water out with compressed air until debris is removed from the joint. Protect adjacent previously cleaned joint spaces from receiving water and debris during the cleaning operation.

##### 3.1.2.1 [Joint Widening (Except Expansion Joints)]

\*\*\*\*\*  
**NOTE: Edit this paragraph as required. New joint  
groove dimensions shall be shown on the plans.**

The following information shall be shown on the project drawings:

1. Spacing, width, and type of joints in concrete pavements to be sealed.
2. Typical details of existing joints.
3. Depth of existing sealant to be removed for each type of joint, if not specified.
4. Detail of type of joint to be refaced or widened with a concrete saw. Show extent of new width and depth of sawing to provide the proper shape factor of the void space in the joint. For materials, other than silicone, the ratio of the depth to width (d/w) of the sealant reservoir should generally be not less than 1 nor greater than 1.5. For silicone sealant a depth to width ratio of approximately 0.5 is preferred. Depending upon the width of the refaced joint, the thickness of the sealant bead should be between 6 and 13 mm 1/4 and 1/2 inch. Following are the recommended details for silicone sealants:

<u>Refaced Joint Width</u>	<u>10 mm</u>	<u>13 mm</u>	<u>19 mm</u>	<u>25 mm</u>
Recess Below Surface	6 mm	6 mm	6 mm	13 mm
Thickness of Sealant	6 mm	6 mm	10 mm	13 mm
Backer Rod Diameter	13 mm	16 mm	22 mm	31 mm
Total Depth of Joint	25 mm	28 mm	38 mm	56 mm

<u>Refaced Joint Width</u>	<u>3/8"</u>	<u>1/2"</u>	<u>3/4"</u>	<u>1"</u>
Recess Below Surface	1/4"	1/4"	1/4"	1/2"
Thickness of Sealant	1/4"	1/4"	3/8"	1/2"
Backer Rod Diameter	1/2"	5/8"	7/8"	1 1/4"
Total Depth of Joint	1"	1 1/8"	1 1/2"	2 1/4"

5. Location and type of bond breaker or back-up.
6. Identify type of sealant based on proposed use of pavements. (See note in paragraph entitled "Joint Sealant.")
7. For joint details see MIL-HDBK-1021/4.

\*\*\*\*\*

Saw joints having grooves less than 10 mm 3/8 inch wide and less than 25 mm

one inch deep to a minimum width of [10] [13] [\_\_\_\_\_] mm [3/8] [1/2]  
[\_\_\_\_\_] inch and to the minimum depth, [of] [25 mm] [38 mm] [one inch] [1  
1/2 inches] [as indicated].

### ]3.1.3 Final Cleaning of Joints

#### 3.1.3.1 Sandblasting Cleaning

\*\*\*\*\*  
NOTE: Specify sandblasting of joint walls following  
sawing of joints. Sandblasting may cause some minor  
deterioration around the joint area. Secure station  
permission before sandblasting. If necessary,  
insert a cross-reference to Section 01 57 19.00 20  
TEMPORARY ENVIRONMENTAL CONTROLS.  
\*\*\*\*\*

Following removal of existing sealant, and sawing, and immediately before  
resealing, thoroughly clean newly exposed concrete joint faces and pavement  
surface extending up to 50 mm 2 inches from each joint edge by sandblasting  
until concrete surfaces in the joint space are free of sealants, dust,  
dirt, water and other foreign materials which would prevent bonding of new  
sealants to the concrete. Use sand particles of the proper size and  
quality for the work. Perform sandblasting with specified nozzles, air  
compressor, and other appurtenant equipment. Position nozzles to clean the  
joint faces. Make at least two passes; one for each joint face. Make as  
many passes as required for proper cleaning. Immediately prior to sealing  
the joint, blow out the joint spaces with compressed air until completely  
free of sand, water, and dust. Joints shall be dry before installation of  
joint sealant. Replace expansion joint filler material damaged in  
performing the work with new materials of the same type and dimensions as  
the existing material, or with appropriate blocking media.

#### 3.1.4 Bond Breaker

At the time the joints receive the final cleaning and are dry, install bond  
breaker material as indicated with a steel wheel or other approved device.

##### 3.1.4.1 Blocking Media (Backer Rod) (Except for Expansion Joints)

Plug or seal off the lower portion of the groove by installing the  
specified blocking media as indicated.

##### 3.1.4.2 Separating Tape

Insert the specified tape as indicated.

#### 3.1.5 Rate of Progress

The final stages of joint preparation, which include placement of bond  
breakers, if required, shall be limited to only that length of joint that  
can be resealed during the same workday.

#### 3.1.6 Disposal of Debris

\*\*\*\*\*  
NOTE: Specify location of disposal of debris.  
\*\*\*\*\*



Sweep from pavement surface to remove excess joint material, dirt, water, sand, and other debris by vacuum sweepers or hand brooms. Remove the debris immediately [to a point off station.] [to an area designated by the Contracting Officer.] [in accordance with Section 02 41 00 [DEMOLITION] [AND ] [DECONSTRUCTION]].

### 3.2 PREPARATION OF SEALANT

#### 3.2.1 Hot-Poured Type

Heat hot-poured sealing materials in accordance with safe heating temperature ranges recommended by the manufacturer. Withdraw and waste sealant that has been overheated or subjected to heating for over 3 hours or that remain in the applicator at the end of the day's operation. Heat sealant in specified equipment.

#### 3.2.2 Cold-Applied, Two Component Type

Reject materials which contain water, hard caking or separated constituents, nonreversible jell, or other unsatisfactory conditions such as settlement of constituents into a soft mass that cannot be readily and uniformly remixed in the field with simple tools. In conformance with the manufacturer's recommendations, mix individual components in separate shipping containers before transferring components to appropriate reservoirs of application equipment. Thoroughly mix components to ensure homogeneity of components and incorporation of constituents at time of transfer. When necessary, for remixing prior to transfer, warm components to a temperature not exceeding 32 degrees C 90 degrees F by placing components in heated storage or by other approved methods. In no case shall components be heated by direct flame or in single-walled, non-oil-bath heating kettles. [Hand mixing of cold-applied two component sealant may be done at the option of the Contractor for sealants conforming to FS SS-S-200, Type H.]

### 3.3 INSTALLATION OF SEALANT

#### 3.3.1 Test Section

\*\*\*\*\*  
NOTE: Specify factory representative for projects  
with more than approximately 3,000 m 10,000 linear  
feet of re-sealing.  
\*\*\*\*\*

Install a test section of 60 m 200 linear feet at the start of the sealing operation for each type sealant to be used. [A representative of the joint seal manufacturer shall be on site full time during the installation of the test section.] Test section shall meet contract requirements. The Contracting Officer shall be notified upon completion of the test section.

#### 3.3.2 Time of Application

After approval of the test section, seal joints immediately following final cleaning and placing of bond breakers. Commence sealing joints when walls are dust free and dry, and when weather conditions meet joint seal manufacturer's instructions. If the above conditions cannot be met, or when rains interrupts sealing operations, reclean and permit the joints to dry prior to installing the sealant.

### 3.3.3 Sealing the Joints

\*\*\*\*\*  
**NOTE: Specify 5 hours tack free time for silicone.**  
\*\*\*\*\*

Do not install joint sealant until joints to be sealed have been inspected and approved. Install bond breaker just prior to pouring sealant. Fill the joints with sealant from bottom up until joints are uniformly filled solid from bottom to top using the specified equipment for the type of sealant required. Fill joints to 6 mm 1/4 inch below top of pavement within tolerances as indicated, and without formation of voids or entrapped air. Except as otherwise permitted, tool the sealant immediately after application to provide firm contact with the joint walls and to form the indicated sealant profile below the pavement surface. Remove excess sealant that has been inadvertently spilled on the pavement surface. [When two-component sealants are placed, each day check hourly the proportioning capability of the equipment to determine that the preset volume output for each component is being maintained. The material used for these checks may be returned to the proper component reservoir. In no case shall two component sealants be installed using gravity methods and pouring spouts, except for approved hand mixing methods. When a primer is supplied or recommended by the manufacturer of a two component sealant, apply the primer evenly to the joint faces in accordance with the manufacturer's recommendations.] Check sealed joints frequently to assure that newly installed sealant is cured to a tack-free condition within [3 hours] [5 hours]. Protect new sealant from rain during curing period.

### 3.4 FIELD QUALITY CONTROL

#### 3.4.1 Sampling Joint Seal

Obtain a one gallon sample of each type of joint seal on the project from material used for each 3,000 m 10,000 linear feet or less of joints sealed. Store samples according to joint seal manufacturer's instructions. Retain samples until final acceptance of the work by the Contracting Officer.

#### 3.4.2 Joints

Inspect and approve joints which have been cleaned and have backer rods or bond breaking tape installed prior to sealing.

#### 3.4.3 Joint Seal Test Section

Inspect joint seal test section [with the joint seal manufacturer's representative]. [The joint seal manufacturer's representative shall provide written notice of deficiencies and required corrections or adjustments in joint seal installation procedures.] Correct deficiencies and obtain approval of test section [by the Contracting Officer] prior to installing joint seals.

#### 3.4.4 Joint Sealer

Inspect installed joint seals for conformance to contract requirements, joint seal manufacturer's instructions, and the test section. Obtain approval for each joint seal installation.

### 3.5 ACCEPTANCE

Reject joint sealer that fails to cure properly, or fails to bond to joint walls, or reverts to the uncured state, or fails in cohesion, or shows excessive air voids, blisters, surface defects, swelling, or other deficiencies, or is not properly recessed within indicated tolerances. Remove rejected sealer and reclean and reseal joints in accordance with the specification. Perform removal and reseal work promptly by and at the expense of the Contractor.

-- End of Section --