
USACE / NAVFAC / AFCEC / NASA

UFGS-26 08 00 (August 2008)

Change 2 - 08/21

Preparing Activity: NAVFAC

Superseding

UFGS-26 08 00 (April 2006)

UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with UMRL dated July 2021

SECTION TABLE OF CONTENTS

DIVISION 26 - ELECTRICAL

SECTION 26 08 00

APPARATUS INSPECTION AND TESTING

08/08, CHG 2: 08/21

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 RELATED REQUIREMENTS
- 1.3 SUBMITTALS
- 1.4 QUALITY ASSURANCE
 - 1.4.1 Qualifications
 - 1.4.2 Acceptance Tests and Inspections Reports
 - 1.4.3 Acceptance Test and Inspections Procedure

PART 2 PRODUCTS

PART 3 EXECUTION

- 3.1 ACCEPTANCE TESTS AND INSPECTIONS
- 3.2 SYSTEM ACCEPTANCE
- 3.3 PLACING EQUIPMENT IN SERVICE

-- End of Section Table of Contents --

INSULATED PAD-MOUNTED SWITCHGEAR
 --Section 26 11 16 SECONDARY UNIT SUBSTATIONS
 --Section 26 11 13.00 20 PRIMARY UNIT SUBSTATION
 --Section 26 36 23 AUTOMATIC TRANSFER SWITCHES AND
 BY-PASS/ISOLATION SWITCH
 --Section 26 23 00 LOW VOLTAGE SWITCHGEAR
 --Section 26 24 13 SWITCHBOARDS
 --Section 26 35 43 400-HERTZ (HZ) SOLID STATE
 FREQUENCY CONVERTER
 --Section 26 35 44 270 VDC SOLID STATE CONVERTER

This section shall also be used for specification sections containing low-voltage or medium voltage generator control switchboards or switchgear, pad-mounted air switches, and medium voltage circuit breakers. Provide the section numbers and titles in this section, and add NETA testing requirements to the applicable section.

Coordinate the sections in your contract documents with this list and with paragraph entitled "Acceptance Tests and Inspection" in PART 3 of this specification.

PART 1 GENERAL

1.1 REFERENCES

NOTE: This paragraph is used to list the publications cited in the text of the guide specification. The publications are referred to in the text by basic designation only and listed in this paragraph by organization, designation, date, and title.

Use the Reference Wizard's Check Reference feature when you add a Reference Identifier (RID) outside of the Section's Reference Article to automatically place the reference in the Reference Article. Also use the Reference Wizard's Check Reference feature to update the issue dates.

References not used in the text will automatically be deleted from this section of the project specification when you choose to reconcile references in the publish print process.

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS

(2021) Standard for Acceptance Testing
 Specifications for Electrical Power
 Equipment and Systems

1.2 RELATED REQUIREMENTS

Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM applies to this section with additions and modifications specified herein.

1.3 SUBMITTALS

NOTE: Review Submittal Description (SD) definitions in Section 01 33 00 SUBMITTAL PROCEDURES and edit the following list, and corresponding submittal items in the text, to reflect only the submittals required for the project. The Guide Specification technical editors have classified those items that require Government approval, due to their complexity or criticality, with a "G". Generally, other submittal items can be reviewed by the Contractor's Quality Control System. Only add a "G" to an item if the submittal is sufficiently important or complex in context of the project.

For Army projects, fill in the empty brackets following the "G" classification, with a code of up to three characters to indicate the approving authority. Codes for Army projects using the Resident Management System (RMS) are: "AE" for Architect-Engineer; "DO" for District Office (Engineering Division or other organization in the District Office); "AO" for Area Office; "RO" for Resident Office; and "PO" for Project Office. Codes following the "G" typically are not used for Navy, Air Force, and NASA projects.

The "S" classification indicates submittals required as proof of compliance for sustainability Guiding Principles Validation or Third Party Certification and as described in Section 01 33 00 SUBMITTAL PROCEDURES.

Choose the first bracketed item for Navy, Air Force, and NASA projects, or choose the second bracketed item for Army projects.

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are [for Contractor Quality Control approval.][for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government.] Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-06 Test Reports

Acceptance Tests and Inspections; G[, [____]]

SD-07 Certificates

Qualifications of Organization, and Lead Engineering Technician; G

[, [____]]

Acceptance Test and Inspections Procedure; G[, [____]]

1.4 QUALITY ASSURANCE

1.4.1 Qualifications

Contractor shall engage the services of a qualified testing organization to provide inspection, testing, calibration, and adjustment of the electrical distribution system and generation equipment listed in paragraph entitled "Acceptance Tests and Inspections" herein. Organization shall be independent of the supplier, manufacturer, and installer of the equipment. The organization shall be a first tier subcontractor. No work required by this section of the specification shall be performed by a second tier subcontractor.

- a. Submit name and qualifications of organization. Organization shall have been regularly engaged in the testing of electrical materials, devices, installations, and systems for a minimum of 5 years. The organization shall have a calibration program, and test instruments used shall be calibrated in accordance with **NETA ATS**.
- b. Submit name and qualifications of the lead engineering technician performing the required testing services. Include a list of three comparable jobs performed by the technician with specific names and telephone numbers for reference. Testing, inspection, calibration, and adjustments shall be performed by an engineering technician, certified by NETA or the National Institute for Certification in Engineering Technologies (NICET) with a minimum of 5 years' experience inspecting, testing, and calibrating electrical distribution and generation equipment, systems, and devices.

1.4.2 Acceptance Tests and Inspections Reports

Submit certified copies of inspection reports and test reports. Reports shall include certification of compliance with specified requirements, identify deficiencies, and recommend corrective action when appropriate. Type and neatly bind test reports to form a part of the final record. Submit test reports documenting the results of each test not more than 10 days after test is completed.

1.4.3 Acceptance Test and Inspections Procedure

Submit test procedure reports for each item of equipment to be field tested at least 45 days prior to planned testing date. Do not perform testing until after test procedure has been approved.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 ACCEPTANCE TESTS AND INSPECTIONS

Testing organization shall perform acceptance tests and inspections. Test methods, procedures, and test values shall be performed and evaluated in accordance with **NETA ATS**, the manufacturer's recommendations, and

paragraph entitled "Field Quality Control" of each applicable specification section. Tests identified as optional in NETA ATS are not required unless otherwise specified. Equipment shall be placed in service only after completion of required tests and evaluation of the test results have been completed. Contractor shall supply to the testing organization complete sets of shop drawings, settings of adjustable devices, and other information necessary for an accurate test and inspection of the system prior to the performance of any final testing. Contracting Officer shall be notified at least 14 days in advance of when tests will be conducted by the testing organization. Perform acceptance tests and inspections on applicable equipment and systems specified in the following sections:

NOTE: Select applicable sections for each project. Ensure each equipment section includes the following information. These changes should be found in NAVFAC LANT's Interim Specification Revision.

1. NETA ATS listed in the references.
2. The words "and Section 26 08 00 APPARATUS INSPECTION AND TESTING apply" added to paragraph entitled "Related Requirements."
3. SD-06 submittals with "Acceptance checks and tests" added in PART 1.
4. Appropriate paragraphs from the NETA manual added under "Field Quality Control" in PART 3.
5. Add any job section numbers and titles containing low-voltage or medium voltage generator control switchgear or switchboards, pad-mounted air switches, or medium voltage circuit breakers. Provide the NETA tests required in the applicable section.

- [a. Section 26 32 15.00 ENGINE-GENERATOR SET STATIONARY 15-2500 KW, WITH AUXILIARIES. Functional engine shutdown tests, vibration base-line test, and load bank test shall not be performed by the testing organization. These tests shall be performed by the start-up engineer.
-] [b. Section 26 12 19.10 THREE-PHASE, LIQUID-FILLED PAD-MOUNTED TRANSFORMERS
-] [c. Section 26 12 21 SINGLE-PHASE PAD-MOUNTED TRANSFORMERS
-] [d. Section 33 71 01 OVERHEAD TRANSMISSION AND DISTRIBUTION
-] [e. Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION. Medium voltage cables and grounding systems only.
-] [f. Section 26 13 00 SF6/HIGH-FIREPOINT FLUID INSULATED PAD-MOUNTED SWITCHGEAR
-] [g. Section 26 11 16 SECONDARY UNIT SUBSTATIONS
-] [h. Section 26 11 13.00 20 PRIMARY UNIT SUBSTATION

-] [i. Section 26 36 23 AUTOMATIC TRANSFER SWITCHES AND BY-PASS/ISOLATION SWITCH
-] [j. Section 26 23 00 LOW VOLTAGE SWITCHGEAR
-] [k. Section 26 24 13 SWITCHBOARDS
-] [l. Section 26 35 43 400 HERTZ ((HZ) SOLID STATE FREQUENCY CONVERTER. The NETA ATS representative must coordinate with the Contractor and the Converter Manufacturers' representative to witness, document, and validate the Converter Field Quality Control, Inspection and Testing. These tests will be performed by the converter manufacturers' representative, however include the documentation in the overall NETA report as well.
-] [m. Section 26 35 44 270 VDC SOLID STATE CONVERTER. The NETA ATS representative must coordinate with the Contractor and the Converter Manufacturers' representative to witness, document, and validate the Converter Field Quality Control, Inspection and Testing. These tests will be performed by the converter manufacturers' representative, however include the documentation in the overall NETA report as well.

] 3.2 SYSTEM ACCEPTANCE

Final acceptance of the system is contingent upon satisfactory completion of acceptance tests and inspections.

3.3 PLACING EQUIPMENT IN SERVICE

A representative of the approved testing organization shall be present when equipment tested by the organization is initially energized and placed in service.

-- End of Section --