

Preparing Activity: TRI SERVICES

UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with TRI SERVICES dated February 2024

\*\*\*\*\*

SECTION TABLE OF CONTENTS

DIVISION 14 - CONVEYING EQUIPMENT

ELECTRIC TRACTION ELEVATORS, JAPAN EDITED SPECIFICATION (JES)

03/24

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
  - 1.2.1 Shop Drawing Requirements
  - 1.2.2 Product Data Requirements
  - 1.2.3 Design Data
    - 1.2.3.1 Reaction Loads
    - 1.2.3.2 Heat Loads
    - 1.2.3.3 Emergency Power Systems
  - 1.2.4 Welders' Requirements
  - 1.2.5 Maintenance Control Program (MCP)
- 1.3 QUALITY ASSURANCE
  - 1.3.1 Qualification
    - 1.3.1.1 Elevator Contractor's Elevator Technicians
  - 1.3.2 Manufacturers' Technical Support
  - 1.3.3 Operation and Maintenance Data
  - 1.3.4 Wiring Diagrams
  - 1.3.5 Machine Room/Control Room Cabinet
- 1.4 NEW INSTALLATION SERVICE
  - 1.4.1 Periodic Elevator Certification Inspection and Testing
- 1.5 MAINTENANCE
- 1.6 FIRE PROTECTION SYSTEM
  - 1.6.1 Fire Alarm Initiating Devices
  - 1.6.2 Fire Sprinklers
  - 1.6.3 Shunt Trip Disconnect

PART 2 PRODUCTS

- 2.1 ELEVATOR DESCRIPTION
  - 2.1.1 Elevator Design Parameters
    - 2.1.1.1 Elevator No.[\_\_\_\_\_] - Emergency Medical Service Accessibility (EMSA)
    - 2.1.1.2 Elevator No.[\_\_\_\_\_] - Larger Capacity (Pallet-Sized) Loading

- 2.1.1.3 Elevator No.[\_\_\_\_\_] - Non-EMSA Elevator
- 2.1.2 Cab Enclosure and Hoistway Entrance Assemblies
- 2.2 ELEVATOR OPERATION
  - 2.2.1 Single, Two-Stop, Automatic Operation
  - 2.2.2 Selective Collective Automatic Operation
  - 2.2.3 Duplex Selective Collective Automatic Operation
  - 2.2.4 Group Automatic Operation
- 2.3 SPECIAL OPERATION AND CONTROL
  - 2.3.1 Keys for Elevator Key Switches
  - 2.3.2 Firefighters' Emergency Operation (FEO)
    - 2.3.2.1 Firefighters' Emergency Operation (FEO) Key Box
  - 2.3.3 Hoistway Access Operation
  - 2.3.4 In-Car Inspection Operation
  - 2.3.5 Independent Service
  - 2.3.6 Selective Door Operation
  - 2.3.7 Elevator Emergency Power Operation
  - 2.3.8 Elevator Auxiliary Power Operating System
  - 2.3.9 Hospital Emergency Commandeering Service (HECS)
- 2.4 ELEVATOR DRIVE MACHINE, HOIST MOTOR, AND DRIVE MOTOR
  - 2.4.1 Manufacturer's Technical Support
  - 2.4.2 Ascending Car Overspeed and Unintended Car Movement Protection
- 2.5 CONTROL EQUIPMENT
  - 2.5.1 Motor Control Equipment
    - 2.5.1.1 Electrical Isolation Protection
  - 2.5.2 Elevator Microprocessor Controller
- 2.6 OPERATING PANELS, SIGNAL FIXTURES, AND COMMUNICATIONS CABINETS
  - 2.6.1 Car and Hall Buttons
  - 2.6.2 Passenger Car-Operating Panel
    - 2.6.2.1 Passenger Controls
    - 2.6.2.2 Service Controls
    - 2.6.2.3 Certificate Window
    - 2.6.2.4 Emergency Signaling Devices
  - 2.6.3 Elevator In-Car Position Indicators
  - 2.6.4 Elevator In-Car Direction Indicators
  - 2.6.5 Hall Call Landing Fixtures
    - 2.6.5.1 Designated Landing Hall Call Fixture
      - 2.6.5.1.1 Location of COMMUNICATION MEANS FAILURE (CMF) Visual Signal
      - 2.6.5.1.2 COMMUNICATION MEANS FAILURE (CMF) Visual and Audible Signal Operation
      - 2.6.5.1.3 Firefighters' Emergency Operation Phase I Switch and Visual Signal
  - 2.6.6 Elevator Car Position and Direction Indicators and Car Arrival Signal
  - 2.6.7 Designated Landing Elevator Identification Fixture
  - 2.6.8 Emergency or Standby Power
- 2.7 CAR DOOR EQUIPMENT
  - 2.7.1 Car Door Operator
  - 2.7.2 Infra-red Curtain Unit
- 2.8 PASSENGER ELEVATOR GUIDES, PLATFORM, AND ENCLOSURE
  - 2.8.1 Roller Guides
  - 2.8.2 Car Enclosure Wall Panels, Return Panels, Doors, Entrance Columns, and Transom
  - 2.8.3 Car Enclosure Top
  - 2.8.4 Car Door
  - 2.8.5 Car Entrance Sill
  - 2.8.6 Cab Finish Floor
  - 2.8.7 Car Fan
  - 2.8.8 Car Lighting

- 2.8.9 Car Protection Pads and Hooks
- 2.9 PASSENGER ELEVATOR HOISTWAY DOORS AND ENTRANCES
  - 2.9.1 Hoistway Entrance Frames
  - 2.9.2 Hoistway Entrance Sills
  - 2.9.3 Hoistway Entrance Doors
  - 2.9.4 Hoistway Entrance Door Track Dust Covers
- 2.10 HOISTWAY EQUIPMENT
  - 2.10.1 Car and Counterweight Guide Rails and Fastenings
  - 2.10.2 Pit Equipment and Support Channels
  - 2.10.3 Pit "STOP" Switch
  - 2.10.4 Traveling Cables
  - 2.10.5 Hoistway Pit Ladder

PART 3 EXECUTION

- 3.1 INSTALLATION
  - 3.1.1 Structural Members and Finish Materials
  - 3.1.2 Miscellaneous Requirements
- 3.2 FIELD QUALITY CONTROL
- 3.3 ACCEPTANCE INSPECTION, TESTING AND COMMISSIONING
  - 3.3.1 Acceptance Inspection Support
  - 3.3.2 Testing Materials and Instruments
  - 3.3.3 Field Tests
    - 3.3.3.1 Endurance Tests
    - 3.3.3.2 Speed Tests
    - 3.3.3.3 Leveling Tests
    - 3.3.3.4 Temperature Rise Tests
    - 3.3.3.5 Balanced Load Test
    - 3.3.3.6 Motor Ampere Tests
    - 3.3.3.7 Elevator Performance and Ride Quality Testing

-- End of Section Table of Contents --

\*\*\*\*\*  
USACE / NAVFAC / AFCEC UFGS-14 21 23.01 33 (March 2024)

JAPAN EDITED SPECIFICATION (JES)  
-----

Preparing Activity: TRI SERVICES

UNIFIED FACILITIES GUIDE SPECIFICATIONS

References are in agreement with TRI SERVICES dated February 2024

\*\*\*\*\*

SECTION 14 21 23.01 33

ELECTRIC TRACTION ELEVATORS, JAPAN EDITED SPECIFICATION (JES)  
03/24

\*\*\*\*\*

NOTE: This guide specification covers the requirements for electric traction passenger elevators.

Adhere to UFC 1-300-02 Unified Facilities Guide Specifications (UFGS) Format Standard when editing this guide specification or preparing new project specification sections. Edit this guide specification for project specific requirements by adding, deleting, or revising text. For bracketed items, choose applicable item(s) or insert appropriate information.

Remove information and requirements not required in respective project, whether or not brackets are present.

Comments, suggestions and recommended changes for this guide specification are welcome and should be submitted as a Criteria Change Request (CCR).

\*\*\*\*\*

\*\*\*\*\*

NOTE: All Army and Navy facility designs which include elevators shall comply with UFC 3-490-06 Elevators.

\*\*\*\*\*

\*\*\*\*\*

NOTE: For Navy and Marine Corps projects, any editing of non-bracketed requirements in this specification must be approved through the NAVFAC FEC VTE Program Lead Certifying Official/Technical Area Expert.

\*\*\*\*\*

PART 1 GENERAL

1.1 REFERENCES

\*\*\*\*\*  
NOTE: This paragraph is used to list the publications cited in the text of the guide specification. The publications are referred to in the text by basic designation only and listed in this paragraph by organization, designation, date, and title.  
\*\*\*\*\*

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 7-16 (2017; Errata 2018; Supp 1 2018) Minimum Design Loads and Associated Criteria for Buildings and Other Structures

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME A17.1/CSA B44 (2021) Safety Code for Elevators and Escalators

ASME A17.2 (2020) Guide for Inspection of Elevators, Escalators, and Moving Walks Includes Inspection Procedures for Electric Traction and Winding Drum Elevators, Hydraulic Elevators, and Escalators and Moving Walks

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C62.41 (1991; R 1995) Recommended Practice on Surge Voltages in Low-Voltage AC Power Circuits

JAPANESE STANDARDS ASSOCIATION (JSA)

JSA JIS A 4302 (2021) Inspection standard of elevator, escalator and dumbwaiter

JSA JIS A 4307 (2019) Lifts for the transport of persons and goods

JSA JIS Z 3801 (2018) Standard qualification test and acceptance requirements for manual welding technique

JSA JIS Z 3821 (2018) Standard qualification test and acceptance requirements for welding technique of stainless steel

JSA JIS Z 3841 (2018) Standard qualification test and acceptance requirements for semi-automatic

welding technique

NATIONAL ELEVATOR INDUSTRY, INC. (NEII)

NEII-1

(2000; R thru 2017) Building  
Transportation Standards and Guidelines,  
including the Performance Standards Matrix  
for New Elevator Installation

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70

(2023; ERTA 4 2023) National Electrical  
Code

1.2 SUBMITTALS

\*\*\*\*\*

NOTE: Review Submittal Description (SD) definitions in Section 01 33 00 SUBMITTAL PROCEDURES and edit the following list, and corresponding submittal items in the text, to reflect only the submittals required for the project. The Guide Specification technical editors have classified those items that require Government approval, due to their complexity or criticality, with a "G." Generally, other submittal items can be reviewed by the Contractor's Quality Control System. Only add a "G" to an item if the submittal is sufficiently important or complex in context of the project.

For Army projects, fill in the empty brackets following the "G" classification, with a code of up to three characters to indicate the approving authority. Codes for Army projects using the Resident Management System (RMS) are: "AE" for Architect-Engineer; "DO" for District Office (Engineering Division or other organization in the District Office); "AO" for Area Office; "RO" for Resident Office; and "PO" for Project Office. Codes following the "G" typically are not used for Navy and Air Force projects.

The "S" classification indicates submittals required as proof of compliance for sustainability Guiding Principles Validation or Third Party Certification and as described in Section 01 33 00 SUBMITTAL PROCEDURES.

Choose the first bracketed item for Navy and Air Force projects, or choose the second bracketed item for Army projects.

\*\*\*\*\*

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are [for Contractor Quality Control approval.][for information only. When used, a code following the "G" classification identifies the office that will review the submittal for the Government.] Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

- Elevator System; G[, [\_\_\_\_\_]]
- Elevator Component Assemblies; G[, [\_\_\_\_\_]]
- Elevator Machine; G[, [\_\_\_\_\_]]
- Elevator Controller; G[, [\_\_\_\_\_]]
- Wiring Diagrams; G[, [\_\_\_\_\_]]

SD-03 Product Data

\*\*\*\*\*  
**NOTE: For Army projects, delete the bracketed items. For Navy projects, keep the bracketed items.**  
\*\*\*\*\*

- Elevator and Accessories[; G[, [\_\_\_\_\_]]]
- Elevator Components[; G[, [\_\_\_\_\_]]]
- Data Sheets[; G[, [\_\_\_\_\_]]]
- Elevator Microprocessor Controller; G[, [\_\_\_\_\_]]

SD-05 Design Data

- Emergency Power Systems
- Heat Loads
- Reaction Loads

SD-07 Certificates

- Warranty
- Endorsement Letter
- Welders' Qualifications

SD-10 Operation and Maintenance Data

- Elevator, Data Package 4; G[, [\_\_\_\_\_]]
- Maintenance Control Program (MCP); G[, [\_\_\_\_\_]]

1.2.1 Shop Drawing Requirements

\*\*\*\*\*  
**NOTE: Designer must confirm electrical disconnects are correctly located in accordance with UFC 3-490-06 section 6-1.2 and HVAC units are correctly located in accordance with UFC 3-490-06 section 5-1.2.**  
\*\*\*\*\*

Provide assembly and arrangement of elevators, accessories, and **elevator component assemblies**. Show location of **elevator machine** in elevator machine room (MR) or machinery space (MS). Show location of **elevator controller** in elevator machine room or elevator control room (CR). Provide details for materials and equipment, including but not limited to operating and signal fixtures, doors, door and car frames, car enclosure, controllers, motors, guide rails and brackets, layout of hoistway in plan and elevation, and other layout information and clearance dimensions.

#### 1.2.2 Product Data Requirements

Provide manufacturers' product data for all **elevator components**, including but not limited to the following: elevator controller, hoist machine and drive motor, design counterbalance, hoist ropes and shackles, overspeed governor, emergency braking system, car and hall fixture buttons and switches, cab, machine room, control room, and machinery space communication devices, door operator, door protection system, and car and counterweight roller guides and buffers. For **data sheets**, provide document identification number or bulletin number, published or copyrighted prior to the date of contract bid opening. Provide controller manufacturer's published procedures for performance of each and all testing.

#### 1.2.3 Design Data

##### 1.2.3.1 Reaction Loads

Provide calculations by registered professional engineer or 1 Kyu Kenchikushi (1st Class Qualified Architect) for **reaction loads** imposed on building by elevator system. Calculations must comply with **ASCE 7-16** and **ASME A17.1/CSA B44**

##### 1.2.3.2 Heat Loads

Provide calculations from elevator manufacturer, or by registered professional engineer, for total anticipated **heat loads** generated by all of the elevator equipment.

##### 1.2.3.3 Emergency Power Systems

\*\*\*\*\*  
**NOTE: All elevators must be provided with an emergency or auxiliary power system to operate the elevator in case the normal power supply fails. The auxiliary power operating system will, upon loss of regular power run to the next available landing, open the doors, and be removed from service. When normal power is re-established, the elevator must be capable to automatically returned to normal use.**  
\*\*\*\*\*

Where the facility does have an emergency power system, confirm the elevators that will be connected to the emergency power system. Confirm the complete emergency power system and sequence of operation for all elevators, including elevator sequential operation and operation of the elevator lobby manual selection switch. Provide wiring diagrams for building emergency power interface with elevator controls. For elevators not supplied by an emergency power system, provide manufacturers' product

data for auxiliary power systems.

#### 1.2.4 Welders' Requirements

Comply with Japan Welding Engineering Society Certifications [JSA JIS Z 3801](#), [JSA JIS Z 3821](#), and [JSA JIS Z 3841](#). Include certified copies of field welders' qualifications. List welders' names with corresponding code marks to identify each welder's welding work.

#### 1.2.5 Maintenance Control Program (MCP)

For each elevator, prepare and provide a written Maintenance Control Program (MCP) that complies with [ASME A17.1/CSA B44](#) Section 8.6, including written documentation that details the test procedures for each and every test that is required to be performed by [ASME A17.1/CSA B44](#). Assemble all MCP documentation, and supporting technical attachments, in a single MCP package and provide in both electronic and hard copy. Assemble entire hard copy MCP in 3-ring binders. For each elevator provided, the MCP must include only documentation and instruction that apply to the elevator specified.

For each elevator, provide an additional, separate binder that includes all maintenance, repair, replacement, call back, and other records required by [ASME A17.1/CSA B44](#). The records binder must be kept in the elevator mechanical room, maintained by elevator maintenance and service personnel, and be available at all times to authorized personnel. Provide detailed information regarding emergency service procedures and elevator installation company personnel contact information.

### 1.3 QUALITY ASSURANCE

#### 1.3.1 Qualification

Provide a designed and engineered elevator system by an elevator contractor regularly engaged in the installation of elevator systems. Provide elevator components manufactured by companies regularly engaged in the manufacture of elevator components. Utilize only licensed and certified elevator personnel for the installation, adjusting, testing, and servicing of the elevators.

##### 1.3.1.1 Elevator Contractor's Elevator Technicians

For elevator installations in Japan, perform all elevator related work under the direct guidance of a certified elevator technician with a minimum of 3 years of experience in the installation of elevator systems of the type and complexity specified in the contract documents. Provide an [endorsement letter](#) from the elevator manufacturer, certifying that the elevator specialist is qualified.

#### 1.3.2 Manufacturers' Technical Support

Provide elevator components from manufacturers that provide online and live telephone elevator technical support to any elevator installation, service, and maintenance contractor. Provide elevator components from manufacturers that guarantee accessibility to all replacement and repair parts and components to any elevator installation, service, and maintenance contractor.

### 1.3.3 Operation and Maintenance Data

Assemble all shop drawing and product data material into O&M Data Packages in accordance with Article SUBMITTALS. Provide two complete O&M Data Packages in hard copy and two complete electronic O&M data packages on separate CDs, in PDF format. Provide all O&M Data Packages to Contracting Officer. Include controller diagnostic documentation and software as required under Article CONTROL EQUIPMENT.

### 1.3.4 Wiring Diagrams

Provide complete **wiring diagrams** and sequence of operations, which show electrical connections and functions of elevator systems. Provide one set (279 mm by 432 mm 11 inch by 17 inch minimum size) of wiring diagrams, with individual sheets laminated in plastic and assembled in binder, to be stored in the machine room or control room cabinet. Provide one additional hard copy set and two complete electronic sets on separate CDs, in PDF format. Provide all wiring diagram sets to the Contracting Officer. Coded diagrams are not acceptable unless fully identified.

### 1.3.5 Machine Room/Control Room Cabinet

For storage of O&M Data Packages and Wiring Diagrams, provide lockable (padlock hasp device) on a metal cabinet with a minimum size of 508 mm W by 305 mm D by 762 mm H 20 inch W by 12 inch D by 30 inch H. Cabinet must be sized large enough to accommodate all O&M Data and hardware required in paragraphs OPERATION AND MAINTENANCE DATA and WIRING DIAGRAMS. Secure cabinet to machine room or control room wall.

## 1.4 NEW INSTALLATION SERVICE

\*\*\*\*\*  
**NOTE: Use Bi-weekly option for hospitals and other high use facilities.**  
\*\*\*\*\*

Provide elevator **warranty** service in accordance with the manufacturer's maintenance plan, warranty requirements, and applicable safety codes, for a period of 12 months after the date of acceptance by Contracting Officer. Perform this work during regular working hours. Provide supplies and parts to keep elevator system in operation. Perform service only by factory trained personnel. Provide [Monthly][Bi-weekly] services to include repairs, adjustments, greasing, oiling, and cleaning. Provide service log in elevator machine room or control room cabinet and update [Monthly][Bi-weekly], throughout the one-year warranty period.

\*\*\*\*\*  
**NOTE: One hour emergency service below is standard; only use 2 hour for remote locations.**  
\*\*\*\*\*

Provide 24-hour emergency service, with [1 hour][2 hour] on-site response time, during this period without additional cost to the Government.

### 1.4.1 Periodic Elevator Certification Inspection and Testing

Provide elevator mechanic to support [NAVFAC ]QEI Certified Elevator Inspector in the periodic 6-month and the annual Category 1 elevator certification inspection and testing. Perform Category 1 inspection and

testing no greater than 30 days prior to the end of the warranty period. Perform all elevator certification testing in the presence of QEI Certified Elevator Inspector.

In conjunction with the testing noted above, test systems for Emergency Power Operation, Earthquake Emergency Operation, and Hospital Emergency Commandeering Service Operation, as applicable. Schedule so that testing does not interfere with building operations.

#### 1.5 MAINTENANCE

Submit Operation and Maintenance Manuals in accordance with Sections 01 78 23 OPERATION AND MAINTENANCE DATA and 01 78 24.00 20 FACILITY DATA WORKBOOK (FDW).

#### 1.6 FIRE PROTECTION SYSTEM

\*\*\*\*\*  
**NOTE: Confirm that sections listed throughout this article are part of project. Add or delete sections as needed for project.**  
\*\*\*\*\*

Coordinate interface between building fire protection system and elevator controls.

Additional fire protection requirements are located in:[ Section 28 31 60 INTERIOR FIRE ALARM SYSTEM, NON-ADDRESSABLE;][ Section 28 31 66 INTERIOR FIRE ALARM AND MASS NOTIFICATION SYSTEM, NON-ADDRESSABLE;][ Section 28 31 70 INTERIOR FIRE ALARM SYSTEM, ADDRESSABLE;][ Section 28 31 76 INTERIOR FIRE ALARM AND MASS NOTIFICATION SYSTEM, ADDRESSABLE;][ Section 28 31 32 FIRE ALARM REPORTING SYSTEM, DIGITAL COMMUNICATOR TYPE;][ Section 21 13 13 WET PIPE SPRINKLER SYSTEMS, FIRE PROTECTION;] [\_\_\_\_\_] and Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM.

##### 1.6.1 Fire Alarm Initiating Devices

Fire alarm initiating devices are specified in [Section 28 31 60 INTERIOR FIRE ALARM SYSTEM, NON-ADDRESSABLE ][Section 28 31 66 INTERIOR FIRE ALARM AND MASS NOTIFICATION SYSTEM, NON-ADDRESSABLE ][Section 28 31 70 INTERIOR FIRE ALARM SYSTEM, ADDRESSABLE ][Section 28 31 76 INTERIOR FIRE ALARM AND MASS NOTIFICATION SYSTEM, ADDRESSABLE ][\_\_\_\_\_] , including conduit and wiring from each detector to fire protection addressable modules in elevator machine room or control room.

##### 1.6.2 Fire Sprinklers

Provide fire sprinklers in accordance with all applicable safety codes and with [Section 21 13 13 WET PIPE SPRINKLER SYSTEMS, FIRE PROTECTION][\_\_\_\_\_]. Provide shutoff valve, check valve, and non-adjustable, zero time-delay flow switch, in each sprinkler line immediately outside of each machine room, control room, and hoistway, as applicable. Provide inspectors' test valve for periodic testing of flow switch and shunt trip disconnect.

Pipe sprinkler piping serving these spaces in a series manner with no laterals. Locate inspectors' test connection at the end of pipe runs such that operation of the test connection will purge air from system piping.

### 1.6.3 Shunt Trip Disconnect

See Table 2.1 Item #5.

## PART 2 PRODUCTS

### 2.1 ELEVATOR DESCRIPTION

Provide elevator system that complies with JSA JIS A 4307, JSA JIS A 4302, ASME A17.1/CSA B44, Table 2.1, and additional requirements specified herein. Provide elevator system that meets or exceeds the NEII-1 Ride Quality Performance Standards Matrix (RQPSM).

TABLE 2		
ITEM #	ITEM	UNITED STATES CRITERIA REFERENCE
1	Sump Pump	ASME A17.1/CSA B44 2.2.2.5
2	Pit Ladder	ASME A17.1/CSA B44 2.2.4.2.1
3	Stop Switch in Pits	ASME A17.1/CSA B44 2.2.6.2
4	Horizontal Car and Counterweight Clearances	ASME A17.1/CSA B44 2.5
5	Shunt Trip	ASME A17.1/CSA B44 2.8.3.3.2
6	Closing of Hoistway Doors	ASME A17.1/CSA B44 2.11.3
7	Hoistway Door Safety Retainers	ASME A17.1/CSA B44 2.11.11.8
8	Hoistway Access Switch	ASME A17.1/CSA B44 2.12.7
9	Railing and Equipment on Car Enclosure Top	ASME A17.1/CSA B44 2.14.1.7
10	Ventilation	ASME A17.1/CSA B44 2.14.2.3
13	Capacity and Data Plates Governor-Rope Tag Suspension Means Data	ASME A17.1/CSA B44 2.16.3 2.18.5.3 2.20.2.1 2.20.2.2
14	Marking Plate Requirements	ASME A17.1/CSA B44 2.19.3.3
15	Spring Buffer Marking Plate	ASME A17.1/CSA B44 2.22.3

TABLE 2

ITEM #	ITEM	UNITED STATES CRITERIA REFERENCE
16	Oil Buffer Marking Plate	ASME A17.1/CSA B44 2.22.4
17	Symbols	ASME A17.1/CSA B44 2.26.12
18	Emergency Communications	ASME A17.1/CSA B44 2.27.1.1.2
19	Emergency Communications	ASME A17.1/CSA B44 2.27.1.1.6
20	Emergency or Standby Power System	ASME A17.1/CSA B44 2.27.2.1
21	Phase I Emergency Recall Operations	ASME A17.1/CSA B44 2.27.3.2 2.28.3.1.6
22	Phase II Emergency In-Car Operation	ASME A17.1/CSA B44 2.27.3.3
23	Instructions for Operation of Elevators Under Phase I Emergency Recall Operation and Phase II Emergency In-Car Operation	ASME A17.1/CSA B44 2.27.7
24	Retainers for Suspension Members	ASME A17.1/CSA B44 8.4.3.1
25	Operation of Elevators Under Earthquake Emergency Conditions	ASME A17.1/CSA B44 8.4.10
26	Code Data Plate	ASME A17.1/CSA B44 8.9
27	Ground-Fault Circuit Interrupter Protection for Personnel	NFPA 70 620.6
28	Hoistway Door Interlock Wiring	NFPA 70 620.11
29	Wiring Methods	NFPA 70 620.21
30	Voice Messages	Voice messages must be in English

TABLE 2		
ITEM #	ITEM	UNITED STATES CRITERIA REFERENCE
31	Bottom of Car Clearances	ASME A17.1/CSA B44 2.4.16
32	Top of Car Clearances	ASME A17.1/CSA B44 2.4.7.2

2.1.1.1 Elevator Design Parameters

\*\*\*\*\*

**NOTE: Traffic Analysis and Minimum Cab Size**

Perform a traffic analysis and conduct interviews with the facility user to determine number, size, and type of elevators necessary to serve the needs of the facility user. For Army and Navy projects, utilize DoD UFC 3-490-06 to determine Design Type. For minimum elevator speed, specify 200 fpm for 2-4 story, 350 fpm for 5-9 story, and 500 fpm, gearless for 10-or-more story elevators.

Specify gearless traction elevators for all buildings more than 10 stories tall.

Size and capacity configurations are limited to three basic configurations as listed in the subparagraphs below. In the rare case that the listed configurations do not meet project requirements, more extensive project-specific editing will be required.

\*\*\*\*\*

2.1.1.1.1 Elevator No.[\_\_\_\_\_] - Emergency Medical Service Accessibility (EMSA)

\*\*\*\*\*

**NOTE: Emergency Medical Service Accessibility (EMSA):** For each building of two stories or greater, provide at least one elevator with a minimum size and arrangement to accommodate an ambulance stretcher **610 mm by 2134 mm 24 inch by 84 inch**, with not less than **127 mm 5 inch** radius corners, in the open, horizontal, position. For buildings with multiple elevators, an EMSA elevator must be accessible from all locations in the building; otherwise additional elevator(s) shall also be EMSA.

Two size and capacity configurations of elevators will meet this requirement. For standard passenger applications use the **1588 kg 3500 lb** capacity, single speed side slide described in this subparagraph. The larger elevator sized to accommodate pallet-size light freight loading described in next subparagraph below will also meet EMSA requirements.

\*\*\*\*\*

Provide elevator(s) with minimum size and arrangement to accommodate an ambulance stretcher 610 mm by 2134 mm with not less than 127 mm 24-inch by 84-inch with not less than 5-inch radius corners, in the open, horizontal position.

- a. Type: [Geared][Gearless]
- b. Rated load: 1588 kg 3500 lb.
- c. Rated Speed: [60][105][150] m/min [200][350][500] fpm
- d. Car Door Type: Single-speed side slide.
- e. Car Door Opening Width: 107 cm 3 ft.-6 in. minimum, or [\_\_\_\_\_].

2.1.1.2 Elevator No.[\_\_\_\_\_] - Larger Capacity (Pallet-Sized) Loading

\*\*\*\*\*

NOTE: Where a larger capacity elevator is required to accommodate light freight, typically pallet-size loading, use this subparagraph. Elevator shall typically be 4000-4500 lb capacity (may be upwards of 6000 lbs. in rare instances), single speed center opening, 48 inch door opening width, and will typically be deeper than the 3500 lb. EMSA elevator above.

This larger elevator will also meet the EMSA requirements described above.

\*\*\*\*\*

- a. Type: [Geared][Gearless]
- b. Rated load: [1814][2268] kg [4000][4500][\_\_\_\_\_] lb.
- c. Rated Speed: [60][105][150] m/min [200][350][500] fpm
- d. Car Door Type: Single-speed, center opening, horizontally sliding.
- e. Car Door Opening Width: [122 cm][137 cm] [4 ft.-0 in][4 ft.-6 in].

2.1.1.3 Elevator No.[\_\_\_\_\_] - Non-EMSA Elevator

\*\*\*\*\*

NOTE: For smaller elevators where EMSA is not required (covered by one of the two elevator types above), this subparagraph may be used. Typical application would be an elevator bank where one elevator meets EMSA requirements. Elevator shall be 1134 kg 2500 lb capacity, 107 cm 42 inch door opening width, and either side slide or center opening, typically to match other elevators in the bank.

This elevator will not meet EMSA requirements.

\*\*\*\*\*

- a. Type: [Geared][Gearless]
- b. Rated load: 1134 kg 2500 lb.
- c. Rated Speed: [60][105][150] m/min [200][350][500] fpm
- d. Car Door Type: Single speed [side slide][center opening], horizontally sliding.
- e. Car Door Opening Width: 107 cm 3 ft.-6 in. minimum, or [\_\_\_\_\_].

2.1.2 Cab Enclosure and Hoistway Entrance Assemblies

\*\*\*\*\*  
**NOTE: If retaining the first option in sentence below, ensure that finishes are indicated, most likely somewhere on the drawings. In either case, indicate finish colors of elevator materials in finish schedule on drawings.**  
 \*\*\*\*\*

\*\*\*\*\*  
**NOTE: Specify stainless steel doors, side panels and wall trim in hospital elevator cabs.**  
 \*\*\*\*\*

Provide finishes [as indicated.][as listed below:

- a. Floor; [carpet][vinyl composition tile][vinyl sheet tile][\_\_\_\_\_].
- b. Walls; [prefinished steel][laminated plastic] on plywood [stainless steel][\_\_\_\_\_]. Provide each cab wall with equally spaced and equally sized wall panels. All wall panel fasteners must be concealed.  
  
 Wall trim; [prefinished steel][stainless steel][\_\_\_\_\_].  
  
 Accessories; Provide hand rails on full length of back wall and side walls of elevator cab.
- c. Car doors, car door returns, and wall reveals; [prefinished steel panels][stainless steel][\_\_\_\_\_].
- d. Ceilings; [supported][prefinished steel panels][anodized aluminum][egg crate][\_\_\_\_\_].  
  
 Ceiling frame; [prefinished steel][stainless steel][anodized aluminum][\_\_\_\_\_].
- e. Hoistway Entrance Assembly Material and Finishes; [prefinished steel][stainless steel][\_\_\_\_\_].]

2.2 ELEVATOR OPERATION

ASME A17.1/CSA B44, Introduction, Section 3, Definitions.

\*\*\*\*\*  
**NOTE: Choose one of the following four types of elevator operation.**  
 \*\*\*\*\*

[2.2.1 Single, Two-Stop, Automatic Operation

\*\*\*\*\*  
**NOTE: Choose for single elevator serving two landings.**  
\*\*\*\*\*

Provide Single Two-Stop Automatic Operation.

][2.2.2 Selective Collective Automatic Operation

\*\*\*\*\*  
**NOTE: Choose for single elevator serving three or more landings.**  
\*\*\*\*\*

Provide Selective Collective Automatic Operation.

][2.2.3 Duplex Selective Collective Automatic Operation

\*\*\*\*\*  
**NOTE: Choose for two adjacent elevators.**  
\*\*\*\*\*

Provide Duplex Selective Collective Automatic Operation. If a car is taken out of service or fails to respond to a landing call within a predetermined adjustable time limit of approximately 40 to 180 seconds, transfer calls to the other car functioning as a single car Selective Collective elevator until the out-of-service car is returned to the system.

][2.2.4 Group Automatic Operation

\*\*\*\*\*  
**NOTE: Choose for three or more elevators that serve the same elevator lobby.**  
\*\*\*\*\*

Provide Group Automatic Operation. If a car is taken out of service, or fails to respond to a landing call within a predetermined adjustable time limit of approximately 40 to 180 seconds, transfer calls to another car until out-of-service car is returned to the system.

]2.3 SPECIAL OPERATION AND CONTROL

Provide the following special operations and control systems.

2.3.1 Keys for Elevator Key Switches

Provide a minimum of twelve keys per unique cylinder used on all key switches for a single elevator. If there is more than one elevator, additional keys will not be required unless there are additional unique lock cylinders. Provide keys with brass or fiberglass tags marked "PROPERTY OF THE U.S. GOVERNMENT" on one side with function of key or approved code number on the other side.

2.3.2 Firefighters' Emergency Operation (FEO)

\*\*\*\*\*

**NOTE: Coordinate FEO Designated Landing with Fire Protection Designer.**

\*\*\*\*\*

See Table 2.1 Item #22.

#### 2.3.2.1 Firefighters' Emergency Operation (FEO) Key Box

Provide flush mounted, locking, FEO Key Box of a minimum size of 127 mm W by 229 mm H by 38 mm D 5 inch W by 9 inch H by 1.5 inch D. Install at a height of 183 cm 6 feet above floor level and directly above the FEO Phase I key switch. Provide box equipped with lock that uses the FEO K1 key.

#### 2.3.3 Hoistway Access Operation

See Table 2.1 Item #8.

#### 2.3.4 In-Car Inspection Operation

Provide In-Car Inspection Operation.

#### 2.3.5 Independent Service

Provide exposed key-operated switch in car operating panel to enable independent service and simultaneously disable in-car signals and landing-call responses. Provide indicator lights that automatically illuminate during independent service. For duplex or group operation, if one car is removed from group another car will respond to its hall calls.

#### 2.3.6 Selective Door Operation

For elevator with one or more rear openings at same level as front opening, provide full-selective operation with car and door operating buttons clearly marked for front and rear openings, front and rear car button for each such floor, and front and rear "DOOR OPEN" and "DOOR CLOSE" buttons. Only door for which the button was operated opens or closes.

#### [2.3.7 Elevator Emergency Power Operation

\*\*\*\*\*

**NOTE: Electrical design shall identify the elevators to be connected to the building emergency power system. Identify and define the complete emergency power system for all elevators. When using the second bracketed option in either of the next two subparagraphs, edit as required for project-specific requirements.**

**For any elevator that is not included in the building emergency power operation, utilize paragraph ELEVATOR AUXILIARY POWER OPERATING SYSTEM.**

\*\*\*\*\*

Provide elevator emergency power operation for[ all elevators][ elevator 1,2,and 3]. Coordinate power supply and control wiring to accomplish initiation and operation of elevators on emergency power.

]2.3.8 Elevator Auxiliary Power Operating System

See Table 2.1 Item #20.

]2.3.9 Hospital Emergency Commandeering Service (HECS)

\*\*\*\*\*  
**NOTE: Only keep this HECS paragraph for hospital elevators or for projects in which this operation is specifically requested by the building owner or facility user.**  
\*\*\*\*\*

Provide Hospital Emergency Commandeering Service.

]2.4 ELEVATOR DRIVE MACHINE, HOIST MOTOR, AND DRIVE MOTOR

Provide elevator drive machine, hoist motor, and motor drive system that is designed to be installed in an elevator machine room (MR) or an elevator machinery space (MS). The elevator machine, motor, and drive configuration and installation design must be mechanically and electrically interchangeable with a minimum of two other elevator manufacturer's drive machines that are readily available in the elevator industry. Paint or finish ferrous surfaces with a minimum of one coat of manufacturer applied rust- inhibiting paint.

Design the elevator drive system so that the hoist motor amperage does not exceed the motor data tag full load amperage in any operating condition, exclusive of acceleration and deceleration. Provide elevator hoist motor that is designed with Class F insulation and rated for 120 starts/hr. Design the elevator drive system to limit Total Harmonic Distortion to a maximum of 5 percent. No single harmonic may exceed 3 percent. Provide an elevator drive machine designed for and provided with stranded steel wire rope for elevator suspension and counterbalance. The minimum acceptable diameter of suspension and counterweight ropes is 9.52 mm 3/8 inches. Aramid fiber ropes, coated steel ropes, and non-circular coated steel belts may not be used for elevator suspension or counterbalance. The elevator drive machine must be equipped with machine manufacturer's designed and installed standard means for the manual release of the driving-machine brake.

2.4.1 Manufacturer's Technical Support

Provide an elevator drive machine from a manufacturer that provides technical support for installation, adjustment, service, and maintenance of the drive system. The support must be identified as available to any licensed elevator contractor.

All drive system related components and parts must be available for purchase and use by any licensed elevator contractor; "exchange-only" provisions for the purchase of spare parts are not acceptable.

2.4.2 Ascending Car Overspeed and Unintended Car Movement Protection

Provide elevator Ascending Car Overspeed and Unintended Car Movement Protection means that is designed to act directly upon, and apply a retarding force to, the elevator suspension ropes. In addition to the requirements of ASME A17.1/CSA B44, the means must be designed to detect and stop movement of the elevator suspension ropes that occurs as a result

of loss of traction between the suspension ropes and the elevator machine drive sheave.

## 2.5 CONTROL EQUIPMENT

Enclose all elevator control equipment in factory-primed and baked-enamel coated sheet-metal cabinets with ventilation louvers and removable or hinged doors. Mount cabinets at a height of 254 mm 10 inches above machine room or control room finish floor.

### 2.5.1 Motor Control Equipment

Provide variable voltage with silicon controlled rectifier (SCR) or Variable-Frequency Variable Voltage (VVF) alternating current (ac) drive control.

#### 2.5.1.1 Electrical Isolation Protection

Provide individual isolation transformers and individual choke reactors for each individual hoist motor. Provide filtering to maintain harmonic distortion below IEEE C62.41 standards as measured at the elevator machine room or control room disconnect.

### 2.5.2 Elevator Microprocessor Controller

For each individual elevator controller, and for each group controller, provide a microprocessor controller that complies with the following paragraphs. Provide controller(s) package that includes all hardware and software required for the installation, maintenance, and service of the elevator, in its' entirety. Provide verification of technical support service that the controller manufacturer provides to any licensed elevator installation, service, and maintenance company. All components and parts must be available for purchase and installation and use by any licensed elevator contractor; "exchange-only" provisions for the purchase of spare parts are not acceptable. Provide verification of telephone and internet based technical support service that the elevator controller manufacturer provides to any licensed elevator installation, service, and maintenance company at an industry competitive price. The service must include live telephone based technical support for installation, adjustment, maintenance, and troubleshooting of the elevator controller and related elevator components. The service must be available during standard working hours.

Provide an elevator controller that is designed to automatically reestablish normal elevator operation following any temporary loss of power, regardless of duration.

## 2.6 OPERATING PANELS, SIGNAL FIXTURES, AND COMMUNICATIONS CABINETS

For all panels and fixtures, provide identical and uniform fixture design, material, finish, and components for all elevators. For all panels and fixtures, legibly and indelibly identify all buttons and all operating positions for each device. Use engraving and backfilling, or photo etching, for button and switch designations. Do not use attached signs. Provide elevator manufacturers' standard grade for all key switches unless otherwise specified. All illuminating panels and fixture components must utilize LED lighting for energy efficiency.

### 2.6.1 Car and Hall Buttons

For all cab and landing fixture buttons, provide industry-standard, vandal resistant push buttons. Buttons must be minimum 19 mm 3/4 inch diameter, stainless steel, with illuminating LED halo.

### 2.6.2 Passenger Car-Operating Panel

\*\*\*\*\*  
**NOTE: Choose "two" Car Operating Panels for high traffic passenger elevators in hospital buildings and office buildings. Choose "one" for elevator system where traffic is moderate such as in barracks, warehouses, clinics or shops.**  
\*\*\*\*\*

Provide each car with[ one][ two] car operating panel[s] that contain[s] operation controls and communication devices. Provide exposed, flush mounted buttons for the controls identified in subparagraph PASSENGER CONTROLS. Provide a lockable service cabinet for the controls listed in subparagraph SERVICE CONTROLS. Use engraving and backfilling or photo etching for button and switch designations. Do not use attached signs.

#### 2.6.2.1 Passenger Controls

In addition to ASME A17.1/CSA B44 requirements, provide the following operating controls, identified as indicated:

- a. LED illuminating car-call buttons identified to correspond to landings served by the elevator.
- b. "DOOR OPEN" and "DOOR CLOSE" buttons. For front and rear openings at the same floor, include the identification "F" and "R" for each opening.
- c. Red, illuminating "ALARM" button.
- d. Key-operated "Independent Service" switch.
- e. "Help" communication device to include communication between elevator cab and elevator machine room or control room.
- [ f. Key-operated "HOSPITAL EMERGENCY COMMANDEERING SERVICE" switch.

#### 2.6.2.2 Service Controls

In addition to ASME A17.1/CSA B44 requirements, provide the following operating controls, identified as indicated:

- a. Provide a key-operated, three-position switch for "In car Inspection Operation" and "Hoistway Access". The center switch position will provide normal, automatic operation.
- b. "Car Light" switch.
- c. "Car Fan" switch with two speed settings identified.
- d. See Table 2.1 Item #28.

#### 2.6.2.3 Certificate Window

Provide a minimum 102 mm wide by 152 mm high 4 inch wide by 6 inch high certificate window for elevator inspection certificate. Locate window in the Service Controls door of the Car Operating Panel.

#### 2.6.2.4 Emergency Signaling Devices

Provide an audible signaling device, operable from the Car Operating Panel button marked "ALARM". The audible signaling device must have a sound pressure rating between 80 and 90 dBA at 3 meters 10 ft. Provide battery backup power capable of operating the audible signaling device for at least 1 hour.

#### 2.6.3 Elevator In-Car Position Indicators

For all elevators, provide illuminating LED position indicator in the Car Operating Panel.

#### 2.6.4 Elevator In-Car Direction Indicators

For 2-stop elevator installations, provide visual direction indicators and audible car arrival signal in the elevator car door jamb, in accordance with ABA Standards. Visual indicators must be visible from the hall call fixture.

#### 2.6.5 Hall Call Landing Fixtures

Provide a hall call fixture adjacent to each elevator. Provide a single push-button for terminal landings and dual push-buttons, up and down, at intermediate landings.

##### 2.6.5.1 Designated Landing Hall Call Fixture

###### 2.6.5.1.1 Location of COMMUNICATION MEANS FAILURE (CMF) Visual Signal

When required by ASME A17.1/CSA B44, provide an elevator CMF audible and illuminating signal, and reset switch, in the FEO Designated Landing hall call fixture. Mount the signal and reset switch at a minimum of 178 mm 7 inches above the "UP" hall call button.

###### 2.6.5.1.2 COMMUNICATION MEANS FAILURE (CMF) Visual and Audible Signal Operation

Provide a CMF visual and audible signal system that conforms to ASME A17.1/CSA B44. Provide continuous verification of operability of the telephone line and immediate activation of audible and visual signals when verification means determines that the telephone line is not functioning. Provide illumination of visual signal at 1 second intervals. Provide a minimum of 65 dBA audible signal at 30 second intervals.

###### 2.6.5.1.3 Firefighters' Emergency Operation Phase I Switch and Visual Signal

See Table 2.1 Item #21.

## 2.6.6 Elevator Car Position and Direction Indicators and Car Arrival Signal

For elevator installations with three or more stops, provide a separate hall landing fixture that includes the visual elevator position indicator, visual direction indicators, and audible car arrival signal, in accordance with ABA Standards.

## 2.6.7 Designated Landing Elevator Identification Fixture

For duplex and group elevator installations, provide a separate elevator identification fixture for each elevator, with identification engraved and backfilled with a contrasting color. Number elevators from left to right, as seen during primary approach from building main entrance to elevator lobby. For multiple elevator groups, begin numbering with group that is closest to the building main entrance.

## 2.6.8 Emergency or Standby Power

When emergency or standby power is provided for elevator operation, provide an elevator emergency power visual indicator that conforms to [ASME A17.1/CSA B44](#). Locate the visual signal in the Firefighters Emergency Operation fixture for each simplex elevator and for each elevator group. When an emergency power selector switch is required, provide switch in a separate, flush mounted fixture located at the designated level, in view of all elevator entrances.

## 2.7 CAR DOOR EQUIPMENT

### 2.7.1 Car Door Operator

Provide elevator door operator equipment and circuitry that is designed and installed as discreet communication. Serial communication must not be used for this system.

### 2.7.2 Infra-red Curtain Unit

Provide Infra-red Curtain Unit (ICU) with multiple infra-red beams that protect to the full height and width of the door opening. Provide door nudging operation.

## 2.8 PASSENGER ELEVATOR GUIDES, PLATFORM, AND ENCLOSURE

### 2.8.1 Roller Guides

Provide coil-spring loaded roller guide assemblies in adjustable mountings on each side of car and counterweight frames in accurate alignment at top and bottom of frames.

### 2.8.2 Car Enclosure Wall Panels, Return Panels, Doors, Entrance Columns, and Transom

Provide 14 Gauge minimum [prefinished steel][stainless steel] cab wall panels and entrance components. Use same material and finish for all hoistway and car entrance assemblies. Apply sound-deadening material on exterior of all cab wall panels.

### 2.8.3 Car Enclosure Top

Provide reinforced, 12 gauge minimum steel car enclosure top. Provide hinged emergency exit with lock sized in accordance with JSA JIS A 4307. Locate emergency exit hinge towards the rear of the elevator cab. Design and configure the elevator cab interior ceiling to provide convenient and unobstructed access to, and use of, emergency exit from inside the elevator cab.

### 2.8.4 Car Door

Provide 16 gauge minimum [prefinished steel][stainless steel] car doors of sandwich construction with flush surfaces on car and landing sides. Provide a minimum of 2 door guide assemblies per door panel, one guide at leading and one at trailing door edge with guides in the sill groove their entire length of travel.

### 2.8.5 Car Entrance Sill

Provide one piece cast nickel silver, stainless steel, or white bronze entrance sill(s). Set sills level and flush with floor finish. Use same material for hoistway and car entrance sills.

### 2.8.6 Cab Finish Floor

Provide cab finish floor with top of finish floor flush with the cab sill.

### 2.8.7 Car Fan

See Table 2.1 Item #10.

### 2.8.8 Car Lighting

Utilize LED lighting for elevator car interior illumination. Provide a minimum of 10 foot-candles, measured at all areas of the car enclosure floor. Provide automatic car lighting operation that will turn off car lights after 3 minutes of inactivity. Car lights must automatically turn on upon actuation of an elevator car or hall call.

### 2.8.9 Car Protection Pads and Hooks

Provide fire retardant, hanging car protection pads that provide protection for all car interior wall panels. Provide permanently installed studs in car that are designed for hanging the car protection pads in the car.

## 2.9 PASSENGER ELEVATOR HOISTWAY DOORS AND ENTRANCES

\*\*\*\*\*

**NOTE: For projects in Japan that require a 1-1/2 hour fire rating, a combination of a 60 minute rated elevator door and a 30 minute fire shutter or fire door is acceptable. Architectural and fire protection drawings and specifications prepared by the designer of record must address the requirement for the additional fire shutter or fire door.**

\*\*\*\*\*

Provide hoistway entrance assemblies with a minimum[ 1 hour][ 1-1/2 hour]

fire rating.[ Elevator doors with a rating of 60 minutes are acceptable provided additional fire shutter or fire door is provided to achieve combined rating required.] Use same material and finish for all hoistway and car entrance assemblies.

#### 2.9.1 Hoistway Entrance Frames

Provide 14 gage minimum [prefinished carbon sheet steel][stainless steel] hoistway entrance frames. Solidly grout uprights of entrance ways to height of 1.5 m 5 feet.

#### 2.9.2 Hoistway Entrance Sills

Provide one-piece cast nickel silver, stainless steel, or white bronze entrance sills. Set top of landing sill flush with top of finish floor. Solidly grout under full length of sill. Use same material for all hoistway and car entrance sills.

#### 2.9.3 Hoistway Entrance Doors

Provide [hollow metal][stainless steel] non-vision construction hoistway entrance doors with flush surfaces on car and landing sides. Provide a minimum of 2 door guide assemblies per door panel, one guide at leading edge and one at trailing edge with guides in the sill groove the entire length of door travel. Use same material and finish for all hoistway and car entrance assemblies.

#### 2.9.4 Hoistway Entrance Door Track Dust Covers

Provide sheet metal hoistway door track dust covers at each landing. Dust covers must cover top and hoistway side of door locks and door roller tracks, and extend the full width of the door track and associated hardware. Dust cover sections will not exceed 1 m 3 feet in length.

### 2.10 HOISTWAY EQUIPMENT

#### 2.10.1 Car and Counterweight Guide Rails and Fastenings

Provide T-section type guide rails for car and counterweight. Paint rail shanks with one coat of black enamel.

#### 2.10.2 Pit Equipment and Support Channels

Provide rail-to-rail pit channels to serve as mounting surface for main guide rails and counterweight guide rails. In addition, pit channels will serve as mounting surfaces for car and counterweight buffers. Method of installation of channels, brackets and buffer mounts will be such that pit waterproofing is not punctured.

#### 2.10.3 Pit "STOP" Switch

See Table 2.1 Item #3.

#### 2.10.4 Traveling Cables

Suspend traveling cables by means of self-tightening webbed devices or internal suspension members.

### 2.10.5 Hoistway Pit Ladder

Provide continuous horizontal rungs for the full height of the pit ladder.

## PART 3 EXECUTION

### 3.1 INSTALLATION

Install in accordance with DOD design criteria, contract specifications, manufacturer's instructions, **NEII-1** Building Transportation Standards and Guidelines, and all applicable building and safety code requirements.

#### 3.1.1 Structural Members and Finish Materials

Do not cut or alter structural members. Do not alter finish materials from manufacturer's original design. Restore any damaged or defaced work to original condition.

#### 3.1.2 Miscellaneous Requirements

Provide recesses, cutouts, slots, holes, patching, grouting, and refinishing to accommodate elevator installation. Use core drilling to drill all new holes in concrete. Finish work to be straight, level, and plumb. During installation, protect machinery and equipment from dirt, water, or mechanical damage. At completion, clean all work and spot paint.

### 3.2 FIELD QUALITY CONTROL

The Contractor will provide and utilize a third-party licensed and certified Qualified Elevator Inspector (QEI) to conduct elevator pre-acceptance inspection and testing. The QEI must perform inspections and witness tests to ensure that the installation conforms to all applicable safety codes and contract requirements. The QEI will be directly employed by the Contractor and independent of the elevator contractor.

Upon completion, the QEI must provide written test data for all **ASME A17.1/CSA B44** Acceptance Tests and written certification that the elevator is complete and ready for final Acceptance Inspection, Testing, and Commissioning.

### 3.3 ACCEPTANCE INSPECTION, TESTING AND COMMISSIONING

When elevator system installation is complete and ready for final inspection, notify Contracting Officer that elevator system is ready for Acceptance Inspection, Testing, and Commissioning. Provide QEI certification specified in Article FIELD QUALITY CONTROL.

\*\*\*\*\*  
**NOTE: For Navy and Marine Corps projects and projects on Navy and Marine Corps bases, use the first bracketed paragraph. Use the second bracketed paragraph for Air Force and Army projects.**  
\*\*\*\*\*

[ The Government will obtain services of Naval Facilities Engineering Systems Command (NAVFAC) QEI Certified Elevator Inspector. NAVFAC QEI will utilize the applicable NAVFAC Elevator Acceptance Inspection Form to record the results of inspection and testing and to identify safety code

and contract deficiencies. Specific values must be provided for all tests required by ASME A17.1/CSA B44, ASME A17.2, and contract documents. Upon completion of inspection and testing, the NAVFAC QEI will sign a copy of the completed forms and provide the signed copy to the Contracting Officer or representative. Within 2 weeks of the inspection, the QEI will also prepare a formal inspection report, including all test results and deficiencies. Upon successful completion of inspection and testing, NAVFAC Certified Elevator Inspector will complete, sign and post form NAVFACENGCOM 9-11014/23(Rev.9-2009), Elevator Inspection Certificate.

] [Contractor will obtain the services of a QEI Certified Elevator Inspector. The QEI must utilize an Elevator Acceptance Inspection Form to record the results of inspection and all testing and to identify safety code and contract deficiencies. Specific values must be provided for all tests required by ASME A17.1/CSA B44, ASME A17.2, and contract documents. Upon completion of inspection and testing, the QEI must sign a copy of the completed forms and provide to the Contracting Officer. Within 2 weeks of the inspection, the QEI must also prepare a formal inspection report, including all test results and deficiencies. Upon successful completion of inspection and testing, the QEI will complete, sign, and provide a certificate of compliance with ASME A17.1/CSA B44.

### ] 3.3.1 Acceptance Inspection Support

Prime and Elevator Contractors must provide inspection support and perform all required tests, in order to demonstrate proper operation of each elevator system and to prove that each system complies with contract requirements and all applicable building and safety codes. Inspection procedures in ASME A17.2 form a part of this inspection and acceptance testing. All inspection and testing must be conducted in the presence of the Qualified Elevator Inspector (QEI).

If the elevator does not comply with all contract and safety code requirements on the initial Acceptance Inspection and Test, the Contractor is responsible for all costs involved with re-inspection and re-testing required as a result of contractor delays and discrepancies discovered during inspection and testing.

### 3.3.2 Testing Materials and Instruments

Provide all testing materials and instruments necessary for Acceptance Inspection, Testing and Commissioning. At a minimum, include calibrated test weights, tachometer, accelerometer, hydraulic pressure gauge, 600-volt megohm meter, volt meter and ammeter, infrared temperature gauge, door pressure gage, dynamometer, and 6 meter 20 foot tape measure.

### 3.3.3 Field Tests

#### 3.3.3.1 Endurance Tests

Test each elevator for a period of 1 hour continuous, automatic operation, with specified rated load in the elevator cab. During the 1 hour test, stop car at each floor, in both directions of travel, and allow automatic door open and close operation. The requirements for Automatic Operation, Rated Speed, Leveling, Temperature Rise and Motor Amperes must be met throughout the duration of the Endurance Test. Restart the 1 hour test period from the beginning, following any shutdown or failure.

#### 3.3.3.2 Speed Tests

Determine actual speed of each elevator, in both directions of travel, with rated load and with no load in elevator car. Make Speed tests at the beginning and at the end of the Endurance test. Determine speed by tachometer reading or accelerometer, excluding accelerating and slow-down zones. Under all conditions, minimum acceptable elevator speed is the Rated speed specified. Maximum acceptable elevator speed is 110 percent of Rated speed.

#### 3.3.3.3 Leveling Tests

Test elevator car leveling operation and provide a leveling accuracy equal to or less than 3 mm 1/8 inch at each floor with no load in car, balanced load in car, and with rated load in car, in both directions of travel. Determine leveling accuracy at the beginning and at the end of the endurance tests.

#### 3.3.3.4 Temperature Rise Tests

Determine temperature rise of elevator drive machine motor during 1-hour full-load test run. Under these conditions, maximum temperature rise must not exceed acceptable temperature rise indicated on manufacturer's data plate. Start test only when equipment is within 5 degrees C of ambient temperature.

#### 3.3.3.5 Balanced Load Test

Place balanced load in the elevator cab, according to the manufacturer's designed counterbalance. Perform electrical and mechanical balanced load tests of car and counterweight.

#### 3.3.3.6 Motor Ampere Tests

At beginning and end of Endurance test, measure and record motor amperage in both directions of travel and in both no-load and rated load conditions.

#### 3.3.3.7 Elevator Performance and Ride Quality Testing

Evaluate elevator performance to ensure compliance with specification requirements related to the NEII-1 Performance Standards Matrix for New Elevator Installations.

-- End of Section --